Quote

Agility#:

Quote#: 668644

Boise Cascade Building Materials Distribution
Boise Structural Solutions

20 Pomerleau St.
Biddeford, Me 04005

Tel: 877-291-5276
Fax: 877-782-0999

Customer: MEWE00 - HILLSIDE LUMBER - ENAP 0067

781 COUNTY ROAD
WESTBROOK, ME04092

Contact: JOE HALL
Email: joe.hall@hillsidelumber.com
Phone: **Fax:**

Job Name: ST LAWRENCE ADDITION/ ED DIP

PORTLAND, ME

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/20/15

Prepared By:	Date Quoted:	Delivery Date:	Last Revised:	Price Protected Until:
SAMANTHA EXT 2761	05/08/2015			**05/15/2015**

ROOF TRUSSES **Designed per: IBC2009/TPI2007 Code.**

PROFILE	LBL	QTY / PLY	OVRALL LGTH / WEIGHT	NET SPAN	PITCH TOP	PITCH BOT	TYPE	SPC	OVERHANG LEFT	OVERHANG RIGHT	CUT	LOADING TLL-TDL-BLL-BDL / Heel Height Left	Heel Height Right	CANTILEVER LEFT	CANTILEVER RIGHT	BRG SIZE LEFT	BRG SIZE RIGHT		
A668644-0001	001	1 / 1	19-04-00 / 79 lbs	19-04-00	5.50	0.00	GESI	24	00-00-00	00-00-00	P	60-10-0-10 Roof Snow=60 / 00-08-05	00-08-05	00-00-00	00-00-00	18-00-00 / **BRG#:**	00-00-00 / 1		
A668644-0002	002	4 / 1	19-04-00 / 76 lbs	18-00-00	5.50	0.00	COMMON	24	00-00-00	00-00-00	P	60-10-0-10 Roof Snow=60 / 00-08-05	00-08-05	00-08-00	00-08-00	00-05-08 / **BRG#:**	00-05-08 / 2		
A668644-0003	003	1 / 1	23-04-00 / 100 lbs	23-04-00	5.50	0.00	GESI	24	00-00-00	00-00-00	P	60-10-0-10 Roof Snow=60 / 00-08-05	00-08-05	00-00-00	00-00-00	02-05-08 / **BRG#:**	00-05-08 / 3		
A668644-0004	004	8 / 1	23-04-00 / 148 lbs	22-00-00	5.50	4.00	SCISSOR	24	00-00-00	00-00-00	P	60-10-0-10 Roof Snow=60 / 00-08-05	00-08-05	00-08-00	00-08-00	00-05-08 / **BRG#:**	00-05-08 / 2		

Total Weight: 1667 lbs

Report Date/Time: 5/20/2015 2:11:59 PM

Agility#: Quote#: 668644

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/20/15

Boise Cascade
Building Materials
Distribution
Boise Structural Solutions

20 Pomerleau St.
Biddeford, Me 04005

Tel: 877-291-5276
Fax: 877-782-0999

Customer: MEWE00 - HILLSIDE LUMBER - ENAP 0067

781 COUNTY ROAD
WESTBROOK, ME04092

Contact: JOE HALL
Email: joe.hall@hillsidelumber.com
Phone: **Fax:**

Job Name: ST LAWRENCE ADDITION/ ED DIP

PORTLAND, ME

Prepared By:	Date Quoted:	Delivery Date:	Last Revised:	Price Protected Until:
SAMANTHA EXT 2761	05/08/2015			05/15/2015

Quote Source: BSS PLAN TAKE OFF

Job Notes To Customer:

8-5/16" FASCIA, 12" OVERWALL HEIGHT

Plan Date:

Special Instructions For Design:

SUB-TOTAL:	
DISCOUNTS:	
GRAND TOTAL:	

****** QUANTITY CHANGES WILL EFFECT PRICES* MAXIMUM UNLOADING TIME IS 1 HOUR***
TRUSS SYMBOLS CONCEPTUAL ONLY NOT FOR DESIGN
****** ALL TRUSSES ARE CUSTOM BUILT AND CANNOT BE RETURNED**
UNLESS SPECIFICALLY NOTED ON THIS QUOTE PRICE DOES NOT INCLUDE:
TREATED LUMBER, SEALED LAYOUTS, BRACING AND / OR HANDLING DRAWINGS
METAL HARDWARE, ENGINEERED LUMBER (LVL,I-JOISTS, ETC.)

SPRING IS HERE, POSTED ROADS ARE HISTORY.

LEAD TIMES QUICK