



SIGN SPECIFICATIONS

SIGN

ID FACE

Substrate .150" colorless solar-grade polycarbonate silk screened on second surface

Background (White) Formed 1.500"

Field (Violet and white) Embossed .750" from background

Bell

Outside surface (Magenta, violet, and white) Embossed 1.000" from field

Inside surface (bottom) (Violet) Debossed .750" from outside

Clapper (Yellow only) Embossed .375" from inside

Wordmark (Violet) Embossed .500"

APPENDAGE FACE

Substrate .118" colorless solar-grade polycarbonate silk-screened or sprayed on second surface

Background (Violet) Formed 1.500"

Letters (Yellow or White) Flat

CABINET

(Painted violet) Extruded aluminum

ILLUMINATION

Internal, with T12/Dsgn50/HO fluorescent lamps

SUPPORT

6" steel square tube

Base painted to match Sherwin Williams 6122 Camelback - Textured finish

ELECTRICAL SPECIFICATIONS

AREA

47.9 sq ft

CURRENT

7.00 amps

CIRCUIT REQUIRED

(1) 20 amp

FACE COLORS (SILK-SCREENED)

- Spraylat Violet L8-7917
- Spraylat Magenta L8-7837
- Spraylat Yellow L8-7836
- Spraylat White 801

EXPOSED METAL COLOR (PAINTED)

- To match Spraylat Violet L8-7917