ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALLS NORTH	WALLS SOUTH	WALLS EAST	WALLS WEST	CEILING MATERIAL	CEILING HEIGHT	ROOM NUMBER	REMARKS
101	OPEN OFFICE	CPT–1	RB–1	PTD–4,5*	PTD–1	PTD–1	PTD–1	ACT–1	–	101	*REFER TO WALL FINISH PLAN ID102 FOR DISTRIBUTION OF ACCENT COLORS
102	VESTIBULE	WOM–1	PT–2	–	–	–	–	ACT–1		102	
103	VESTIBULE	WOM–1	PT–2	–	–	–	–	ACT–1		103	
104	NETWORK	SEALED CONC.	RB–2	PTD–1	PTD–1	PTD–1	PTD–1	ACT–1		104	
106	SPRINKLER	SEALED CONC.	RB–2	PTD–1	PTD–1	PTD–1	PTD–1	ACT–1		106	
111	WORK/PAGINATION	CPT–2	RB–1	PTD–1	PTD–1	PTD–1	PTD–3	ACT–1		111	
112	DIRECTOR	CPT–2	RB–1	PTD–1	PTD–1	PTD–1	PTD–3	ACT–1		112	
113	VP	CPT–2	RB–1	PTD–1	PTD–1	PTD–1	PTD–3	ACT–1		113	
114	VIDEO CONFERENCE	CPT–2	RB–1	PTD–1	PTD–1	PTD–1	PTD–3	ACT–1		114	
115	STORAGE	CPT–2	RB–1	PTD–1	PTD–3	PTD–1	PTD–1	ACT–1		115	
116	MEETING	CPT–2	RB–1	PTD–1	PTD–3	PTD–1	PTD–1	ACT–1		116	
117	MEETING	CPT–2	RB–1	PTD–1	PTD–3	PTD–1	PTD–1	ACT–1		117	
118	INT. WORK/PAGINATION	CPT–2	RB–1	PTD–1	PTD–1	PTD–3	PTD–1	ACT–1		118	
121	FUTURE TRAINING	–	–	–	–	–	–	–		121	
122	FUTURE TRAINING	–	–	–	–	–	–	–		122	
131	BREAK	CPT–1/BBT–1	RB–2	PTD–6	PTD–6	PTD–6	PTD–6	ACT–1		131	
132	MEN	PT–1/CPT–1	PT–2/RB–1	PTD–1/PT*	PTD–1	PTD–1	PTD–1	ACT–1		132	*PT–1 ON WET WALLS, FULL HEIGHT.
133	WOMEN	PT–1/CPT–1	PT–2/RB–1	PTD–1/PT*	PTD–1	PTD–1	PTD–1	ACT–1		133	*PT–1 ON WET WALLS, FULL HEIGHT.
134	FIRST AID	BBT–1	RB–2	PTD–1	PTD–1	PTD–1	PTD–1	ACT–1		134	
135	LACT.	BBT–1	RB–2	PTD–1	PTD–1	PTD–1	PTD–1	ACT–1		135	
136	HOUSEKEEPING	SEALED CONC.	RB–2	PTD–1/FRP	PTD–1	PTD–1/FRP	PTD–1	ACT–1		136	
137	COATS	CPT–1	RB–1	PTD–1	PTD–1	PTD–1	PTD–1	ACT–1		137	
138	CLOSET	PT–1	PT–2	PTD–1	PTD–1	PTD–1	PTD–1	ACT–1		137	
201	STAIR	RS–2	–	PTD–1	–	PTD–1	PTD–1	ACT–1		201	
202	STORAGE	SEALED CONC.	RB–2	PTD–1	PTD–1	PTD–1	PTD–1			202	

GENERAL FINISH NOTES:

1. WOOD SPECIES TO BE CLEAR FINISH WHITE BIRCH, PLAIN SLICED.
2. SILLS TO BE CLEAR FINISH WHITE BIRCH, PLAIN SLICED.
3. REFER TO ID101 FOR FLOOR FINISH PLAN AND LEGEND.
4. REFER TO ID102 FOR WALL FINISH PLAN AND LEGEND.
5. REFER TO RCP FOR CEILING HEIGHTS AND SOFFIT LOCATIONS.
6. REFER TO INTERIOR ELEVATIONS ON SHEET AE201 FOR ADDITIONAL INFORMATION REGARDING LOCATION OF EQUIPMENT, ACCESSORIES, INTERIOR FINISHES, AND WALL TILE PATTERNS.

FINISH ABBREVIATIONS:

ACT	ACOUSTICAL CEILING TILE
CPT	CARPET TILE
FRP	FIBER REINFORCED PANEL
GT	GLASS WALL TILE
GWB	GYPSUM WALLBOARD
LVT	LUXURY VINYL TILE
PLAM	PLASTIC LAMINATE
PT	PORCELAIN TILE
PTD	PAINTED
RB	RESILIENT BASE
RS	RESILIENT SHEET
RCP	REFLECTED CEILING PLAN
SSM	SOLID SURFACE MATERIAL
WOM	WALK OFF MAT

FINISH LEGEND:

*NOTE: PRODUCTS IDENTIFIED BELOW ARE BASIS OF DESIGN. WHERE MATERIAL SPECIFICATIONS ALLOW ALTERNATE MANUFACTURERS/PRODUCTS, THE ARCHITECT RESERVES THE RIGHT TO REQUIRE CUSTOM COLOR MATCHING OR TO REJECT AN ALTERNATE WHEN IT IS DETERMINED BY THE ARCHITECT TO BE INCONSISTENT WITH THE DESIGN INTENT.

ACOUSTICAL CEILING TILE:
ACT–1 ARMSTRONG DUNE 1774, 24"X24", 15/16" ANGLED TEGULAR EDGE WITH 15/16" GRID.

BIOBASED TILE:
BBT–1 ARMSTRONG STRIATIONS, COLOR T3609, MALTED MILK, 12"x24".

CARPET TILE:
CPT–1 SHAW, DIFFUSE #59575. 24" SQUARE TILES W/ ECOWORX BACKING. COLOR: MOVEMENT #75481. INSTALLATION METHOD: ASHLAR.
CPT–2 SHAW, DISPERSE #59576. 24" SQUARE TILES W/ ECOWORX BACKING. COLOR: MOVEMENT #75481. INSTALLATION METHOD: ASHLAR.

LUXURY VINYL TILE:
LVT–1 TANDUS–CENTIVA, CONTOUR SERIES, COLOR: ANTIQUE TOWER. SIZE: 6"X36". SQUARE EDGE, SAWN FINISH. UNIDIRECTIONAL INSTALLATION, STAGGER JOINTS.

PLASTIC LAMINATE:
PLAM–1 FORMICA, PECAN WOODLINE 5883–58 (BREAK ROOM CABINETS AND WINDOW SILLS).

PORCELAIN TILE:
PT–1 CROSSVILLE, BASALT 12"X24". INSTALL WITH JOINTS STAGGERED AT 1/3 INTERVALS, PERPENDICULAR TO PATH OF TRAVEL. COLOR: CALDERA.
PT–2 CROSSVILLE, BASALT 6"Hx12" COVE BASE. COLOR: CALDERA.

PAINT:
PTD–1 BENJAMIN MOORE, SPANISH OLIVE 1509 (FIELD)
PTD–2 BENJAMIN MOORE, ANTIQUE PEWTER 1560 (TRIM)
PTD–3 BENJAMIN MOORE, SCENIC DRIVE 697
PTD–4 BENJAMIN MOORE, CALICO BLUE 707
PTD–5 BENJAMIN MOORE, GREAT BARRINGTON GREEN HC–122
PTD–6 BENJAMIN MOORE, SWEET VIBRATIONS 391

RESILIENT BASE:
RB–1 JOHNSONITE RUBBER WALL BASE, STRAIGHT TOELESS BASE FOR CARPET, 4"H. COLOR: 29–MOON ROCK.
RB–2 JOHNSONITE RUBBER WALL BASE, TRADITIONAL W/TOE , 4"H. COLOR: 29–MOON ROCK.

RESILIENT SHEET
RS–1 JOHNSONITE, OPTIMA. 6'–6" ROLL. COLOR: MALT
RS–2 NORA SATURA, STAIR TREADS/RISERS. COLOR: CALLISTO #5107

SOLID SURFACE MATERIAL:
SSM–1 CORIAN, SORREL (BREAK ROOM)
SSM–2 CORIAN, GREEN TEA (RESTROOMS)

WALK OFF MAT:
WOM–1 TANDUS, ABRASIVE ACTION II, COLOR: WINTER GRAY 19103. 24"X24" TILES, DIRECT GLUE.

REV.	DESCRIPTION	DATE
1	CONFORMED SET	4–21–15
0	ISSUED FOR CONSTRUCTION	3–3–15

CONFORMED SET
4–21–15

CURRENT ISSUE STATUS:

LICENSED ARCHITECT JANET L. JOHANSEN #1991 STATE OF MAINE 4-21-15

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772–3846
fax. (207) 772–1070
www.smrtinc.com

L.L. BEAN
CHESHIRE BUILDING RENOVATIONS
PORTLAND, MAINE

FINISH SCHEDULE

SHEET TITLE:

SCALE:	AS NOTED	DATE:	3–3–15
PROJECT MANAGER:	JLH	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:			
A/E OF RECORD:	JLH	SHEET No.	ID601
SMRT CAD FILE:	ID601–14199		
PROJECT No.	14199–00		

© COPYRIGHT 2013 SMRT INC.