A1 FLOOR PLAN

1/8" = 1'-0"

NOTES:

1. SEE SHEET GI001 FOR LEGEND, ABBREVIATIONS AND PROJECT GENERAL NOTES.
2. PATCH ALL EXISTING WALL SURFACES TO REMAIN. PREPARE EXISTING SURFACES FOR NEW FINISHES. RE: FINISH PLAN AND FINISH SCHEDULE.
3. REPAIR EXISTING VAPOR BARRIER AT LOCATIONS ON EXTERIOR WALL WHERE DAMAGED HAS OCCURRED. MAINTAIN CONTINUITY OF EXISTING BARRIER AT EXISTING WALLS.

KEYED NOTES:

1. PLAM OVER EXISTING PLAM SILL, SEE DETAIL F9/AE511.
2. BLACK OUT FILM ON EXISTING GLAZING.
3. DECORATIVE COLUMN COVER. (1'-4" O.D.), RE: SPECS.
4. NOT USED.
5. PROVIDE (1) LAYER OF 5/8" TYPE X GWB TO EXISTING WALL STUDS. HOLD BOTTOM EDGE OF GWB 1/2" AFF, TYP.
6. DOOR OPERATOR PUSH PLATE.
7. NOT USED.
8. PATCH EXISTING POLY VAPOR BARRIER OVER EXISTING BATT INSULATION. INSTALL POLY VAPOR BARRIER TO MATCH EXISTING AT LOCATIONS WHERE BATT INSULATION IS EXPOSED. MAINTAIN CONTINUITY OF BARRIER, TYP.,
9. PROVIDE FIBERGLASS REINFORCED PANELS (FRP), TO 4'-0" ABOVE MOP SINK.
10. EXTEND EXISTING PARTITION WALL TO 12'-6" AFF.

EQUIPMENT/ACCESSORY SCHEDULE

TAG	DESCRIPTION	
A	SOAP DISPENSER	O/C
B	PAPER TOWEL DISPENSER	O/C
C	TOILET TISSUE DISPENSER	O/C
D	ELECTRIC HAND DRYER	O/C
E	SANITARY NAPKIN DISPOSAL UNIT	C/C
F	18" VERTICAL GRAB BAR	C/C
G	36" GRAB BAR	C/C
H	42" GRAB BAR	C/C
I	NOT USED	–
J	ROBE/COAT HOOK	C/C
K	MIRROR	C/C
L	REFRIGERATOR	O/C
M	MICROWAVE	O/O
N	VENDING MACHINE	O/V
O	PRINTER	O/O
P	ICE MAKER	O/C
Q	TOASTER	O/O
R	COFFEE MAKER	O/C
S	WHITE BOARD	O/C
T	TV	O/C
U	TRASH/RECYCLE BIN	O/O
V	WATER COOLER	O/O

C/C – CONTRACTOR FURNISHED/CONTRACTOR INSTALLED
O/C – OWNER FURNISHED/CONTRACTOR INSTALLED
O/O – OWNER FURNISHED/OWNER INSTALLED
O/V – OWNER FURNISHED/VENDOR INSTALLED
(CONTRACTOR SHALL PROVIDE BLOCKING IN WALL)

REV.	DESCRIPTION	DATE
2	CONFORMED SET	4-21-15
1	ISSUED FOR ADDENDUM 1	3-11-15
0	ISSUED FOR CONSTRUCTION	3-3-15

CONFORMED SET
4-21-15

CURRENT ISSUE STATUS:

PROJECT NORTH

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

L.L. BEAN
CHESHIRE BUILDING RENOVATIONS
PORTLAND, MAINE

FIRST FLOOR PLAN

SHEET TITLE:

SCALE:	1/8"=1'-0"	DATE:	3-3-15
PROJECT MANAGER:	JLH	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:	CAH		
A/E OF RECORD:	JLH	SHEET No.	AE101
SMRT CAD FILE:	AE101-14199		
PROJECT No.	14199-00		

© COPYRIGHT 2013 SMRT INC.