NOTE:

1. SEE SHEET E-001 FOR LEGEND AND GENERAL NOTES.

KEYED NOTE:

1. POWER POLE'S PROVIDED BY FURNITURE CONTRACTOR AND SHOWN FOR REFERENCE ONLY.
2. CONNECT EXISTING SPRINKLER TAMPER AND FLOW SWITCHES INTO NEW FIRE ALARM SYSTEM. PROVIDE ADDRESSABLE INTERFACE MODULES AS NECESSARY.
3. SEE ELEVATION K1-A ON AE201 FOR AV SYSTEM BACKBOX MOUNTING LOCATIONS.
4. EXTRON INPUT BOX, COORDINATE BOX AND CONDUIT REQUIREMENTS WITH LL BEAN.
5. EXTRON CONTROL BOX, COORDINATE BOX AND CONDUIT REQUIREMENTS WITH LL BEAN.
6. ARLINGTON BOX, COORDINATE BOX AND CONDUIT REQUIREMENTS WITH LL BEAN.
7. PROVIDE BACK BOX FOR AIPHONE VIDEO INTERCOM DEVICE. COORDINATE WITH LL BEAN'S FOR REQUIREMENTS.
8. NOT USED.
9. VERIFY FINAL LOCATION WITH PORTLAND FIRE DEPARTMENT.

REV.	DESCRIPTION	DATE
2	CONFORMED SET	4-21-15
1	ISSUED FOR ADDENDUM 2	3-18-15
0	ISSUED FOR CONSTRUCTION	3-3-15

CONFORMED SET
4-21-15

CURRENT ISSUE STATUS:

PROJECT NORTH

STATE OF MAINE WILLIAM R. HERP No. 7680 LICENSED PROFESSIONAL ENGINEER 4/21/15

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

L.L. BEAN
CHESHIRE BUILDING RENOVATIONS
PORTLAND, MAINE

ELECTRICAL SYSTEMS PLAN

SHEET TITLE:

SCALE:	1/8"=1'-0"	DATE:	3-3-15
PROJECT MANAGER:	JLH	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:	RBB		
A/E OF RECORD:	WRH	SHEET No.	EY101
SMRT CAD FILE:	EY101-14199		
PROJECT No.	14199-00		

© COPYRIGHT 2013 SMRT INC.

A1 FLOOR PLAN

1/8" = 1'-0"