FLOOR FINISH NOTES:

1. FOR ADDITIONAL INFORMATION REGARDING FINISHES, INCLUDING DEFINITION OF ABBREVIATIONS, RE: ID601.
2. NEW FLOORING TO RUN BENEATH NEW CASEWORK.
3. ALL FLOORING TRANSITION STRIPS ARE TO BE LOCATED DIRECTLY BELOW DOOR WHEN IN CLOSED POSITION. FLOORING ON EITHER SIDE SHOULD NOT BE SEEN WHEN DOOR IS CLOSED.
4. CONTRACTOR TO PERFORM ALKALINITY AND ADHESION TESTS (ASTM F 1869 & 2170) RECOMMENDED BY FLOORING MANUFACTURER FOR EACH TYPE OF FLOORING. PROCEED WITH INSTALLATION ONLY AFTER SUBSTRATES PASS TESTING. VERIFY RESULTS WITH FLOORING MANUFACTURER.
5. PORCELAIN TILE PT-1 SHALL BE INSTALLED STAGGERED AT 1/3 POINT INTERVALS.
6. CPT-1 AND CPT-2 INSTALLATION METHOD: ASHLAR
7. PROVIDE JOHNSONITE TRANSITION STRIP CTA-29-HT AT LOCATIONS WHERE FLOORING TRANSITIONS FROM CARPET TO RESILIENT.
8. PROVIDE JOHNSONITE TRANSITION STRIP CTA-29-M AT LOCATIONS WHERE FLOORING TRANSITIONS FROM CARPET TO LVT.
9. PROVIDE JOHNSONITE TRANSITION STRIP CTA-29-L AT LOCATIONS WHERE FLOORING TRANSITIONS FROM CARPET TO PORCELAIN TILE.

LEGEND:

- CPT-1
- CPT-2
- BBT-1 BIOBASED TILE
- PT-1
- RS-1
- RS-2
- WOM-1
- CS-1 SEALED CONCRETE

REV.	DESCRIPTION	DATE
2	CONFORMED SET	4-21-15
1	ISSUED FOR POST-BID ADD 1	3-30-15
0	ISSUED FOR CONSTRUCTION	3-3-15

CONFORMED SET
4-21-15

CURRENT ISSUE STATUS:

PROJECT NORTH

LICENSED ARCHITECT JANET L. HANSEN #1991 STATE OF MAINE 4-21-15

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

L.L. BEAN
CHESHIRE BUILDING RENOVATIONS
PORTLAND, MAINE

FLOOR FINISH PLAN

SHEET TITLE:

SCALE:	1/8"=1'-0"	DATE:	3-3-15
PROJECT MANAGER:	JLH	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:			
A/E OF RECORD:	JLH	SHEET No.	ID101
SMRT CAD FILE:	ID101-14199		
PROJECT No.	14199-00		

© COPYRIGHT 2013 SMRT INC.

A1 | FLOOR FINISH PLAN
1/8" = 1'-0"