## NOTES:

1. SEE SHEET GI001 FOR LEGEND, ABBREVIATIONS AND PROJECT GENERAL NOTES.
2. SEE SHEET AE501 FOR TYP. ROOF DETAILS.

## KEYED NOTES:

1. INFILL ROOF OPENING W/ METAL ROOF DECK AT LOCATIONS WHERE MECHANICAL UNITS WERE REMOVED. MATCH EXISTING. REFER TO STRUCTURAL. REFER TO MECHANICAL FOR LOCATIONS AND EXTENTS OF EQUIPMENT REMOVALS. PATCH ROOFING SYSTEM TO MATCH EXISTING. MATCH EXISTING INSULATION THICKNESS AND EXISTING SLOPE TO DRAIN CONDITION.
2. PATCH TO MATCH EXISTING ROOFING SYSTEM AT NEW EQUIPMENT INSTALLATIONS. SEE TYPICAL ROOF DETAILS.
3. FUTURE.
4. NOT USED.
5. WALK-WAY PAD, RE: SPECS.
6. EXISTING EXHAUST FAN TO BE REMOVED AND EXISTING ROOF CURB TO REMAIN IN PLACE. PROVIDE NEW CAP ON EXISTING CURB AND INSULATE. RE: PLUMBING FOR INSTALLATION OF CURB MOUNTED SPIGOT.

| REV. | DESCRIPTION | DATE |
|---|---|---|
| 1 | CONFORMED SET | 4-21-15 |
| 0 | ISSUED FOR CONSTRUCTION | 3-3-15 |

CONFORMED SET
4-21-15

CURRENT ISSUE STATUS:

PROJECT NORTH

LICENSED ARCHITECT JANET L. HANSEN #1991 STATE OF MAINE 4-21-15

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

L.L. BEAN
CHESHIRE BUILDING RENOVATIONS
PORTLAND, MAINE

ROOF PLAN

SHEET TITLE:

| | | | |
|---|---|---|---|
| SCALE: | 1/8"=1'-0" | DATE: | 3-3-15 |
| PROJECT MANAGER: | JLH | GRAPHIC SCALE: | 0" 1" |
| JOB CAP/DRAWN: | CAH | | |
| A/E OF RECORD: | JLH | SHEET No. | |
| SMRT CAD FILE: | AE121-14199 | | AE121 |
| PROJECT No. | 14199-00 | | |

© COPYRIGHT 2013 SMRT INC.

A1 ROOF PLAN
1/8" = 1'-0"