L.L. BEAN

PORTLAND, MAINE

CHESHIRE BUILDING RENOVATIONS

ABBREVIATIONS

A/C	AIR CONDITIONING
ACPLAS	ACOUSTICAL PLASTER
ACT	ACOUSTIC CEILING TILE
AFF	ABOVE FINISHED FLOOR
AP	ACCESS PANEL
A/V	AUDIO/VISUAL
BCE	BOTTOM CHORD EXTENSION
BD	BOARD
BLP	BORROWED LIGHT PANEL
BO	BOTTOM OF
BOF	BOTTOM OF FOOTING
BOS	BOTTOM OF STEEL
BS	BOTH SIDES
BSE	BSBRICK SHELF ELEVATION
C	CHANNEL
CB	CATCH BASIN; CHALKBOARD
C/C	CONTRACTOR FURNISHED/ CONTRACTOR INSTALLED
CFM	CUBIC FEET PER MINUTE
CG	CORNER GUARD
CJ	CONTROL JOINT, CONSTRUCTION JOINT
CLG	CEILING
CMU	CONCRETE MASONRY UNIT
CT	CERAMIC TILE
CUH	CABINET UNIT HEATER
DF	DRINKING FOUNTAIN
DR	DISPLAY RAIL
DW	DISHWASHER
(E)	EXISTING
EF	EXHAUST FAN; EACH FACE
EJ	EXPANSION JOINT
EPDM	ETHYLENE PROPYLENE DIENE MONOMER
EW	EACH WAY
EWC	ELECTRIC WATER COOLER
FB	FLAT BAR
FBO	FURNISHED BY OTHERS
FCO	FLOOR CLEAN-OUT
FD	FLOOR DRAIN
FE	FIRE EXTINGUISHER
FF	FINISHED FLOOR; FAR FACE
FO	FRAMED OPENING
FS	FAR SIDE
GB	GRAB BAR
GC	GENERAL CONTRACTOR
GDT	GYPSUM DROP-IN TILE
GWB	GYPSUM WALL BOARD
H	HORIZONTAL
HC	HANDICAPPED; HOLLOW CORE
HM	HOLLOW METAL
HRU	HEAT RECOVERY UNIT
HT	HEIGHT
H&V	HEATING AND VENTILATING
HVAC	HEATING, VENTILATING AND AIR CONDITIONING
IF	INSIDE FACE
IJ	ISOLATION JOINT
INV	INVERT
L	ANGLE
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
LP	LIGHTING PANEL; LIQUIFIED PROPANE
MB	MARKER BOARD
MDO	MEDIUM DENSITY OVERLAY
MO	MASONRY OPENING
MR	MOISTURE-RESISTANT
MUA	MAKE-UP AIR
N	NOSING
NIC	NOT IN CONTRACT
NS	NEAR SIDE
NTS	NOT TO SCALE
O/C	OWNER FURNISHED/ CONTRACTOR INSTALLED
OC	ON CENTER
OF	OUTSIDE FACE
OH	OVERHEAD
O/O	OWNER FURNISHED/OWNER INSTALLED
PA	PUBLIC ADDRESS
PAF	POWDER-ACTUATED FASTENER
PL	PLATE
PLAM	PLASTIC LAMINATE
PLF	POUNDS PER LINEAR FOOT
PP	POWER PANEL
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	PRESSURE-TREATED
PVC	POLYVINYL CHLORIDE
PWP	PLASCORE WALL PANEL
R	RISER; RADIUS
RB	RESILIENT BASE
RD	ROOF DRAIN
RO	ROUGH OPENING
RR	RUB-RAIL
SACT	SUSPENDED ACOUSTIC TILE CEILING
SBO	IBC SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
SC	SOLID CORE
SCHD	SCHEDULE
SF	SQUARE FOOT; SUPPLY FAN
SK	SHEAR KEY
SN	SANITARY NAPKIN (DISPENSER)
SP	SPACES
SS	STAINLESS STEEL
T	TREAD
TB	TACKBOARD
T&B	TOP AND BOTTOM
TBM	TEMPORARY BENCHMARK
TCE	TOP CHORD EXTENSION
TJ	TIE JOIST
TO	TOP OF
TOC	TOP OF CONCRETE
TOF	TOP OF FOOTING
TOM	TOP OF MASONRY
TOP	TOP OF PIER
TOS	TOP OF STEEL; TOP OF SLAB
TOW	TOP OF WALL
TP	TOILET PAPER (DISPENSER)
UH	UNIT HEATER
UNO	UNLESS NOTED OTHERWISE
V	VENT PIPE; VERTICAL
VB	VAPOR BARRIER
VCT	VINYL COMPOSITION TILE
VP	VISION PANEL
VTR	VENT THROUGH THE ROOF
W/	WITH
WC	WATER CLOSET
WF	WIDE FLANGE
WH	WATER HEATER
W/O	WITHOUT
WP	WORKING POINT
WS	WEB STIFFENER
WWF	WELDED WIRE FABRIC

LEGEND

GRID LOCATION	TITLE
SCALE	REFERENCE SHEET

DRAWING TITLE BLOCK

A1 / A101 — BUILDING SECTION

A1 / A101 — WALL SECTION

A1 / A101 — DETAIL

LEVEL LINE

2 — REVISION

A — WINDOW TYPE

A501 — DOOR NUMBER

LOBBY / A153 — ROOM NAME / ROOM NUMBER

G14 / A200 — INTERIOR ELEVATION

15 — WALL TYPE

S — BACKER ROD AND SEALANT

A1 / A101 — EXTERIOR ELEVATION

DRAWING LIST:

GENERAL

GI001 COVER SHEET

ARCHITECTURAL

A-001 LIFE SAFETY PLAN, MOUNTING HEIGHTS AND PARTITION TYPES

AD101 FIRST FLOOR DEMOLITION PLAN
AD102 SECOND FLOOR DEMOLITION PLAN
AD121 ROOF DEMOLITION PLAN

AE101 FIRST FLOOR PLAN
AE102 SECOND FLOOR PLAN

AE111 REFLECTED CEILING PLANS

AE121 ROOF PLAN

AE201 INTERIOR ELEVATIONS

AE301 WALL SECTIONS

AE401 ENLARGED PLAN

AE501 DETAILS

AE511 CASEWORK DETAILS

AE601 DOOR AND WINDOW INFORMATION

INTERIORS

ID101 FIRST FLOOR FINISH PLAN
ID102 FIRST FLOOR WALL FINISH PLAN
ID601 FINISH SCHEDULE

STRUCTURAL

SF101 ROOF FRAMING PLAN
SF501 FRAMING SECTIONS AND DETAILS

FIRE PROTECTION

FP101 FIRE PROTECTION PLAN

MECHANICAL

M-001 HVAC LEGEND AND ABBREVIATIONS

MD101 HVAC FIRST FLOOR DEMOLITION PLAN

MH101 HVAC FIRST FLOOR PLAN
MH102 HVAC MEZZANINE AND ROOF PLANS

M-501 HVAC DETAILS
M-601 HVAC SCHEDULES
M-651 HVAC SCHEMATICS

PLUMBING

PL001 PLUMBING LEGEND AND ABBREVIATIONS

PD101 PLUMBING DWV PIPING DEMOLITION PLAN
PD102 PLUMBING SUPPLY PIPING DEMOLITION PLAN

PL101 FIRST FLOOR PLUMBING PLAN
PL102 ROOF PLUMBING PLAN

PL501 PLUMBING DETAILS
PL601 PLUMBING SCHEDULES

ELECTRICAL

E-001 ELECTRICAL LEGEND AND GENERAL NOTES

ED101 ELECTRICAL DEMOLITION PLAN

EL101 ELECTRICAL LIGHTING PLAN

EP101 ELECTRICAL POWER PLAN

EY101 ELECTRICAL SYSTEMS PLAN

E-102 SECOND FLOOR AND PART PLANS
E-103 ELECTRICAL ROOF PLAN

E-601 ELECTRICAL SCHEDULES

E-651 ELECTRICAL ONE-LINE, FIRE ALARM RISER, AND LIGHTING CONTROL DIAGRAMS

GENERAL NOTES:

1. DO NOT SCALE THE DRAWINGS.
2. FIELD VERIFY ALL DIMENSIONS AND LAYOUT PRIOR TO PROCEEDING WITH WORK. NOTIFY ARCHITECT IN WRITING OF ANY DISCREPANCIES OR INCONSISTENCIES. FAILURE TO REPORT ANY DISCREPANCIES WITHIN THESE CONSTRUCTION DOCUMENTS TO THE ARCHITECT WILL NOT BE GROUNDS FOR ADDITIONAL COST OR CHANGE ORDERS.
3. "PROVIDE" MEANS "FURNISH AND INSTALL".
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MATERIALS, AND WORKMANSHIP IN ACCORDANCE WITH FEDERAL, STATE, CITY AND LOCAL BUILDING CODES AND THEIR REQUIREMENTS.
5. THE CONTRACTOR AND ALL TRADES SHALL NOTE REQUIREMENTS OF "GENERAL NOTES" ON ALL SHEETS.
6. REFER TO LARGE SCALE PLANS FOR PARTITION TYPES AND DIMENSIONS IN AREAS WHICH ARE DETAILED AT A LARGER SCALE.
7. EACH TRADE TO PROVIDE SMOKE OR FIRE SEALANT AT PENETRATIONS AS REQUIRED FOR WALL TYPE. ALL SEALANT, FIRE STOPPING, AND SMOKE STOPPING ASSEMBLIES SHALL BE U.L. RATED.
8. DIMENSIONS CENTERLINE OF INTERIOR STUD PARTITIONS, EXTERIOR STUD PARTITIONS ARE DIMENSIONED TO EXTERIOR FACE OF STUD, UNLESS INDICATED OTHERWISE.
9. REFER TO ALL CONSTRUCTION DOCUMENTS FOR REQUIREMENTS WHICH MAY AFFECT THE WORK AND COORDINATE SAME.
10. REFERENCE DETAILS AND ENLARGED PLANS FOR ADDITIONAL DIMENSIONAL INFORMATION.
11. DOOR JAMBS SHALL BE LOCATED 6" FROM CORNER IN STUD PARTITIONS, UNLESS INDICATED OTHERWISE.
12. EACH TRADE TO COORDINATE WITH FURNITURE AND EQUIPMENT LOCATED ON PLANS.
13. ALL NEW PENETRATIONS WITHIN EXISTING WALLS SHALL BE PATCHED AND SEALED AS REQUIRED BY APPLICABLE FIRE AND ACOUSTIC RATINGS.
14. PROVIDE BLOCKING IN WALLS AS REQUIRED WHERE CASEWORK, FURNITURE, SHELVES, HANDRAILS, AND/OR OTHER MISC. EQUIPMENT AND FIXTURES ARE LOCATED.

REV.	DESCRIPTION	DATE
2	CONFORMED SET	4-21-15
1	ISSUED FOR ADDENDUM 1	3-11-15
0	ISSUED FOR CONSTRUCTION	3-3-15

CONFORMED SET
4-21-15

CURRENT ISSUE STATUS:

PROJECT NORTH

LICENSED ARCHITECT JANET L. HANSEN #1991 STATE OF MAINE 4-21-15

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING

144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

L.L. BEAN
CHESHIRE BUILDING RENOVATIONS
PORTLAND, MAINE

COVER SHEET

SHEET TITLE:

SCALE:	AS NOTED	DATE:	3-3-15
PROJECT MANAGER:	JLH	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:	CAH		
A/E OF RECORD:	JLH	SHEET No.	GI001
SMRT CAD FILE:	GI001-14199		
PROJECT No.	14199-00		

© COPYRIGHT 2013 SMRT INC.

Approved as to Form and Content
Corporation Counsel
Date: 05/09/15