K1 HEAD DETAIL

3" = 1'-0"

K5 JAMB DETAIL

3" = 1'-0"

G1 DOOR TYPES

1/4" = 1'-0"

G6 FRAME TYPES

1/4" = 1'-0"

DOOR SCHEDULE

DOOR NUMBER	ROOM NAME	DOOR SIZE	DOOR MATERIAL	DOOR ELEVATION	GLAZING	FRAME MATERIAL	FRAME ELEVATION	FRAME HEAD	FRAME JAMB	FRAME SILL	HWS	FIRE RATING (MIN.)	DOOR NUMBER	NOTES
101A	OPEN OFFICE	3'-6"-7'-0"X1-3/4"	INS. HM	HG	INS./TEMP	HM	1 (4)	–	–	–	1		101A	(3)(4)(6)
101B	OPEN OFFICE	3'-8"-7'-0"X1-3/4"	INS. HM	HG	INS./TEMP	HM	1 (4)	–	–	–	1		101B	(3)(4)(6)
102A	VESTIBULE	(2)3'-0"-7'-0"X1-3/4"	ALUM	FG	INS./TEMP	ALUM	–	–	–	–	10		102A	(3)
102C	VESTIBULE	3'-0"-7'-0"X1-3/4"	HM	FG	INS./TEMP	HM	–	–	–	–	11		102C	(1)
103A	VESTIBULE	(2)3'-0"-7'-0"X1-3/4"	ALUM	FG	INS./TEMP	ALUM	–	–	–	–	2		103A	(2)(3)
103B	VESTIBULE	3'-0"-7'-0"X1-3/4"	HM	FG	INS./TEMP	HM	–	–	–	–	3		103B	(1)(2)
104	NETWORK	3'-0"-7'-0"X1-3/4"	WD	F	–	HM	1	K1/AE601	K5/AE601	–	4		104	
106	SPRINKLER	3'-0"-7'-0"X1-3/4"	WD	F	–	EXISTING	–	–	–	–	5		106	
111	WORK/PAGINATION	3'-0"-7'-0"X1-3/4"	WD	NG	TEMP	HM	1	K1/AE601	K5/AE601	–	6		111	
112	DIRECTOR	3'-0"-7'-0"X1-3/4"	WD	FG	TEMP	HM	1	K1/AE601	K5/AE601	–	6		112	
113	VP	3'-0"-7'-0"X1-3/4"	WD	FG	TEMP	HM	1	K1/AE601	K5/AE601	–	6		113	
114	VIDEO CONFERENCE	3'-0"-7'-0"X1-3/4"	WD	FG	TEMP	HM	1	K1/AE601	K5/AE601	–	6		114	
115	STORAGE	3'-0"-7'-0"X1-3/4"	WD	FG	TEMP	HM	1	K1/AE601	K5/AE601	–	6		115	
116	MEETING	3'-0"-7'-0"X1-3/4"	WD	FG	TEMP	HM	1	K1/AE601	K5/AE601	–	6		116	
117	MEETING	3'-0"-7'-0"X1-3/4"	WD	FG	TEMP	HM	1	K1/AE601	K5/AE601	–	6		117	
118	INT. WORK/PAGINATION	3'-0"-7'-0"X1-3/4"	WD	NG	TEMP	HM	1	K1/AE601	K5/AE601	–	6		118	
121	FUTURE TRAINING	3'-0"-7'-0"X1-3/4"	WD	NG	TEMP	HM	1	K1/AE601(5)	K5/AE601(5)	–	6		121	
122	FUTURE TRAINING	3'-0"-7'-0"X1-3/4"	WD	NG	TEMP	HM	1	K1/AE601(5)	K5/AE601(5)	–	6		122	
134	FIRST AID	3'-0"-7'-0"X1-3/4"	WD	F	–	HM	1	K1/AE601	K5/AE601	–	7		134	
135	LACT.	3'-0"-7'-0"X1-3/4"	WD	F	–	HM	1	K1/AE601	K5/AE601	–	8		135	
136	HSKP	3'-0"-7'-0"X1-3/4"	WD	F	–	HM	1	K1/AE601	K5/AE601	–	4		136	
138	CLOSET	2'-8"-6'-8"X1-3/4"	WD	F	–	HM	1	K1/AE601	K5/AE601	–	4		138	
141A	LOADING DOCK	(E)(2)2'-10"-7'-0"X1-3/4"	EXISTING	–	–	EXISTING	EXISTING	–	–	–	9		141A	
141B	LOADING DOCK	(E)3'-0"-7'-0"X1-3/4"	EXISTING	–	–	EXISTING	EXISTING	–	–	–	EXISTING		141B	(1)(3)
141C	LOADING DOCK	(E)8' OVERHEAD DOOR	EXISTING	–	–	EXISTING	EXISTING	–	–	–	EXISTING		141C	
141D	LOADING DOCK	(E)8' OVERHEAD DOOR	EXISTING	–	–	EXISTING	EXISTING	–	–	–	EXISTING		141D	
202	SHELL SPACE	(E)3'-6"-7'-0"X1-3/4"	EXISTING	–	–	EXISTING	EXISTING	–	–	–	EXISTING		202	
203	ELECTRICAL	(E)3'-6"-7'-0"X1-3/4"	EXISTING	–	–	EXISTING	EXISTING	–	–	–	EXISTING		203	

(1) CARD READER.
(2) DOOR OPERATOR.
(3) PREP DOOR FRAME FOR OWNER INSTALLED DOOR POSITION INDICATOR.
(4) VERIFY EXISTING OPENING SIZE.
(5) FUTURE 5/8" GWB ON INTERIOR FACE OF WALL PARTITION.
(6) GROUT HM FRAME SOLID.

HARDWARE SETS

HWS 1
HINGES, CONCEALED ROD EXIT DEVICE, LOCK CYLINDER, CLOSER, WEATHERSTRIPPING, THRESHOLD.

HWS 2
HINGES, CONCEALED ROD EXIT DEVICE WITH KEY OUTSIDE UNLOCKS/LOCKS, OFFSET PULL, CLOSER, WEATHERSTRIPPING, THRESHOLD.

HWS 3
CONCEALED ROD EXIT DEVICE W/ ELECTRIC STRIKE, CLOSER. DOOR TO HAVE CARD ACCESS DEVICE INSTALLED BY OWNER.

HWS 4
HINGES, LOCKSET (STORAGE FUNCTION), STOP.

HWS 5
HINGES, LOCKSET (STORAGE FUNCTION).

HWS-6
HINGES, LOCKSET (OFFICE FUNCTION), STOP.

HWS 7
HINGES, PASSAGE SET, STOP.

HWS 8
HINGES, LOCKSET (PRIVACY FUNCTION), STOP.

HWS 9
REPLACE EXISTING KNOB STYLE HARDWARE WITH LEVER STYLE HARDWARE ON ACTIVE LEAF AND REPLACE WEATHERSTRIPPING. INSTALL MAG LOCK. (DOOR TO HAVE CARD ACCESS DEVICE INSTALLED BY OWNER.

HWS 10
HINGES, CONCEALED ROD EXIT DEVICE W/ KEY OUTSIDE UNLOCK/LOCKS, AUTOMATIC DOOR OPERATOR ON TAGGED LEAF, CLOSER ON OTHER LEAF, WEATHERSTIPPING, THRESHOLD.

HWS-11
HINGES, CONCEALED ROD EXIT DEVICE WITH ELECTRIC STRIKE, AUTOMATIC DOOR OPERATOR. (DOOR TO HAVE CARD ACCESS DEVICE INSTALLED BY OWNER.)

GENERAL DOOR NOTES

1. SEE SPECIFICATIONS FOR HARDWARE SET DESCRIPTIONS.
2. SEE TITLE SHEET G001 FOR STANDARD ABBREVIATIONS.
3. ALL SWINGING DOORS TO BE 1-3/4" THICK (U.N.O.).
4. ALL DOORS SHALL BE 3/4" UNDERCUT (TYPICAL) EXCEPT WHEN THERE IS A BOTTOM FRAME OR SILL THRESHOLD OR SPECIFICALLY NOTED OTHERWISE.
5. ALL DOORS WITH BOTTOM FRAMES OR SILL THRESHOLDS SHALL HAVE MANUFACTURERS RECOMMENDED STANDARD UNDERCUT.
6. GLAZING NOTED ON DOOR SCHEDULE IS FOR THE DOOR AND SIDELIGHTS IN THE FRAME (TYPICAL). RE: SPECS FOR GLAZING TYPES.
7. REFER TO FLOOR PLAN FOR NOTES ON EXISTING DOORS.

DOOR ABBREVIATIONS

AL/ALUM	ALUMINUM	S/S	STAINLESS STEEL
HM	HOLLOW METAL	STL	STEEL
LAM	LAMINATED	TEMP	TEMPERED GLASS
INS	INSULATED	WIRE	WIRE GLASS
WD	WOOD	REL	RELOCATE(D)

NOTE:
RE: SPECIFICATIONS FOR GLAZING TYPES

A1 WINDOW TYPES

1/4" = 1'-0"

REV.	DESCRIPTION	DATE
3	CONFORMED SET	4-21-15
2	ISSUED FOR POST-BID ADD 1	3-30-15
1	ISSUED FOR ADDENDUM 1	3-11-15
0	ISSUED FOR CONSTRUCTION	3-3-15

CONFORMED SET
4-21-15

CURRENT ISSUE STATUS:

LICENSED ARCHITECT JANET L. HANSEN #1991 STATE OF MAINE 4-21-15

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

L.L. BEAN
CHESHIRE BUILDING RENOVATIONS
PORTLAND, MAINE

DOOR AND WINDOW INFORMATION

SHEET TITLE:

SCALE:	AS NOTED	DATE:	3-3-15
PROJECT MANAGER:	JLH	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:	CAH		
A/E OF RECORD:	JLH	SHEET No.	AE601
SMRT CAD FILE:	AE601-14199		
PROJECT No.	14199-00		

© COPYRIGHT 2013 SMRT INC.

Approved as to Form and Content
Date: 06/09/15