NOTE:

1. SEE SHEET M-001 FOR LEGEND AND ABBREVIATIONS.

KEYED NOTES:

1. REMOVE ALL EXISTING SUPPLY, RETURN AND EXHAUST DUCTWORK AND ASSOCIATED HANGERS, AND SUPPORTS COMPLETE.
2. REMOVE SPLIT SYSTEM AIR CONDITIONING UNIT / GAS FURNACE AND ASSOCIATED PIPING, HANGERS AND SUPPORTS COMPLETE.
3. REMOVE DUCTLESS SPLIT SYSTEM AIR CONDITIONING UNIT AND ASSOCIATED PIPING, HANGERS AND SUPPORTS COMPLETE.
4. EXISTING GAS FIRED UNIT HEATER AND ASSOCIATED FLUE GAS VENT TO REMAIN.
5. ABANDON EXHAUST FAN IN PLACE. REMOVE ASSOCIATED DUCTWORK, HANGERS, SUPPORTS, ETC. COMPLETE TO WALL AND CAP. FILL THRU WALL DUCTWORK WITH FIBERGLASS INSULATION.
6. REMOVE EXHAUST FAN AND ASSOCIATED DUCTWORK COMPLETE. CURB TO REMAIN, INSTALL INSULATED SHEET METAL CAP ON ROOF CURB.

REV.	DESCRIPTION	DATE
1	CONFORMED SET	4-21-15
0	ISSUED FOR CONSTRUCTION	3-3-15

CONFORMED SET
4-21-15

CURRENT ISSUE STATUS:

PROJECT NORTH

STATE OF MAINE
CALEB J. MILLIKEN
No. 12274
LICENSED
PROFESSIONAL ENGINEER
4/21/15

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

L.L. BEAN
CHESHIRE BUILDING RENOVATIONS
PORTLAND, MAINE

HVAC FIRST FLOOR
DEMOLITION PLAN

SHEET TITLE:

SCALE:	1/8"=1'-0"	DATE:	3-3-15
PROJECT MANAGER:	JLH	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:	CAH/KPB		
A/E OF RECORD:	CJM	SHEET No.	
SMRT CAD FILE:	MD101-14199	MD101	
PROJECT No.	14199-00		

© COPYRIGHT 2013 SMRT INC.

A1 HVAC DEMOLITION PLAN

1/8" = 1'-0"