WALL FINISH NOTES:

1. FOR ADDITIONAL INFORMATION REGARDING FINISHES, INCLUDING DEFINITION OF ABBREVIATIONS, RE: ID601.
2. HVAC GRILLES OR DIFFUSERS MOUNTED ON GWB SHALL BE FIELD PAINTED TO MATCH COLOR OF WALL.
3. ELECTRICAL PANELS LOCATED OUTSIDE OF ELECTRICAL ROOMS SHALL BE FIELD PAINTED TO MATCH THE COLOR OF THE WALL ON WHICH IT IS MOUNTED.
4. ALL WALLS NOT INDICATED TO RECEIVE AN ACCENT PAINT SHALL BE PAINTED PTD-1. REFER TO ROOM FINISH SCHEDULE ID601 FOR FIELD/ACCENT DESIGNATIONS.
5. ALL DOOR TRIM TO BE PAINTED PTD-2.
6. WET WALLS IN RESTROOMS TO RECEIVE PORCELAIN TILE PT-1, FULL HEIGHT. INSTALL HORIZONTALLY, WITH JOINTS STAGGERED AT 1/3 INTERVALS.

REV.	DESCRIPTION	DATE
1	CONFORMED SET	4-21-15
0	ISSUED FOR CONSTRUCTION	3-3-15

CONFORMED SET
4-21-15

CURRENT ISSUE STATUS:

PROJECT NORTH

LICENSED ARCHITECT JANET L. HANSEN #1991 STATE OF MAINE 4-21-15

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

L.L. BEAN
CHESHIRE BUILDING RENOVATIONS
PORTLAND, MAINE

WALL FINISH PLAN

SHEET TITLE:

SCALE:	1/8"=1'-0"	DATE:	3-3-15
PROJECT MANAGER:	JLH	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:			
A/E OF RECORD:	JLH	SHEET No.	
SMRT CAD FILE:	ID102-14199	ID102	
PROJECT No.	14199-00		

© COPYRIGHT 2013 SMRT INC.

A1 | WALL FINISH PLAN
1/8" = 1'-0"