



LOADCENTER: 200A, 120 / 240VAC, 1PH, 3W, MANUAL TRANSFER

VA	LOAD SERVED	BREAKER		BREAKER		LOAD SERVED	VA
		POLE	TRIP	TRIP	POLE		
2145	LTE CABINET	2	50A	1	2	CDMA CABINET	8400
-	SPARE	-	-	3	4	SPARE	-
-	SPARE	-	-	5	6	SPARE	-
-	SPARE	-	-	7	8	SPARE	-
-	SPARE	-	-	9	10	SPARE	-
-	SPARE	-	-	11	12	SPARE	-
-	SPARE	-	-	13	14	SPARE	-
-	SPARE	-	-	15	16	SPARE	-
-	SPARE	-	-	17	18	SPARE	-
-	SPARE	-	-	19	20	SPARE	-
-	SPARE	-	-	21	22	SPARE	-
-	SPARE	-	-	23	24	SPARE	-
2145	SUB TOTAL					SUB TOTAL	8400

TOTAL VA = 10,545 TOTAL AMP = 44 x 1.1 x 1.25 = 60A

- BREAKERS:**
- 50 AMP P/N 0501067 SAP74820
 - 80 AMP P/N 0501069 SAP67461
 - 100 AMP P/N 0501070 SAP67462

POWER PANEL SCHEDULE

SCALE: N.T.S.

NOTES:

- FOR COMPLETE INTERNAL WIRING AND ARRANGEMENT, REFER TO VENDOR PRINTS PROVIDED BY EQUIPMENT MANUFACTURER.
- PROVIDE 100A SERVICE ENTRANCE RATED DISCONNECT IF NOT ALREADY EXISTING. REPLACE EXISTING 200A DISCONNECT WITH 100A SERVICE ENTRANCE RATED DISCONNECT IF APPLICABLE.

ONE LINE DIAGRAM

SCALE: N.T.S.

PLANS PREPARED FOR:

10 Corporate Drive, Suite 210, Bedford, NH 03110

PROJECT INFORMATION

853408-NORTH DEERING

1335 WASHINGTON AVE
PORTLAND, ME 04103
(CUMBERLAND COUNTY)

PLANS PREPARED BY:

511 Congress Street Suite 200, Portland ME 04101
P: (207) 775-5401 F: (207) 772-4762 www.amec.com

PROJECT COORDINATION & MANAGEMENT:

KJK Wireless, LLC

127 Ridge Road, Nashua, NH 03062
Phone: (603) 888-8974

SEAL

MICHAEL S. DELETETSKY
No. 5023
LICENSED PROFESSIONAL ENGINEER

REV	DATE	ISSUED FOR
△	5/23/13	ISSUED FOR CONSTRUCTION

PROJECT NO: 3618138235

DRAWN BY: CBM

RELEASED BY: MSD

SHEET TITLE

ONE-LINE AND POWER PANEL SCHEDULE

SHEET NUMBER	REVISION:
E-1	0