

Anchorages of Column to Footings

* Simpson PB566HDG 2 per post

Sonotubes

10" evenly spaced 4' Below grade

Ledger Fastened with

4" Ledger Lock Bolts 2-16" o.c.

Joist Hangers

LSU28Z - on every Floor Joist Both sides

18-Gauge Hurricane Ties on each Rafter