

BILL TO:


SHIP TO:

QUOTE #	STATUS	CUSTOMER PO#	DATE QUOTED
364086	None		4/5/2017 12:38:13 PM
QUOTED BY	TERMS	PROJECT NAME	QUOTE NAME
Anthony Quinn		Unassigned	BARRINGER/25 NEVADA AVE

LINE #	DESCRIPTION	QTY	LIST PRICE	NET PRICE	EXTD. PRICE
100-1		1	\$324.69	\$202.96	\$202.96

Classics New Construction Double Hung
 35.5 X 39.5 Unit Size, White, Insul Low-E & Argon, DLO
 Width Equal, 6/1 Lite 5/8" Flat, White Grille in Airspace,
 30.62 X 14.25 Clear Opening, 3.03 SQFT, Dual Lock,
 w/Balance Covers, No Window Opening Control Device,
 Insert Full Screen Applied
 w/Nailing Flange, w/J Channel, No Exterior Casing
 Unit 1: UFactor: 0.28, SHG: 0.26, VLT: 0.47, CR: 61

KITCHEN



(A)


Opening: 36" X 40"
 O.S.M.: 35.5" X 39.5"

Tag: None Assigned

LINE #	DESCRIPTION	QTY	LIST PRICE	NET PRICE	EXTD. PRICE
200-1		1	\$269.46	\$168.44	\$168.44

Classics New Construction Double Hung
 23.5 X 39.5 Unit Size, White, Insul Low-E & Argon, DLO
 Width Equal, 4/1 Lite 5/8" Flat, White Grille in Airspace,
 18.62 X 14.25 Clear Opening, 1.84 SQFT, Single Lock,
 w/Balance Covers, No Window Opening Control Device,
 Insert Full Screen Applied
 w/Nailing Flange, w/J Channel, No Exterior Casing
 Unit 1: UFactor: 0.28, SHG: 0.26, VLT: 0.47, CR: 61

BATH



(B)

Opening: 24" X 40"
 O.S.M.: 23.5" X 39.5"


Tag: None Assigned

QUOTE #	STATUS	CUSTOMER PO#	DATE QUOTED
364086	None		4/5/2017 12:38:13 PM
QUOTED BY	TERMS	PROJECT NAME	QUOTE NAME
Anthony Quinn		Unassigned	BARRINGER/25 NEVADA AVE

LINE #	DESCRIPTION	QTY	LIST PRICE	NET PRICE	EXTD. PRICE
300-1		1	\$356.21	\$222.67	\$222.67

Classics New Construction Double Hung
 33.5 X 48.5 Unit Size, White, Insul Low-E & Argon, DLO
 Width Equal, 6/1 Lite 5/8" Flat, White Grille in Airspace,
 28.62 X 18.75 Clear Opening, 3.72 SQFT, Dual Lock,
 w/Balance Covers, White Window Opening Control Device,
 Insert Full Screen Applied
 w/Nailing Flange, w/J Channel, No Exterior Casing
 Unit 1: UFactor: 0.28, SHG: 0.26, VLT: 0.47, CR: 61

BACK
BED
REAR



(C)


Opening: 34" X 49"
 O.S.M.: 33.5" X 48.5"

Tag: None Assigned

LINE #	DESCRIPTION	QTY	LIST PRICE	NET PRICE	EXTD. PRICE
400-1		1	\$479.00	\$299.42	\$299.42

Classics New Construction Casement
 CA3048, Left Operating, White, Insul Low-E & Argon,
 Special Hinge, 22.5 X 42.5 Clear Opening, 6.64 SQFT,
 White Window Opening Control Device, White Handle &
 Lock, Screen Applied
 w/Nailing Flange, w/J Channel, No Exterior Casing
 Unit 1: UFactor: 0.25, SHG: 0.28, VLT: 0.51, CR: 62
 Energy Star Qualified (Northern)

BACK
BED
CASLE



(D)


Opening: 30" X 48"
 O.S.M.: 29.5" X 47.5"

Tag: None Assigned

LINE #	DESCRIPTION	QTY	LIST PRICE	NET PRICE	EXTD. PRICE
500-1		1	\$479.00	\$299.42	\$299.42

Classics New Construction Casement
 CA3048, Right Operating, White, Insul Low-E & Argon,
 Special Hinge, 22.5 X 42.5 Clear Opening, 6.64 SQFT,
 White Window Opening Control Device, White Handle &
 Lock, Screen Applied
 w/Nailing Flange, w/J Channel, No Exterior Casing
 Unit 1: UFactor: 0.25, SHG: 0.28, VLT: 0.51, CR: 62
 Energy Star Qualified (Northern)

FRONT
BACK
BED
CASLE



(D)

Opening: 30" X 48"
 O.S.M.: 29.5" X 47.5"


Tag: None Assigned

QUOTE #	STATUS	CUSTOMER PO#	DATE QUOTED
364086	None		4/5/2017 12:38:13 PM
QUOTED BY	TERMS	PROJECT NAME	QUOTE NAME
Anthony Quinn		Unassigned	BARRINGER/25 NEVADA AVE

LINE #	DESCRIPTION	QTY	LIST PRICE	NET PRICE	EXTD. PRICE
600-1		1	\$397.21	\$248.30	\$248.30

Classics New Construction Double Hung
 41.5 X 48.5 Unit Size, White, Insul Low-E & Argon, DLO
 Width Equal, 6/1 Lite 5/8" Flat, White Grille in Airspace,
 36.62 X 17.25 Clear Opening, 4.38 SQFT, Dual Lock,
 w/Balance Covers, White Window Opening Control Device,
 Insert Full Screen Applied
 w/Nailing Flange, w/J Channel, No Exterior Casing
 Unit 1: UFactor: 0.28, SHG: 0.26, VLT: 0.47, CR: 61

*FRONT
 BEDROOM
 STREET*



(E)


Opening: 42" X 49"
 O.S.M.: 41.5" X 48.5"

Tag: None Assigned

LINE #	DESCRIPTION	QTY	LIST PRICE	NET PRICE	EXTD. PRICE
700-1		1	\$828.42	\$517.85	\$517.85

Classics New Construction Double Hung Narrow Vertical
 Mull
 40.719 X 48.5 Unit Size ; 40.719 X 48.5 Unit Size, White,
 Insul Low-E & Argon, DLO Width Equal, 6/1 Lite 5/8" Flat,
 White Grille in Airspace, 35.84 X 17.25 Clear Opening, 4.29
 SQFT, Dual Lock, w/Balance Covers, White Window
 Opening Control Device, Insert Full Screen Applied
 w/Nailing Flange, w/J Channel, No Exterior Casing
 Unit 1: UFactor: 0.28, SHG: 0.26, VLT: 0.47, CR: 61
 Unit 2: UFactor: 0.28, SHG: 0.26, VLT: 0.47, CR: 61

*LIVING
 ROOM
 STREET*



(F)


Opening: 82" X 49"
 O.S.M.: 81.5" X 48.5"

Tag: None Assigned

LINE #	DESCRIPTION	QTY	LIST PRICE	NET PRICE	EXTD. PRICE
800-1		1	\$346.69	\$216.71	\$216.71

Classics New Construction Double Hung
 33.5 X 48.5 Unit Size, White, Insul Low-E & Argon, DLO
 Width Equal, 6/1 Lite 5/8" Flat, White Grille in Airspace,
 28.62 X 18.75 Clear Opening, 3.72 SQFT, Dual Lock,
 w/Balance Covers, No Window Opening Control Device,
 Insert Full Screen Applied
 w/Nailing Flange, w/J Channel, No Exterior Casing
 Unit 1: UFactor: 0.28, SHG: 0.26, VLT: 0.47, CR: 61

*LIVING
 ROOM
 GABLE*



(C)

Opening: 34" X 49"
 O.S.M.: 33.5" X 48.5"

Tag: None Assigned