



NOTES:

1. INSTALL 1/2" x 14" ANCHOR BOLTS W/ 3" THREADED PIPE AND 3" BEND 6-0" O.C., MAXIMUM, AND 1-0" FROM SECURE SILL W/ HEX. NUT & WASHER.
2. MINIMUM SOIL BEARING PRESSURE IS ASSUMED TO BE 3000 LB. PER SQ. FT. ADDITIONAL REINFORCING TO BE IN FOUNDATION WALL IF SOIL CONDITIONS DICTATE.
3. FOUNDATIONS TO BE LOCATED BELOW FROST LINE AND

DETAIL 1/2" = 1'-0"

DETAIL 1/2" = 1'-0"