

Project Title: New House

Energy Code: 2009 IECC
Location: Portland, Maine
Construction Type: Single Family

Glazing Area Percentage: 1% Heating Degree Days: 7378 Climate Zone: 6

Construction Site: Owner/Agent: Designer/Contractor:

Lot 1 Gleason Architects
Stepping Stone P.O. Box 596
Portland, ME Stratham, NH

gleasonarchitects@gmail.com

Compliance: Passes using UA trade-off

Compliance: **30.2% Better Than Code** Maximum UA: **1917** Your UA: **1339**The % Better or Worse Than Code index reflects how close to compliance the house is based on code trade-off rules. It DOES NOT provide an estimate of energy use or cost relative to a minimum-code home.

Data filename: C:\Users\Dsve\Documents\REScheck\lot1-stepping stone.rck

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Glazing or Door U-Factor	UA
Floor 1: Slab-On-Grade:Unheated Insulation depth: 4.0'	1130		11.0		765
Wall 1: Wood Frame, 16" o.c.	18080	21.0	21.0		445
Window 1: Wood Frame:Double Pane	225			0.350	79
Door 1: Solid	21			0.600	13
Door 2: Glass	42			0.500	21
Ceiling 1: Flat Ceiling or Scissor Truss	1130	38.0	38.0		16

Compliance Statement: The proposed building design described here is consistent with the building plans, specifications, and other calculations submitted with the permit application. The proposed building has been designed to meet the 2009 IECC requirements in REScheck Version 4.4.2.3 and to comply with the mandatory requirements listed in the REScheck Inspection Checklist.

Name - Title Signature Date

Project Title: New House Report date: 01/24/13

Page 1 of 4



Ceilings:
Ceiling 1: Flat Ceiling or Scissor Truss, R-38.0 cavity + R-38.0 continuous insulation
Comments:
Above-Grade Walls:
Wall 1: Wood Frame, 16" o.c., R-21.0 cavity + R-21.0 continuous insulation Continuous insulation specified for this above-grade wall has consistent R-value rating across full area of the wall. Comments:
Windows:
Window 1: Wood Frame:Double Pane, U-factor: 0.350
For windows without labeled U-factors, describe features:
#Panes Frame Type Thermal Break? Yes No
Comments:
Doors:
Door 1: Solid, U-factor: 0.600
Comments:
This door is exempt from the U-factor requirement.
Door 2: Glass, U-factor: 0.500
Comments:
Floors:
Floor 1: Slab-On-Grade:Unheated, 4.0' insulation depth, R-11.0 continuous insulation
Comments:
Slab insulation extends down from the top of the slab to at least 4.0 ft. OR down to at least the bottom of the slab then horizontally for a total distance of 4.0 ft.
Air Leakage:
Joints (including rim joist junctions), attic access openings, penetrations, and all other such openings in the building envelope that are sources of air leakage are sealed with caulk, gasketed, weatherstripped or otherwise sealed with an air barrier material, suitable film or solid material.
Air barrier and sealing exists on common walls between dwelling units, on exterior walls behind tubs/showers, and in openings betwee window/door jambs and framing.
Recessed lights in the building thermal envelope are 1) type IC rated and ASTM E283 labeled and 2) sealed with a gasket or caulk between the housing and the interior wall or ceiling covering.
Access doors separating conditioned from unconditioned space are weather-stripped and insulated (without insulation compression or damage) to at least the level of insulation on the surrounding surfaces. Where loose fill insulation exists, a baffle or retainer is installed to maintain insulation application.
Wood-burning fireplaces have gasketed doors and outdoor combustion air.
Automatic or gravity dampers are installed on all outdoor air intakes and exhausts.
Air Sealing and Insulation:
Building envelope air tightness and insulation installation complies by either 1) a post rough-in blower door test result of less than 7 ACH at 50 pascals OR 2) the following items have been satisfied:
(a) Air barriers and thermal barrier: Installed on outside of air-permeable insulation and breaks or joints in the air barrier are filled or repaired.
(b) Ceiling/attic: Air barrier in any dropped ceiling/soffit is substantially aligned with insulation and any gaps are sealed.

Project Title: New House

(c) Above-grade walls: Insulation is installed in substantial contact and continuous alignment with the building envelope air barrier.

Data filename: C:\Users\Dsve\Documents\REScheck\lot1-stepping stone.rck

- (d) Floors: Air barrier is installed at any exposed edge of insulation.
- (e) Plumbing and wiring: Insulation is placed between outside and pipes. Batt insulation is cut to fit around wiring and plumbing, or sprayed/blown insulation extends behind piping and wiring.
- (f) Corners, headers, narrow framing cavities, and rim joists are insulated.
- (g) Shower/tub on exterior wall: Insulation exists between showers/tubs and exterior wall.

Sι	ın	ro	^	m	e.	

•	onis.
	Sunrooms that are thermally isolated from the building envelope have a maximum fenestration U-factor of 0.50 and the maximum skylight U-factor of 0.75. New windows and doors separating the sunroom from conditioned space meet the building thermal envelope requirements.
ı	Materials Identification and Installation:
	Materials and equipment are installed in accordance with the manufacturer's installation instructions. Materials and equipment are identified so that compliance can be determined. Manufacturer manuals for all installed heating and cooling equipment and service water heating equipment have been provided. Insulation R-values and glazing U-factors are clearly marked on the building plans or specifications.
[Ouct Insulation:
	Supply ducts in attics are insulated to a minimum of R-8. All other ducts in unconditioned spaces or outside the building envelope are insulated to at least R-6.
[Ouct Construction and Testing:
	Building framing cavities are not used as supply ducts.
	All joints and seams of air ducts, air handlers, filter boxes, and building cavities used as return ducts are substantially airtight by means of tapes, mastics, liquid sealants, gasketing or other approved closure systems. Tapes, mastics, and fasteners are rated UL 181A or UL 181B and are labeled according to the duct construction. Metal duct connections with equipment and/or fittings are mechanically fastened. Crimp joints for round metal ducts have a contact lap of at least 1 1/2 inches and are fastened with a minimum of three equally spaced sheet-metal screws. Exceptions:
	Joint and seams covered with spray polyurethane foam.
	Where a partially inaccessible duct connection exists, mechanical fasteners can be equally spaced on the exposed portion of the joint so as to prevent a hinge effect.
	Continuously welded and locking-type longitudinal joints and seams on ducts operating at less than 2 in. w.g. (500 Pa). Duct tightness test has been performed and meets one of the following test criteria:
	(1) Postconstruction leakage to outdoors test: Less than or equal to 8 cfm per 100 ft2 of conditioned floor area.
	(2) Postconstruction total leakage test (including air handler enclosure): Less than or equal to 12 cfm per 100 ft2.
	(3) Rough-in total leakage test with air handler installed: Less than or equal to 6 cfm per 100 ft2 of conditioned floor area.
	(4) Rough-in total leakage test without air handler installed: Less than or equal to 4 cfm per 100 ft2 of conditioned floor area.
7	Temperature Controls:
	Where the primary heating system is a forced air-furnace, at least one programmable thermostat is installed to control the primary heating system and has set-points initialized at 70 degree F for the heating cycle and 78 degree F for the cooling cycle.
	Heat pumps having supplementary electric-resistance heat have controls that prevent supplemental heat operation when the compressor can meet the heating load.

Heating and Cooling Equipment Sizing: Additional requirements for equipment sizing are included by an inspection for compliance with the International Residential Code. For systems serving multiple dwelling units documentation has been submitted demonstrating compliance with 2009 IECC Commercial Building Mechanical and/or Service Water Heating (Sections 503 and 504).

Circulating Service Hot Water Systems:

Circulating service hot water pipes are insulated to R-2. Circulating service hot water systems include an automatic or accessible manual switch to turn off the circulating pump when the system is not in use.

Heating and Cooling Piping Insulation:

HVAC piping conveying fluids above 105 degrees F or chilled fluids below 55 degrees F are insulated to R-3.

Swimming Pools:

Heated swimming pools have an on/off heater switch.

Project Title: New House Report date: 01/24/13 Data filename: C:\Users\Dsve\Documents\REScheck\lot1-stepping stone.rck

	Pool heaters operating on natural gas or LPG have an electronic pilot light.
	Timer switches on pool heaters and pumps are present. Exceptions:
	Where public health standards require continuous pump operation.
	Where pumps operate within solar- and/or waste-heat-recovery systems.
	Heated swimming pools have a cover on or at the water surface. For pools heated over 90 degrees F (32 degrees C) the cover has a minimum insulation value of R-12. Exceptions:
	Covers are not required when 60% of the heating energy is from site-recovered energy or solar energy source.
L	ighting Requirements:
	A minimum of 50 percent of the lamps in permanently installed lighting fixtures can be categorized as one of the following:
	(a) Compact fluorescent
	(b) T-8 or smaller diameter linear fluorescent
	(c) 40 lumens per watt for lamp wattage <= 15
	(d) 50 lumens per watt for lamp wattage > 15 and <= 40
	(e) 60 lumens per watt for lamp wattage > 40
C	Other Requirements:
	Snow- and ice-melting systems with energy supplied from the service to a building shall include automatic controls capable of shutting off the system when a) the pavement temperature is above 50 degrees F, b) no precipitation is falling, and c) the outdoor temperature is above 40 degrees F (a manual shutoff control is also permitted to satisfy requirement 'c').
C	Certificate:
	A permanent certificate is provided on or in the electrical distribution panel listing the predominant insulation R-values; window U-factors; type and efficiency of space-conditioning and water heating equipment. The certificate does not cover or obstruct the visibility of the circuit directory label, service disconnect label or other required labels.
NOT	ES TO FIELD: (Building Department Use Only)

Project Title: New House Data filename: C:\Users\Dsve\Documents\REScheck\lot1-stepping stone.rck Report date: 01/24/13 Page 4 of 4



Insulation Rating	R-Value	
Ceiling / Roof	76.00	
Wall	42.00	
Floor / Foundation	11.00	
Ductwork (unconditioned spaces):		
Glass & Door Rating	U-Factor	SHGC
Window	0.35	0.70
Door	0.50	0.70
Heating & Cooling Equipment	Efficiency	
Heating System:		
Cooling System:		
Water Heater:		

Date: _

Comments:

Name: _