



TFXX.R21159

Prepared Roof Covering Materials, Formed or Molded Metal, Fiber-Cement or Plastic

[Page Bottom](#)

[Questions?](#)

[Previous Page](#)

Prepared Roof Covering Materials, Formed or Molded Metal, Fiber-Cement or Plastic

[Guide Information](#)

CROWE BUILDING PRODUCTS LTD

R21159

116 BURRIS ST
HAMILTON
ON L8N 2J5, CANADA

Formed roofing shingles, for installation over minimum 15/32 in. thick plywood decks as a Class A prepared roof coverings when laid over one layer of 1/4 in. thick G-P Gypsum Dens-Deck® or 1/2 in. thick gypsum board followed by one or more layers of Type 30 underlayment either as an interply or as a base sheet alone.

Formed Roofing shingles , for installation as Class B prepared roof covering. Limited to 15/32 in. plywood decks and one ply of Type G1 plysheet.

Formed roofing shingles, for installation over minimum 15/32 in. plywood decks as a Class C prepared roof coverings when applied with one layer of Type 30 underlayment either as an interply or as a base sheet alone.

Formed roofing shingles, for installation as wind resistant roof coverings when installed in accordance with manufacturer's installation instructions. These shingles may also bear the statement "Also evaluated at wind velocities up to 110 mph".
