

**PRESS RELEASE - Underwriters Laboratories Listing #R21159**

We are pleased to announce that Underwriters Laboratories Inc. has completed their tests and factory inspections. We are now listed for the following classifications:

**UL790**

Class A - prepared roof covering when laid over one layer of 1/4 in. thick G-P Gypsum Dens-Deck or 1/2 in thick gypsum board followed by one or more layers of type 30 underlayment either as an interply or as a base sheet alone.

Class B - prepared roof-covering limited to minimum 15/32 in. plywood or similar decks and one ply Type G1 Fiberglass felt base sheet.

Class C - for installation over minimum 15/32 in. plywood or similar decks when applied with type 30 underlayment either as an interply or as a base sheet alone.

**UL997**

For installation as wind resistant roof coverings when installed in accordance with manufacturer's installation instructions. These shingles may also bear the statement " Also evaluated at wind velocities up to 110 mph" .

**UL2218**

Class 4 Hail Impact Resistance.

"This investigation was initiated with a purpose to establish a program of Listing and Follow-up Service for the products involved in the construction of the test assemblies. Product Listing involves more than merely testing in accordance with a designated Standard. It also involves the implementation of an ongoing program of unannounced visits at the factory whereby Underwriters field representatives audit the quality control programs for factory output, which bears the UL Mark" .

**To search out Authentic Roof Listing on the Underwriters Laboratories web site:**

Please go to: <http://www.ul.com>

**ONLINE CERTIFICATIONS DIRECTORY - UL File Number**

**Enter: R21159**

**This will take you to Two Listings for Crowe Building Products Ltd.  
The first is for Fire and Wind, the second is for Hail Impact.**

For more information please call us at 905-529-6818

Thank you!

Authentic Sales Department