Inspections Division
Date: 12/29/14

FIRST FLOOR PLAN
SCALE: 1/8" = 1'-0"

DOOR SCHEDULE

| MARK | | DOOR WIDTH | DOOR HEIGHT | REMARKS |
|---|---|---|---|---|
| FIRST FLOOR | | | | |
| 1 | | 3'-0" | 6'-8" | ENTRY DOOR |
| 2 | PR. | 2'-0" | 6'-8" | CLOSET DOOR |
| 3 | | 3'-0" | 6'-8" | ENTRY DOOR TO GARAGE - 60 MIN RATED |
| 4 | | 2'-6" | 6'-8" | BASEMENT DOOR |
| 5 | | 2'-0" | 6'-8" | POCKET DOOR - BATHROOM |
| 6 | | 6'-0" | 6'-8" | SLIDER TO PATIO |
| 7 | | 8'-0" | 8'-0" | OVER HEAD DOOR |
| SECOND FLOOR | | | | |
| 8 | | 2'-6" | 6'-8" | BEDROOM |
| 9 | PR. | 2'-0" | 6'-8" | CLOSET - BIFOLD |
| 10 | | 2'-6" | 6'-8" | BEDROOM |
| 11 | PR. | 2'-6" | 6'-8" | CLOSET - BIFOLD |
| 12 | | 2'-6" | 6'-8" | BEDROOM |
| 13 | PR. | 2'-6" | 6'-8" | CLOSET - BIFOLD |
| 14 | | 2'-6" | 6'-8" | BATHROOM |
| 15 | | 2'-6" | 6'-8" | BEDROOM |
| 16 | | 2'-6" | 6'-8" | BATHROOM |
| 17 | | 2'-0" | 6'-8" | CLOSET |
| 18 | PR. | 2'-0" | 6'-8" | CLOSET - SLIDER |
| 19 | PR. | 2'-0" | 6'-8" | CLOSET - SLIDER |
| 20 | PR. | 2'-6" | 6'-8" | CLOSET - SLIDER |
| 21 | PR. | 2'-6" | 6'-8" | CLOSET - SLIDER |
| 22 | | 5'-0" | 6'-8" | EXTERIOR SLIDER |
| 23 | | 2'-6" | 6'-8" | BATHROOM |

WINDOW SCHEDULE

| MARK | | DOOR WIDTH | DOOR HEIGHT | REMARKS |
|---|---|---|---|---|
| 2436 | | 2'-0 1/2" | 3'-2 1/2" | ALSIDE |
| 3660 | | 3'-2 1/2" | 5'-0 1/2" | ALSIDE - EGRESS UNIT |
| 4643 | 2 - | 2'-0 1/2" | 3'-6 1/2" | ALSIDE - KITCHEN (CASEMENT) |
| 4660 | | 4'-4 1/2" | 5'-0 1/2" | ALSIDE |

| NO. | DESCRIPTION OF REVISION | DATE |
|---|---|---|
| 1 | GENERAL REVISIONS | 06/19/13 |

NEW HOUSE
LOT 7, STEPPING STONE LANE
PORTLAND, MAINE

Gleason Architects
P.O. BOX 596, 152 PORTSMOUTH AVENUE
STRATHAM, NEW HAMPSHIRE 03885
603 772-7370 FAX NO. 603 772-6044

ARCHITECT

ENGINEER
DATE 12/21/12
PROJECT NO. 201240
SHEET NO.
A-2
OF SHEETS