
NOT TO SCALE

**VERIFY HOISTWAY DIMENSIONS** WITH MANUFACTURE PRIOR TO POURING ELEVATOR PIT

ELEVATOR 2 TO BE ON BATTERY BACKUP

PROVIDE VANDAL RESISTANT FIXTURES FOR BOTH THE CAR CONTROLS AND HALL STATION ON ALL FLOORS



## HOISTWAY PLAN

NOTE A: OIL PIPE LINES AND FITTINGS SHALL BE PROPERLY SUPPORTED TO RELIEVE STRAIN. NOTE B: ALL REACTIONS INCLUDE ALLOWANCE FOR IMPACT.

NOTE C: THYSSENKRUPP ELEVATOR TO BE NOTIFIED OF ANY CHANGE TO ELEVATOR HOISTWAY OR MACHINE ROOM DESIGN.

NOTE D: ELEVATOR DESIGN & FABRICATION BASED ON ESTIMATED CAB WEIGHT SHOWN. LAYOUT APPROVAL WILL BE CONSTRUED AS FINAL CAB WEIGHT, UNLESS OTHERWISE NOTIFIED.

OILDRAULIC ELEVATOR CONTRACT DATA PLEASE VERIFY WALL THICKNESS TYPE: AMEE 25 HLS AND TYPE AT EACH LANDING SPEED: FPM UP 150 FPM DOWN MAX. CAPACITY: 2500 FLR THKNESS WALL TYPE OPERATION: CAR ENCLOSURE: DOOR TYPE: ONE SPEED - LEFT HAND PLATFORM THK: 3 3/8 FINISHED FLOOR: TELEPHONE: PIT LADDER: POWER SUPPLY: **POWER UNIT:** HP STARTING: GLOPU: GLOJ: JACK MODEL: OVERTRAVEL TOP BOTTOM WALL THK: PLUNGER O.D.: CYLINDER O.D.: WALL THK: **NET AREA** BOTTOM CAR RUNBY: 6" CAR BUFFER STROKE: 2 1/2"

BETWEEN PIT FLR. & CAR BOLSTER ON COMPRESSED BUFFER: 2'-4 1/8"

BUFFER REACTION (TYP. AT EACH BUFFER) = EST. WORKING PRESS S = 1.38 FORMED S = 3.27 FORMED \_\_\_\_\_ S = 5.429 FORMED FRAME I = 9.82 CROSSHEAD I = 21.71 BOLSTER I = 2.17 STILE A = 1.85 7GAx6"x2 1/2" A = 2.264 7GAx8"x2 3/4" r = 1.009 t = 10GA

THE FOLLOWING CONDITIONS MUST BE MET BEFORE INSTALLATION IS COMPLETED, AND ARE NOT INCLUDED IN THE ELEVATOR CONTRACT: . A PLUMB, PROPERLY VENTILATED HOISTWAY (ACCORDING TO CODE AND SIZES SHOWN).

. ADEQUATE SUPPORT FOR JACK, GUIDE RAIL BRACKETS, AND BUFFERS (FOR REACTIONS SHOWN ). HOISTWAY BARRICADES AND ALL CUTTING AND PATCHING TO INSTALL HOISTWAY

ENTRANCES, SILLS, HALL FIXTURES, OIL AND ELECTRIC LINES. PIT LIGHTS AND SWITCH, CONVENIENCE OUTLETS WITH GFCI PROTECTION PER NEC, PIT LADDER PER CAR (ACCORDING TO CODE). NOTE: MUST BE CLEAR OF ALL ELEVATOR EQUIPMENT.

DEDICATED 120 VOLT,15 AMP. SERVICE, ALONG WITH TELEPHONE CIRCUIT WHEN REQUIRED, TO TERMINALS OF EACH REQUIRED CONTROLLER (AS LOCATED ON PLAN VIEW) FOR THE FOLLOWING: - CAR LIGHT AND ALARM CIRCUIT WITH GFCI PROTECTION PER NEC - GROUP CONTROL WHEN REQUIRED

NOTE: IF STANDBY POWER IS SUPPLIED TO ELEVATOR, CAR LIGHT AND ALARM CIRCUIT AND GROUP CONTROL SERVICE MUST BE STANDBY POWER BACKED.

BRANCH CIRCUIT CONDUCTOR SIZING, MATERIALS, AND INSULATION (INCLUDING BRANCH CIRCUIT OVERCURRENT PROTECTIVE DEVICE) TO COMPLY WITH ALL LOCAL ELECTRICAL CODES. AMPS STARTING CURRENT WITH A MAX. ALLOWABLE VOLTAGE DROP OF 10%. AMPS FULL LOAD CURRENT WITH A MAX. ALLOWABLE VOLTAGE DROP OF 5%. AMPS RATED CURRENT WITH A MAX. ALLOWABLE VOLTAGE DROP OF 5%.

POWER REQUIREMENTS STATED IN NOTE 6 VERIFIED BY:

NOTE: ALSO, A FOURTH WIRE OF SAME SIZE AS THREE PHASE WIRES IS REQUIRED FOR GROUNDING PURPOSES TO MINIMIZE ELECTRICAL NOISE INTERFERENCE. THE GROUNDING WIRE MUST BE CONNECTED TO THE BUILDINGS ELECTRICAL SYSTEM GROUND. IF BATTERY OPER. LOWERING IS PROVIDED, A MECHANICAL AUX. CONTACT SHALL BE INSTALLED ON THE DISC SW. FOR EA. CAR. THE AUX. CONTACT SHALL BE CONFIGURED AS SPST AT 1A 110VAC (MIN). THE AUX. CONTACT SHALL BE OPEN WHEN THE DISC SW. IS IN THE OPEN POSITION. IF A SHUNT TRIP CIRCUIT BREAKER IS PROVIDED, AN AUX. CONTACT SHALL BE INSTALLED ON THE CIRCUIT BREAKER.

GEN. CONTRACTOR MUST FORWARD POWER REQUIREMENTS TO ELEC. CONTRACTOR.

AN ENCLOSED MACHINE AREA (ACCORDING TO CODE), WITH ADEQUATE LIGHT, HEAT, AND VENTILATION (MIN. 50°F., MAX. 90°F. WITH NON-CONDENSING HUMIDITY OF 10-90%), AND SEALED CONCRETE FLOOR SLAB SURFACE. NOTE: MUST PROVIDE ADEQUATE DOOR SIZE TO ALLOW INSTALLATION OF EQUIPMENT, OR LEAVE WALL OUT UNTIL EQUIPMENT IS IN PLACE.

8. ENTRANCE WALL WITH LINTELS MUST BE PROVIDED AFTER ENTRANCE FRAMES ARE SET OR LEAVE A ROUGH OPENING 15" WIDER AND 15" HIGHER THAN THE FRAME OPENING. SEE INSTALLATION PROCEDURES FOR FRAME-TO-WALL INTERFACE DETAILS TO ENSURE CONFORMANCE WITH THE LABELED ENTRANCE INTERFACE CONSTRUCTION.

). POCKETS IN CORRIDOR WALL (PER FIXTURE DRAWINGS) FOR HALL FIXTURES. NOTE: MUST BE LOCATED AS DIRECTED BY ELEVATOR CONTRACTOR

10. SMOKE SENSORS (AS REQUIRED).

CONDUIT AND WIRING FROM HOISTWAY TO ELEVATOR MONITORING PANELS (FOR SECURITY, LIFE, SAFETY, OR FIRE REQUIREMENTS).

12. PIPE SLEEVES, TRENCHING, AND BACK FILLING FOR OIL AND/OR CONDUIT LINES AS SHOWN OR LOCATED BY ELEVATOR CONTRACTOR.


CAR STATIO	ON:								
CAR RIDING	3 LANTERI	٧:				Han annual a			
RAIL FORCES			F1 F2				~~		
	F1		78 LBS.	215 LBS.		AND DESCRIPTION OF THE PROPERTY OF THE PROPERT			
OME	GA RAILS								
								BY	
DATE	SYM.	REVISION							CH
DESIGNED	PER ASM	E A17.1			DO NOT S	SCALE T	HIS DRAW	ING	
FOR: ELEV#									
ADDRESS:									
CITY:									
ARCHITEC	T:								
GENERAL	CONTRAC	TOR:							
ELEVATOR	CONTRAC	CTOR:							
This draw	ing and a	all informa	tion thereor	n is the p	proprietary	proper	ty of Thys	senKrup	p

Elevator and must not be made public or copied. This drawing is loaned subject to return on demand and is not to be used directly or indirectly in any manner detrimental to the interest of ThyssenKrupp Elevator.



## ThyssenKrupp Elevator

CHKD. BRANCH JOB NUMBER DRAWING NO. REV. SHEET NO M25LHTWIN1 1 OF 1



COLSON AND COLSON
GENERAL CONTRACTOR, INC.

SIDENCE, MAINE 04103 RETIRE

DATE 8/28/2015 **REVISED DATE** 

SHEET A9.0b