

ZONE 4 HOLDOWN SCHEDULE

						<del></del>
QC	THIRD FLOOR	SECOND FLOOR	FIRST FLOOR	A307 BOLT DIA. (UNO)	EMBED. DEPTH	CONC. PA (WxWxD
11A			3610	3/4"	10-1/2"	NO PAD
11)			9000	3/4*	10-1/2"	54x54x24 W/(7)#5 E.\
13			17082	1"	15-1/2"	90x90x24 W/(11)#4 E TOP & BTN
21		6100	6100	5/8*	10-1/2"	42x42x18 W/(8)#4 E.\
23		12000	17500	1-1/8"	13-1/2"	102x102x2 W/(8)#5 E.\ TOP & BTN
31	6100	6100	6100	5/8*	10-1/2"	42x42x18 W/(8)#4 E.\
33	6000	12000	17500	1-1/8*	13-1/2"	102x102x2 W/(8)#5 E.\ TOP & BTN
35	12000	20000	21875	<b>*</b> 1-1/4"	16-7/8"	108x108x3 W/(11)#5 E TOP & BTN

HOLDOWN NOTES EMBEDMENT DEPTHS ARE CALCULATED FOR THE SIMPSON SET-XP EPOXY SYSTEM. ALL OTHER EPOXY SYSTEMS SHALL BE APPROVED BY THE ARCHITECT or ENGINEER BEFORE INSTALLATION.

-ARCHITECT TO RECEIVE WRITTEN CONFIRMATION THAT HOLDOWNS ARE INSTALLED PER THE MANUFACTURER'S RECOMMENDATIONS. -EMBEDMENT DEPTH IS REQUIRED DEPTH MEASURED FROM TOP OF CONCRETE PAD. (EXCLUDE SLAB AND STEMWALL DEPTH)... -CONCRETE PAD DIMENSIONS SHALL ACHIEVE 100% STRENGTH WITHOUT USING EDGE

REDUCTION FACTORS TO ACHIEVE DESIGN UPLIFT (TENSILE) RESISTANCE OF EMBEDDED -ALL HOLES DRILLED IN OR THROUGH WOOD MEMBERS FOR HOLDOWN RODS AND ANCHOR BOLTS TO BE A MINIMUM OF 1/32" TO A MAXIMUM OF 1/8" LARGER THAN THE BOLT

-IF HOLDOWN FOOTING SIZE IS LARGER THAN COLUMN PAD USE HOLDOWN SCHEDULE

★- A193 GR B7 BOLT REQUIRED.

NOTE: SEE ANCHOR BOLT LAYOUT ON SHEET S2.7a & S2.7b FOR INSTALLATION INFORMATION.

## **FOUNDATION NOTES**

- BOTTOM PLATE ANCHORS: EXTERIOR SHEARWALL REFER TO SHEARWALL SCHEDULE EXTERIOR NON-SHEARWALL 1/2"Øx10" ANCHOR BOLTS @ 48" o.c. AND 6" FROM ENDS AND PLATE SPLICES. INTERIOR SHEARWALL- REFER TO SHEARWALL SCHEDULE INTERIOR NON-SHEARWALL - "HILTI" DS72S36 @ 48"oc AND 6" FROM ENDS.
- 28 DAY CONCRETE STRENGTH =3,000 psi MIN.
- SOIL BEARING CAPACITY PER SOILS REPORT
- SPREAD FOOTINGS = 4,000 psf. SQUARE FOOTINGS = 4,000 psf.
- DIMENSIONS SHOWN ARE: EXTERIOR WALLS = OUTSIDE EDGE OF STEM WALL INTERIOR WALLS = CENTER OF THICKENED SLAB FREE STANDING COLUMNS = CENTER OF COLUMN
- FINISHED FLOOR ELEVATION PER CIVIL GRADING PLANS
- MINIMUM FOUNDATION DEPTH 54" BELOW FINISH GRADE.
- VERIFY ELEV. PIT REQ'TS. W/ MANUF. (DIM. SHOWN TO INSIDE FACE.)
- 8. FINISH GRADE (F.G.) TO BE 8" BELOW FINISH FLOOR (F.F.) ELEVATION.
- EXTRACT FROM SOILS REPORT PREPARED BY:
- S. W. COLE ENGINEERING, INC. 286 PORTLAND ROAD GRAY, MAINE 04039
- PHONE: 207-657-2866 PROJECT #14-1188S **DATE: JANUARY 16, 2015**

\*\* HOLDOWNS LOCATED AT FOUNDATION

SEE S1.1 - S1.3 FOR ADDITIONAL FOUNDATION LOCATION AND INFORMATION. SEE S1.4 - S1.6 FOR ADDITIONAL FRAMING MEMBERS LOCATION AND INFORMATION.

8/28/2015

REVISED DATE 1 9/22/2015



1ST FLOOR HOLDOWN PLAN