

STRUCTURAL FRAMING NOTES

STRUCTURAL LEGEND:

REFERENCE

STRUCT. NOTE

HEAT PUMP UNIT

HORIZONTAL EXIT

TUBE STEEL COLUMN

WOOD COLUMN

DESIGNATION

DESIGNATION

C2 COLUMN REF.

P1 COLUMN PAD TAG

F-1 FOOTING TAG

FIRE WALL/FIRE BARRIER

SIMPSON SSU HANGERS. CONNECT JACK TRUSS TOP AND BOTTOM CHORD, OR angle RAFTER AND CLG JOISTS (WHERE STICK FRAMING IS USED) TO CARRY TRUSS.

A SHEARWALL ON WALL SHOWN

HOLDOWN REF. SYSTEM REFERENCE

(11) (SEE S2.7a & S2.7b) SEE DETAILS

WB - STARTS AT WOOD BEAM

HOLDOWN REFERENCE(SEE 1/S2.4)

S = SINGLE CS16x49" LONG STRAP

w/ (22) 10d PER STRAP

w/ (22) 10d PER STRAP

S3 = TRIPLE CS16x49" LONG STRAP

w/ (22) 10d PER STRAP

S4 = TRIPLE CS14x57" LONG STRAP

w/ (30) 10d PER STRAP

S2 = DBL. CS16x49" LONG STRAP

SB - STARTS AT STEEL BEAM

SHEAR PANEL ON DASHED SIDE

10,17/S2.2 FOR FT'G

2 TYPICAL STAIR CONSTRUCTION: (see architectural details A7.4) MID LANDINGS - 1-3/4x11-7/8 LVL @ 24" oc. HEADER'S - (2) 1-3/4x11-7/8.

SEE DETAIL 13/S2.5 FOR STRINGER SIZE AND SPACING, DETAIL 11/S3.3 FOR ROOF FRAMING & DETAIL 9/S2.4 FOR BEAM SIZE AND LOCATIONS. \langle 3 angle GRADUATED TRUSSES FOR HIP/VALLEY CONSTRUCTION.

- SPACE JOISTS 32" FOR H.V.A.C. SUPPORT FLOOR SHEATHING w/ FLAT 4x12 @ 24" o.c. w/ Z2 CLIPS THIS LOCATION. (TYP.) TRUSSES BEAR ON EXTERIOR WALL AND CANTILEVER OVER TOP FLOOR
- DECKS. SIMPSON H1 EACH TRUSS CANTILEVERED. TRUSSES BEAR ON TOP OF WALL, OR COLUMN. SIMPSON H2.5 ANCHOR TIES TRUSS TO FRAMING MEMBER BELOW EACH END OF EACH TRUSS
- SPACE FRAMING MEMBER FOR MECH CHASE, HATCHES AND OPENINGS. SEE DTLS. 2 & 3/S2.5 CONFIRM CLEAR OPENING REQMNTS WITH MECH CONTR.
- $\fbox{8}$ 2x6 DECK JOISTS @ 16" oc/ U.O.N. SEE DTL SHEET A7.3 and 10 & 11/S2.3 FOR DECK FRAMING.
- 9 SHEAR WALL NOTES-(PANELS REFER TO DETAIL 2/S2.6)
 * SHEAR WALL CONSTRUCTION IN ACCORDANCE WITH REPORT NO NER-272. * SHEAR WALL PERPENDICULAR TO CORRIDOR CONTINUE THROUGH ATTIC TO UNDER SIDE OF ROOF SHEATHING. USE SAME WALL TYPE AS USED ON THIRD
- $\langle 10 \rangle$ STICK FRAME OVER ELEVATOR w/ 2x8 RAFTERS @ 16" o.c. ON CRIPPLE WALLS,

FLOOR. (DETAIL 1/S2.6) OR SHEAR "B" WHICHEVER IS GREATER.

ON SHAFT AND CORRIDOR. $\langle 11 \rangle$ DECK BELOW

- 1. HEIGHT OF TOP PLATE 9'-1" U.O.N. $\langle 12
 angle$ 2HR STAIR, ELEVATOR AND CHASE FRAMING, SEE 17, 18 AND 19 ON S2.9
- 13) FIRE BARRIER WALL SEE DETAIL 15 AND 16 ON S2.9 \langle 14angle DRAG STRUTS - REFER TO STRUC. DETAIL 8 /S2.6, DRAG STRUT @ FLOOR.

2x6 AT 16" O.C. BEARING

2x8 BEARING WALL PER PLAN

2x10 AT 24" O.C. BEARING WALL

J = FLOOR JOISTS

CJ = CEILING JOISTS

FRAMING DIRECTION

EXTENT OF FRAMING

SINGLE JOIST / TRUSS

TRUSS / GIRDER TRUSS

STRUCT MEMBER (SEE BELOW)

HALF HIGH WALL PER PLAN

R = RAFTERS

FRAMING TYPE

= DBL. JOIST / VLY, TRUSS HIP

WALL U.N.O.

- \langle 15angle DRAG STRUTS REFER TO STRUC. DETAIL 9 /S2.6, DRAG STRUT @ FLOOR.
- DRAG STRUTS REFER TO STRUC. DETAIL 11/S2..6 DESIGN TRUSS FOR ADDITIONAL 2000# LATERAL LOAD PLACED ON TOP CHORD OF TRUSS. SEE DETAIL 13/S2.6 FOR UPLIFT CONNECTIONS. SEE DETAIL 15/S2.6 FOR WALL CONNECTION. DRAG STRUTS - REFER TO STRUC. DETAIL 12/S2.6. DESIGN TRUSS FOR
- $^{\prime}$ ADDITIONAL 5000# LATERAL LOAD PLACED ON TOP CHORD OF TRUSS. SEE DETAIL 13/S2.6 FOR UPLIFT CONNECTIONS.
- LOCATION OF FUTURE DOOR 14'-6" FROM CORRIDOR SIDE OF WALL OR 6"
 AWAY FROM NEAREST WALL (PROVIDE DOOR HEADER IN FRAMING SEE DETAIL
- $\langle 19 \rangle$ SCISSORS TRUSSES TO BARE ON BEAMS. DO NOT HANG TRUSSES FROM BEAM) $\langle 20
 angle$ (1)-MST72 STRAPS BM TO DBL TOP PLATE/TRUSS OR BEAM TO BEAM $\langle 21
 angle$ (2)-MST72 STRAPS BM TO DBL TOP PLATE. W/ (56)-16d NAILS
- MITER BEAMS AT CORNERS OR PROVIDE (2) SIMPSON HGA10 ANGLES TOP AND BOTTOM. (AT ELEVATOR)

PROVIDE BLK'G FOR KITCHEN HOOD. COORDINATE W/ KITCHEN EQUIP.

SUPPLIER FOR LOCATION OF BLK'G. GRADUATE TRUSS OVER-FRAMING @ 24" o.c. W/ SIMPSON VTC2 CLIPS AS REQ'D, OVERFRAMING TRUSSES TO BE PLACED ON ROOF SHT'G (PER DETAIL

2. STRUCTURAL MEMBER MATERIALS - GLB = 24F-V4 (DF/DF) - CONT GLB = 24F-V8 (DF/DF) - DBM = (3) 2x12 #1/#2 SPF or 3-1/8x12 G.L.B.< 12'-0" 12'-0" < 5-1/8x12" GLB 12'-0" < 20'-0" - HDR 0" SPAN 6'-0" (3)2x10" #1/#2 SPF

3. REFER TO SHEET S2.1 FOR ASSEMBLY OF BUILT-UP COLUMNS AND MULTIPLE LAMINATED VENEER (LVL) MEMBERS.

- HDR 6'-1" SPAN 9'-0" (3)2x12" #1/#2 SPF

- 4. TRUSSES ARE TO BE ALIGNED ON BOTH SIDES OF THE CORRIDOR. ADJUST SPACING OF TRUSSES AS REQUIRED. 5. PROVIDE ADDITIONAL TRUSS OVER SHEARWALLS THAT ARE PARALLEL TO
- 6. ALL 36" DOOR HEADERS TO BE (3) 2x10 U.O.N. 7. REFER TO DTLS. #1 & #3 ON S2.3 FOR ALLOWABLE HOLES IN STRUC. MEMBERS. NO HOLES ARE TO BE PUT IN LVL MATERIALS WITHOUT ENGINEERS APPROVAL. 8. BOTTOM OF BEAM ELEVATION AT TOP PLATE U.O.N.
- 9. REFER TO DETAILS #4 & #9 ON S2.3 FOR HEADER DETAILS. 10.TOP PLATE CONTINUITY IN SHEAR AND

LOAD-BEARING WALLS TO BE

13.BRACE TOP OF ALL INTERIOR

- MAINTAINED PER DETAIL #14 ON S2.3. 11.PREFABRICATED PANELS CONNECTED PER DETAILS #10 & #14 ON S2.6. 12.ALL TRUSSES ARE @ 24" oc U.O.N.
- NON-BEARING WALLS ACCORDING TO DETAIL 15/S2.5 AND 7/S3.3 14.ROOF AND FLOOR SHEATHING GRADE
- PER S2.1 AND NAILING REQUIREMENTS PER DETAIL 16/S2.5 SEE DETAIL #1/S3.3 FOR NAIL LOCATIONS 15.(2) 2x6 POST @ ALL GIRDER TRUSS BEARING (U.N.O.)
- 16.REFER TO 8/S3.0 FOR ELEC. PANEL FRAMING. 17.(3) 2x6 AT EA END OF DBM U.O.N. 18. ALL TRUSSES TO BE INSTALLED AND


BRACED PER 'BCSI 1-03'

	COLUMN S	CHEDUL	E
COL	MATERIAL	SIZE	BASEPLATE
C1	SPF #1/#2 OR BETTER DFL #2	(2) 2x6 4x6	
C2	SPF #1/#2 OR BETTER	(3) 2x6	
	DFL #1	6x6	
C3	SPF #1/#2 OR BETTER	(4) 2x6	
	DFL #1	6x8	
C4	ASTM A500	3-1/2x3-1/2x1/4"	9-1/2"x0'-91/2x3/4
C5	ASTM A500	4x4x1/4"	10"x0'-10"x3/4"
C6	ASTM A500	4x4x5/16"	10"x0'-10"x3/4"
C7	ASTM A500	4x4x3/8"	10"x0'-10"x3/4"
C8	ASTM A500	5x5x3/8"	11"x0'-11"x3/4"
C9	ASTM A500	5x5x1/4"	11"x0'-11"x3/4"
C10	ASTM A500	6x6x5/16"	12"x12"x3/4"
C11	SPF #1/#2 OR BETTER DFL #2	(4) 2x4 4x6	
C12	ASTM A500	8x8x1/4"	14"x14"x3/4"

JOIST SCHEDULE (NOTE NOT ALL JOISTS ARE USE								
JOIST	MATERIAL	SIZE	SPACING					
J-1	REDBUILT RED-145	9-1/2" DEPTH	24" oc					
J-2	REDBUILT RED-190	18" DEPTH	24" oc					
J-3	REDBUILT RED-190	18" DEPTH	16" oc					
J-4	REDBUILT RED-190	DBL. 18" DEPTH	19.2" oc					
J-5	REDBUILT RED-190	18" DEPTH (multi-span)	24" oc					
J-6	REDBUILT RED-I45	DBL. 9-1/2" DEPTH	16" oc					
J-7	REDBUILT RED-I45	9-1/2" DEPTH	12" oc					
J-8	REDBUILT RED-190	DBL. 18" DEPTH	16" oc					
J-9	REDBUILT RED-190	DBL. 18" DEPTH	24" oc					
CJ-1	SPF #1/#2	2x10	24" oc					
***************************************	THE RESERVE AND ADDRESS OF THE PARTY AND ADDRE		(NOTE NOT ALL					

l			1
	RAFTER	SCHEDULE	(NOTE NOT ALL RAFTERS ARE USED)
RAFTER	MATERIAL	SIZE/SPAN*	SPACING
R-1	SPF #1/#2	2x12, 8'-6" SPAN	24" oc
R-2	SPF #1/#2	2x12, 11'-6" SPAN	16" oc
R-3	REDBUILT RED-190	11-7/8" DEPTH	24" oc
R-4	REDBUILT RED-190	DBL 11-7/8" DEPTH	19.2" oc
R-5	SPF #1/#2	2x6, 7'-6" SPAN	24" oc
* SPAN IS	APPROXIMATE VERIFY II	N FIFI D	, , , , , , , , , , , , , , , , , , ,


R-3	F	REDBUILT RED-190					11-7/8" DEPTH						24" oc		
R-4	F	REDBUILT RED-190					DBL 11-7/8" DEPTH							19.2" o	С
R-5	s	SPF #1/#2				2	2x6, 7'-6" SPAN							24" oc	arass
* SPAN IS APPROXIMATE VERIFY IN FIELD * NOT ALL JOISTS LISTED MAY BE USED. (verify per plans.)															
SHEARWALL SCHEDULE															
		T'G. T HCKN		SHT'G. NAIL INFO.			IL							ARWALI	
ŢŢ.			ES	SEE NOTE			NOTES	16 NA				д) #	ALL ANCHO BOLTS TO BE		
SHEARWALL MARK	APA	WALL BD.	BOTH SIDES	NAIL ®	EDGE oc	FIELD oc	KEY N	NAILING	ROWS	JPA OC	00 8- ¹ 25	JSTS. PERP. TO WALL (SEE DET. #)	ANCI BOLT & SP @	HOR I DIA. ACING " oc	1.0.
$\langle A \rangle$		564		6d CLR.	7"	7"	4	.9		24"	24"	6/S2.3 or 5/S2.6	1/2" DIA. @ 48 or 5/8" DIA. @ 48		
(a)	7.					2"				001	201	6/S2.3	1/2" DI	A. @ 36"	



KEY NOTES

- 3x STUDS AT ADJOINING PLY'WD PANEL EDGES.
- 2. 3x STUDS AND SILL PLATES. STAGGER PLY'WD PANEL EDGES.
- 3. 3x DF/L STUDS AND SILL PLATES. STAGGER PLY'WD PANEL EDGES. 4. 5/8" GYPSUM SHEATHING TO BE SECURED WITH 6d COOLER NAILS OR #6-1|" TYPE "W" OR "S" SCREWS DIRECTLY TO STUDS.
- 5. PLY'WD PANEL EDGES ARE TO BE STAGGERED TO FALL ON DIFFERENT FRAMING 6. NAILS ARE TO BE COMMON or HOT DIPPED GALVINIZED U.O.N.
- 7. 3x SILL PLATES REQUIRED AT FOUNDATION ONLY. SHEAR PANEL NOTES
- * SHEAR VALUES ARE ADJUSTED FOR SPRUCE-PINE-FIR STUDS @ 16" oc U.O.N. * ALL APA SHEATHING SHEARWALLS TO BE BACKED WITH 2" NOMINAL OR WIDER
- * WHEN APA RATED PANELS ARE INSTALLED TO BOTH SIDES OF WALL PANEL JOINTS OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS. * NAILING NOT TO PENETRATE THE OUTER VENEER LAYER.
- * WHEN USING A NAIL GUN, CONTRACTOR SHALL ENSURE THAT GUN IS SET TO INSTALL NAIL SLIGHTLY PROUD OF SURFACE BEING NAILED. NAIL SHALL THEN BE SET BY HAMMER. DO NOT ALLOW NAIL TO OVER PENETRATE WOOD SURFACE ESPECIALLY ON SHEARWALLS.
- * ALL EDGES ON APA RATED PANELS TO BE BLOCKED TO MAINTAIN STRENGTH. * ALL PANELS LISTED MAY NOT BE USED ON ALL PROJECTS. REFER TO THE
- SHEARWALL LAYOUT PLANS FOR SIZE, TYPE AND LOCATION OF PANELS. * GYPSUM WALLBOARD LOAD IS REDUCED IN HIGH SEISMIC LOCATIONS. * SEE DETAIL #14/S2.5 FOR STAPLES TO NAIL EQUIVALENT TABLE. * 7/16 OSB (PS2-92 GRADE) MAY BE USED IF APPLIED DIRECTLY TO FRAMING WHEN
- STUDS ARE SPACED A MAXIMUM OF 16" o.c. OR PANELS ARE APPLIED WITH LONG DIMENSION ACROSS STUDS. 15/32 OSB SHALL BE USED WHEN STUDS ARE SPACED A MAXIMUM OF 24" o.c. * USE EITHER 16d NAILS OR 'LTP4' CLIPS WHEN SHT'G IS ATTACHED TO LOWER TOP

* ALL ANCHOR BOLTS AT SHEARWALLS TO HAVE A 3x3x1/4 THICK PLATE WASHER.



5/8" DIA. @ 8"

ETIR

REVISED DATE 1 9/22/2015 SHEET

8/28/2015