


SEE DETAIL 1 AND 3 ON S2.3 FOR ALLOWABLE BORING / NOTCHING OF MEMBERS.

ALL 2ND FLOOR BEARING WALL STUDS TO BE 2x6 #1/#2 SPF @ 16" o.c. AND SILL AND DBL TOP PLATES TO BE 2x6 SPF GRADE.



**STRUCTURAL LEGEND:**

	DETAIL REFERENCE		SHEARWALL ON WALL SHOWN SHEAR PANEL ON DASHED SIDE		2x6 AT 16" O.C. BEARING WALL U.O.
	STRUCT. NOTE		HOLD-DOWN REF. SYSTEM REFERENCE (SEE S2.7 & S2.7.1) SEE DETAILS 10,17/S2.2 FOR FTG		2x6 BEARING WALL PER PLAN
	HEAT PUMP UNIT		FIRE WALL/FIRE BARRIER HORIZONTAL EXIT		HALF HIGH WALL PER PLAN
	WOOD COLUMN DESIGNATION		SUBSCRIPTS: WB - STARTS AT WOOD BEAM SB - STARTS AT STEEL BEAM		STRUCT. MEMBER (SEE BELOW)
	TUBE STEEL COLUMN DESIGNATION		HOLD-DOWN REFERENCE (SEE 1/S2.4)		FLOOR JOISTS
	C2 COLUMN REF.		S = SINGLE CS16x49" LONG STRAP w/ (22) 10d PER STRAP		CEILING JOISTS
	COLUMN PAD TAG		S2 = DBL. CS16x49" LONG STRAP w/ (22) 10d PER STRAP		FRAMING TYPE
	F-1 FOOTING TAG		S3 = TRIPLE CS16x49" LONG STRAP w/ (22) 10d PER STRAP		SINGLE JOIST / TRUSS
			S4 = TRIPLE CS16x57" LONG STRAP w/ (30) 10d PER STRAP		DBL. JOIST / VLY. TRUSS HIP TRUSS / GIRDER TRUSS

- STRUCTURAL FRAMING NOTES:**
- SIMPSON SSU HANGERS - CONNECT JACK TRUSS TOP AND BOTTOM CHORD, OR RAFTER AND CLG JOISTS (WHERE STICK FRAMING IS USED) TO CARRY TRUSS.
  - TYPICAL STAIR CONSTRUCTION: (see architectural details A7.4)
  - MID LANDINGS - 1-3/4x11-7/8 LVL @ 24" oc.
  - HEADERS - (2) 1-3/4x11-7/8 LVL @ 24" oc.
  - SEE DETAIL 13/S2.5 FOR STRINGER SIZE AND SPACING. DETAIL 11/S3.3 FOR ROOF FRAMING & DETAIL 9/S2.4 FOR BEAM SIZE AND LOCATIONS.
  - GRADUATED TRUSSES FOR HIP/VALLEY CONSTRUCTION.
  - SPACE JOISTS 32" FOR H.V.A.C. SUPPORT FLOOR SHEATHING w/ FLAT 4x12 @ 24" o.c. w/ Z2 CLIPS THIS LOCATION. (TYP.)
  - TRUSSES BEAR ON EXTERIOR WALL AND CANTILEVER OVER TOP FLOOR DECKS. SIMPSON H1 EACH TRUSS CANTILEVERED.
  - TRUSSES BEAR ON TOP OF WALL, OR COLUMN. SIMPSON H2.5 ANCHOR TIES TRUSS TO FRAMING MEMBER BELOW EACH END OF EACH TRUSS
  - SPACE FRAMING MEMBER FOR MECH CHASE, HATCHES AND OPENINGS. SEE DTLS. 2 & 3/S2.5 CONFORM CLEAR OPENING REQMENTS WITH MECH CONTR.
  - 2x6 DECK JOISTS @ 16" o.c. U.O.N. SEE DTL SHEET A7.3 AND 10 & 11/S2.3 FOR DECK FRAMING.
  - SHEAR WALL NOTES-PANELS REFER TO DETAIL 2/S2.6
  - SPACE WALL CONSTRUCTION IN ACCORDANCE WITH REPORT NO. NR-272. \* SHEAR WALL PERPENDICULAR TO CORRIDOR CONTINUE THROUGH ATTIC TO UNDER SIDE OF ROOF SHEATHING. USE SAME WALL TYPE AS USED ON THIRD FLOOR. (DETAIL 1/S2.6) OR SHEAR "B" WHICHEVER IS GREATER.
  - STICK FRAME OVER ELEVATOR w/ 2x8 RAFTERS @ 16" o.c. ON CRIPPLE WALLS, ON SHAFT AND CORRIDOR.
  - DECK BELOW

- GENERAL STRUCTURAL NOTES:**
- HEIGHT OF TOP PLATE 9'-1" U.O.N.
  - STRUCTURAL MEMBER MATERIALS - GLB = 24F-V4 (DF) OR - CONT GLB = 24F-V8 (DF) OR - DBM = (3) 2x12 #1/#2 SPF OR 3-1/8x12 G.L.B. @ 12'-0" 12'-0" x 5-1/8x12' GLB 12'-0" x 20'-0" - HDR 6" SPAN 6'-0" (3)2x10" #1/#2 SPF - HDR 6'-1" SPAN 9'-0" (3)2x12" #1/#2 SPF
  - REFER TO SHEET S2.1 FOR ASSEMBLY OF BUILT-UP COLUMNS AND MULTIPLE LAMINATED VENEER (L.V.) MEMBERS.
  - TRUSSES ARE TO BE ALIGNED ON BOTH SIDES OF THE CORRIDOR. ADJUST SPACING OF TRUSSES AS REQUIRED.
  - PROVIDE ADDITIONAL TRUSS OVER SHEARWALLS THAT ARE PARALLEL TO TRUSSES.
  - ALL 36" DOOR HEADERS TO BE (3) 2x10 U.O.N.
  - REFER TO DTLS. #1 & #3 ON S2.3 FOR ALLOWABLE HOLES IN STRUC. MEMBERS. NO HOLES ARE TO BE PUT IN LVL MATERIALS WITHOUT ENGINEERS APPROVAL.
  - BOTTOM OF BEAM ELEVATION AT TOP PLATE U.O.N.
  - REFER TO DETAILS #4 & #9 ON S2.3 FOR HEADER DETAILS.
  - TOP PLATE CONTINUITY IN SHEAR AND LOAD-BEARING WALLS TO BE MAINTAINED PER DETAIL #14 ON S2.3.
  - PREFABRICATED PANELS CONNECTED PER DETAILS #10 & #14 ON S2.5.
  - ALL TRUSSES ARE @ 24" oc U.O.N.
  - BRACE TOP OF ALL INTERIOR NON-BEARING WALLS ACCORDING TO DETAIL 15/S2.5 AND 7/S3.3
  - ROOF AND FLOOR SHEATHING GRADE PER S2.1 AND NAILING REQUIREMENTS PER DETAIL 16/S2.5 SEE DETAIL #1/S3.3 FOR NAIL LOCATIONS
  - (2) 2x6 POST @ ALL GIRDER TRUSS BEARING (U.O.N.)
  - REFER TO 8/S3.0 FOR ELEC. PANEL FRAMING.
  - (3) 2x6 AT EA END OF DBM U.O.N.
  - ALL TRUSSES TO BE INSTALLED AND BRACED PER 'BCS' 1-03'

- GENERAL STRUCTURAL NOTES:**
- REFER TO DETAILS #4 & #9 ON S2.3 FOR HEADER DETAILS.
  - TOP PLATE CONTINUITY IN SHEAR AND LOAD-BEARING WALLS TO BE MAINTAINED PER DETAIL #14 ON S2.3.
  - PREFABRICATED PANELS CONNECTED PER DETAILS #10 & #14 ON S2.5.
  - ALL TRUSSES ARE @ 24" oc U.O.N.
  - BRACE TOP OF ALL INTERIOR NON-BEARING WALLS ACCORDING TO DETAIL 15/S2.5 AND 7/S3.3
  - ROOF AND FLOOR SHEATHING GRADE PER S2.1 AND NAILING REQUIREMENTS PER DETAIL 16/S2.5 SEE DETAIL #1/S3.3 FOR NAIL LOCATIONS
  - (2) 2x6 POST @ ALL GIRDER TRUSS BEARING (U.O.N.)
  - REFER TO 8/S3.0 FOR ELEC. PANEL FRAMING.
  - (3) 2x6 AT EA END OF DBM U.O.N.
  - ALL TRUSSES TO BE INSTALLED AND BRACED PER 'BCS' 1-03'

COLUMN SCHEDULE			
COL	MATERIAL	SIZE	BASEPLATE
C1	SPF #1/#2 OR BETTER	(2) 2x6 4x8	
C2	SPF #1/#2 OR BETTER	(3) 2x6 6x6	
C3	DFL #1	(4) 2x6 6x8	
C4	ASTM A500	3-1/2x3-1/2x1/4"	9-1/2"x0'-91/2"x3/4"
C5	ASTM A500	4x4x1/4"	10"x0'-10"x3/4"
C6	ASTM A500	4x4x5/16"	10"x0'-10"x3/4"
C7	ASTM A500	4x4x3/8"	10"x0'-10"x3/4"
C8	ASTM A500	5x5x3/8"	11"x0'-11"x3/4"
C9	ASTM A500	5x5x1/4"	11"x0'-11"x3/4"
C10	ASTM A500	6x6x5/16"	12"x12"x3/4"
C11	SPF #1/#2 OR BETTER	(4) 2x4 4x6	
C12	ASTM A500	8x8x1/4"	14"x14"x3/4"

JOIST SCHEDULE			
JOIST	MATERIAL	SIZE	SPACING
J-1	REDBUILT RED-I45	9-1/2" DEPTH	24" oc
J-2	REDBUILT RED-I90	18" DEPTH	24" oc
J-3	REDBUILT RED-I90	18" DEPTH	16" oc
J-4	REDBUILT RED-I90	DBL. 18" DEPTH	19.2" oc
J-5	REDBUILT RED-I90	18" DEPTH (multi-span)	24" oc
J-6	REDBUILT RED-I45	DBL. 9-1/2" DEPTH	16" oc
J-7	REDBUILT RED-I45	9-1/2" DEPTH	12" oc
J-8	REDBUILT RED-I90	DBL. 18" DEPTH	16" oc
J-9	REDBUILT RED-I90	DBL. 18" DEPTH	24" oc
CJ-1	SPF #1/#2	2x10	24" oc

RAFTER SCHEDULE			
RAFTER	MATERIAL	SIZE/SPAN*	SPACING
R-1	SPF #1/#2	2x12, 8'-6" SPAN	24" oc
R-2	SPF #1/#2	2x12, 11'-6" SPAN	16" oc
R-3	REDBUILT RED-I90	11-7/8" DEPTH	24" oc
R-4	REDBUILT RED-I90	DBL. 11-7/8" DEPTH	19.2" oc
R-5	SPF #1/#2	2x6, 7'-6" SPAN	24" oc

SHEARWALL SCHEDULE					
SHEARWALL MARK	SHT'G. TYPE & THICKNESS	SHT'G. NAIL INFO.	FLR. TO FLR. CONNECTION	SHEARWALL TO CONC. CONN.	
				ALL ANCHOR BOLTS TO BE 10"	ANCHOR BOLT DIA. & SPACING * oc
A	SPF	8d CLN 7"	24" 24"	6/S2.3	1/2" DIA @ 48"
B	7/16"	8d 6"	22" 22"	6/S2.3	1/2" DIA @ 36"
C	7/16"	8d 4"	14" 14"	6/S2.3	1/2" DIA @ 24"
D	7/16"	8d 12"	11" 11"	6/S2.3	1/2" DIA @ 10"
E	7/16"	8d 3"	8" 8"	6/S2.3	1/2" DIA @ 8"
F	7/16"	8d 2"	8" 8"	6/S2.6	5/8" DIA @ 12"
G	7/16"	8d 4"	7" 7"	7/S2.6	1/2" DIA @ 12"
H	7/16"	8d 2"	8" 8"	7/S2.6	1/2" DIA @ 10"
J	10x10"	2" 2"	8" 8"	7/S2.6	1/2" DIA @ 8"


NOTE: SHEARWALL TYPES "F" - "J" ARE ON BOTH SIDES OF WALL.

KEY NOTES:

- 3x STUDS AT ADJOINING PLYWD PANEL EDGES.
- 3x STUDS AND SILL PLATES. STAGGER PLYWD PANEL EDGES.
- 3x DFL STUDS AND SILL PLATES. STAGGER PLYWD PANEL EDGES.
- 5/8" GYPSUM SHEATHING TO BE SECURED WITH 6d COOLER NAILS OR #6-1" TYPE "W" OR "S" SCREWS DIRECTLY TO STUDS.
- PLYWD PANEL EDGES ARE TO BE STAGGERED TO FALL ON DIFFERENT FRAMING MEMBERS.
- NAILS ARE TO BE COMMON OR HOT DIPPED GALVANIZED U.O.N.
- 3x SILL PLATES REQUIRED AT FOUNDATION ONLY.

SHEAR PANEL NOTES:

- SHEAR WALLS ARE ADJUSTED FOR SPRUCE-PINE-FIR STUDS @ 16" oc U.O.N.
- ALL APA SHEATHING SHEARWALLS TO BE BACKED WITH 2" NOMINAL OR WIDER FRAMING.
- WHEN APA RATED PANELS ARE INSTALLED TO BOTH SIDES OF WALL JOINTS OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS.
- NAILING NOT TO PENETRATE THE OUTER VENEER LAYER.
- WHEN USING A NAIL GUN, CONTRACTOR SHALL ENSURE THAT GUN IS SET TO INSTALL NAIL SLIGHTLY PROUD OF SURFACE BEING NAILED. NAIL SHALL THEN BE SET BY HAMMER. DO NOT ALLOW NAIL TO OVER PENETRATE WOOD SURFACE ESPECIALLY ON SHEARWALLS.
- ALL EDGES ON APA RATED PANELS TO BE BLOCKED TO MAINTAIN STRENGTH.
- ALL PANELS LISTED MAY NOT BE USED ON ALL PROJECTS. REFER TO THE SHEARWALL LAYOUT PLANS FOR SIZE, TYPE AND LOCATION OF PANELS.
- GYPSUM WALLBOARD LOAD IS REDUCED IN HIGH SEISMIC LOCATIONS.
- SEE DETAIL #14/S2.5 FOR STAPLES TO NAIL EQUIVALENT TABLE.
- 7/16" OSB (PS2-S2 GRADE) MAY BE USED IF APPLIED DIRECTLY TO FRAMING WHEN STUDS ARE SPACED A MAXIMUM OF 16" o.c. OR PANELS ARE APPLIED WITH LONG DIMENSION ACROSS STUDS. 15/32 OSB SHALL BE USED WHEN STUDS ARE SPACED A MAXIMUM OF 24" o.c.
- USE EITHER 16d NAILS OR LTP4" CLIPS WHEN SHT'G IS ATTACHED TO LOWER TOP PLATE.
- ALL ANCHOR BOLTS AT SHEARWALLS TO HAVE A 3x3x1/4" THICK PLATE WASHER.



**lenity**  
architecture

3150 Letts Court, SE, Salem, Oregon 97302  
P-503 399 1090 F-503 399 0665 W-venityarchitecture.com

**COLSON AND COLSON**  
GENERAL CONTRACTOR, INC.  
2860 MCGILCHRIST STREET SE, SUITE 200  
SALEM, OREGON 97302  
PHONE (503) 586-7401

**PORTLAND**  
RETIREMENT RESIDENCE  
802 OCEAN AVE. PORTLAND, MAINE 04103

**3RD FLOOR**  
WING 'C'  
FRAMING PLAN

DATE  
8/28/2015

REVISED DATE  
9/22/2015

SHEET  
S1.9

**3RD FLOOR WING 'C' FRAMING PLAN**  
SCALE: 1/8"=1'-0"

NEW: 1/20/2015 10:43 AM Andrew.pdf: 1/20/2015 11:39 AM Jpendon... 3rd floor wing c framing plan.dwg: 81.3