2

R1.5

VAN GARAGE ROOF LAYOUT (TYP. 1)

Fasten Jack trusses to Corner girder with (2) 10d CWN on the top plus (1) on the bottom chord

1

R1.5

GARAGE ROOF LAYOUT (TYP. 1)

Fasten Jack trusses to Corner girder with (2) 10d CWN on the top plus (1) on the bottom chord

GENERAL N

- In any run of 10 or more truss
bracing, needs diagonal brace
feet). Diagonal brace should b
degrees, and should cross at le
-These truss plans are to be us
the job blueprints. If there are
please notify the truss designer.
-All hardware is specified as Simpson hardware. Equivalents are acceptable.
-If there are any questions, please phone Fred Vanheddegan at **(250) 874-3304**.

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 04/11/16

TRUSSES TO BE PLACED @ 2'-0" o/c UNLESS OTHERWISE NOTED!

ALL BEAMS SHOWN ON DRAWINGS ARE PROVIDED BY OTHERS AND ARE ONLY SHOWN FOR REFERENCE!
REFER TO ENGINEERED TRUSS SHOP DRAWINGS FOR BRACING REQUIREMENTS OF TRUSSES AND LOCATIONS.

NOTE: T1/T3 TYPE TRUSS WILL ACCOMADATE CANTILEVER CONDITION AND REGULAR BEARING.

NOTE: FOR TRUSS UPLIFT FOLLOW THE BELOW SCHEDULE:

0 - 600lbs = 1 - H2.5A

600 - 1200lbs = 2 - H2.5A

1200 - 3965lbs = MGT+HDU4

3965 - 10980lbs = HGT2+HTT22 (2)

HANGER SCHEDULE

- Simpson Hanger LUS24
- Simpson Hanger HUS26
- Simpson Hanger THASR/L29
- Simpson Hanger HGUS210-3
- Simpson Hanger HGUS210-2

Project Design Data:

Building Code	IBC2009/TPI2007			
Building Classification	Commercial			
Wind Loading	100 mph		Exposure B	
Typical Roof Loading	TCLL- 40 psf	TCDL- 7 psf	BCLL- 10 psf	BCDL- 10 psf
Mechanical Well Loading	TCLL- 40 psf	TCDL- 80 psf	BCLL- 10 psf	BCDL-10 psf

INLINE TRUSS

304 7th ST
CRANBROOK, BC Cell: 250-874-3304
E-mail: fredvan@inlinetruss.com

Project/Builder: **COLSON & COLSON**

Legal Address: **PORTLAND, ME**

Model: **PORTLAND RETIREMENT RESIDENCE**

Drawing Title: **GARAGE ROOF**

Scale:	Date:	Drawn By:	Job Number:
1/8" = 1'	23 SEPT 2015	FV	UXXX
Revision:	Date:	Comments:	Drawing Number:
00	23 SEPT 2015	FOR APPROVALS ONLY	R1.5