PANEL SCHEDULE

panel: E2 | mounting: SURFACE | location: STORAGE 249 | connected load amps: 83
voltage: 120/208 | phase: 3 | bus & main: 225A MLO | calculated load amps: 81

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
2	4TH FLR CORE RECEPT.	12	720	20/1	1	*	2	20/1	500	12	1ST FLR FIREPLACE	5
2	OFFICE RECEPT.	12	720	20/1	3	*	4	20/1	540	12	1ST FLR DINING RECEPT.	2
2	OFFICE RECEPT.	12	540	20/1	5	*	6	20/1	540	12	1ST FLR ACTIVITY RECEPT.	2
2	ELEVATOR MACHINE RM RECEPT	12	360	20/1	7	*	8	20/1	1000	12	AV CABINET	2
2	ELEVATOR PIT RECEPT.	12	180	20/1	9	*	10				SHUNT TRIP SPACE	
5	ELEV 1 SUMP PUMP	12	500	20/1	11		* 12	20/1	750	12	MEDIA RM. PROJECTOR	2
2	2ND FLR CORE RECEPT.	12	720	20/1	13	*	14	20/1	720	12	MEDIA RM. RECEPT	2
2	3RD FLR CORE RECEPT.	12	720	20/1	15	*	16	20/1	1200	12	F-3	5
5	AC-2 - FAN CONNECTION	10	1574	25/3	17		* 18	20/1	900	12	1ST FLR WING B RECEPT.	2
5	*	10	1574	*	19	*	20	20/1	900	12	2ND FLR WING B RECEPT.	2
5	*	10	1574	*	21	*	22	20/1	900	12	3RD FLR WING B RECEPT.	2
5	F-2	12	1620	20/1	23	*	24	20/1	900	12	4TH FLR WING B RECEPT.	2
5	F-2A	12	1620	20/1	25	*	26	20/1	360	12	ROOF RECEPT.	2
6	1ST FLR FIRE SMOKE DAMPERS	12	500	15/1	27	*	28	15/2	635	12	ELEVATOR DS-1A	5
6	2ND FLR FIRE SMOKE DAMPERS	12	500	15/1	29	*	30	*	635	12	*	5
6	3RD FLR FIRE SMOKE DAMPERS	12	500	15/1	31	*	32	25/3	1574	10	AC-1 - FAN CONNECTION	6
6	4TH FLR FIRE SMOKE DAMPERS	12	500	15/1	33	*	34	*	1574	10	*	6
	SPARE			20/1	35	*	36	*	1574	10	*	6
	SPARE			20/1	37	*	38	20/1	360	12	ROOF RECEPT.	2
	SPARE			20/1	39	*	40				SPACE	
	SPARE			20/1	41		* 42				SPACE	

Phase A	10908 VA	NOTES:	line-line voltage
Phase B	9043 VA		208
Phase C	10033 VA		largest motor (va)
Total Connected	29984 VA		

PANEL SCHEDULE

panel: E1 | mounting: RECESSED | location: OFFICE 168 | connected load amps: 126
voltage: 120/208 | phase: 3 | bus & main: 225A MLO | calculated load amps: 97

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
4	MICROWAVE OVEN - 72	12	1800	20/1	1	*	2	20/1	360	12	S.S. UTILITY DISTRIBUTION - 48	4
4	HOT WATER DISPENSER - 73	8	3150	40/2	3	*	4				SHUNT-TRIP SPACE	
4	*	8	3150	*	5	*	6	20/1	900	12	S.S. UTILITY DISTRIBUTION - 48	4
4	COFFEE BREWER - 74	8	3150	40/2	7	*	8				SHUNT-TRIP SPACE	
4	*	8	3150	*	9	*	10	25/3	1694	10	AC-3 - FAN CONNECTION	5
6	EF-1 (KITCHEN EXHAUST FAN)	12	1141	20/3	11	*	12	*	1694	10	*	5
6	*	12	1141	*	13	*	14	*	1694	10	*	5
6	*	12	1141	*	15	*	16	20/1	500	12	EMS CONTROL PANEL	4
4	MAKE-UP AIR SUPPLY FAN	12	1694	20/3	17	*	18	20/1	1127	12	ICE MACHINE - 69	4
6	*	12	1694	*	19	*	20	20/1			SPARE	
6	*	12	1694	*	21	*	22	20/1	480	12	GRILL - 42	4
6	F-1	12	1662	20/1	23	*	24				SHUNT-TRIP SPACE	
4	CONVECTION OVEN - 47	12	1080	20/1	25	*	26	20/3	578	12	COOLER COMPRESSOR - 7A	4
	SHUNT-TRIP SPACE				27	*	28	*	578	12	*	4
4	CONVECTION OVEN - 47	12	1080	20/1	29	*	30	*	578	12	*	4
	SHUNT-TRIP SPACE				31	*	32	25/3	829	12	FREEZER COMPRESSOR - 5A	4
4	FREEZER HEAT TRACE - 5A	12	1000	20/1	33	*	34	*	829	12	*	4
4	FREEZER EVAPORATOR - 5A	12	1040	20/2	35	*	36	*	829	12	*	4
4	*	12	1040	*	37	*	38	20/1	360	12	COOLER/FREEZER ALARM - COV	4
4	COOLER EVAPORATOR - 5A	12	437	20/2	39	*	40	20/1	1200	12	FREEZER DOOR HTR. - 5	4
4	*	12	437	*	41	*	42	20/1	420	12	WALK-INS LTS. - 5	4

Phase A	13726 VA	NOTES:	line-line voltage
Phase B	15853 VA		208
Phase C	15782 VA		largest motor (va)
Total Connected	45361 VA		0 M

PANEL SCHEDULE

panel: E | mounting: SURFACE | location: ELEC. 176 | connected load amps: 324
voltage: 120/208 | phase: 3 | bus & main: 400A BUS 350A MAIN | calculated load amps: 291

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
6	1ST FLR FIRE SMOKE DAMPERS	12	840	15/1	1	*	2	20/1	900	12	1ST FLR WING B RECEPT.	2
6	2ND FLR FIRE SMOKE DAMPERS	12	840	15/1	3	*	4	20/1	900	12	2ND FLR WING B RECEPT.	2
6	3RD FLR FIRE SMOKE DAMPERS	12	840	15/1	5	*	6	20/1	900	12	3RD FLR WING B RECEPT.	2
6	4TH FLR FIRE SMOKE DAMPERS	12	840	15/1	7	*	8	15/1	384	12	WATER HEATER +	5
	SPACE				9	*	10	15/1	384	12	WATER HEATER +	5
	SPACE				11	*	12	15/1	384	12	WATER HEATER +	5
	SPACE				13	*	14	15/1	150	12	RECIRCULATION PUMP	6
	SPACE				15	*	16	20/1	500	12	MIXING VALVE	5
	SPACE				17	*	18	15/1			SPARE	
2	TELEPHONE BOARD RECEPT.	12	180	20/1	19	*	20	20/1	900	12	ELEC/MECH RM RECEPT.	2
2	TELEPHONE BOARD RECEPT.	12	180	20/1	21	*	22	20/2	900	12	SPRINK. SYSTEM AIR COMP.	5
	SPACE				23	*	24	*	900	12	*	5
	SPACE				25	*	26	20/1	900	12	4TH FLR WING B RECEPT.	2
5	DATA CABINET	12	500	20/1	27	*	28	20/1			SPARE	
	SPACE				29	*	30	20/1			SPARE	
	SPACE				31	*	32	150/3	11222	1/0	PANEL EM2	8
	SPACE				33	*	34	*	10617	1/0	*	8
	SPACE				35	*	36	*	9987	1/0	*	8
8	PANEL EM1	3/0	13726	200/3	37	*	38	XXX3	8983		ELEVATOR	6
8	*	3/0	15853	*	39	*	40	*	8983		*	6
8	*	3/0	15782	*	41	*	42	*	8983		*	6

Phase A	39025 VA	NOTES:	line-line voltage
Phase B	39657 VA		208
Phase C	37776 VA	+ PROVIDE LOCK-ON/OFF DEVICE	largest motor (va)
Total Connected	116458 VA		0

PANEL SCHEDULE

panel: EM | mounting: SURFACE | location: ELEC 183 | connected load amps: 152
voltage: 120/208 | phase: 3 | bus & main: 225A BUS 225A MAIN | calculated load amps: 170

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
1	CORE LIGHTS (1ST)	10	886	20/1	1	*	2	20/1	500	12	ELEVATOR 2 CAB LIGHTS	1
1	REAR BLDG EGRESS LIGHTING	10	766	20/1	3	*	4	20/1	1185	10	WING B LIGHTS (2ND/STAIRS)	1
1	ELEVATOR 1 PIT LIGHTS	12	64	20/1	5	*	6	20/1	1190	10	WING B LIGHTS (1ST/STAIRS)	1
1	ELEV. 1 EQUIP RM LIGHTS	12	64	20/1	7	*	8	20/1	768	10	CORE LIGHTS (1ST)	1
1	FRONT BLDG EGRESS LIGHTING	10	434	20/1	9	*	10	20/1	1241	10	CORE LIGHTS (2ND/STAIRS)	1
5	E-CALL REMOTE HEADEND	12	500	20/1	11	*	12	20/1	1218	12	ACTIVITY LIGHTING	1
1	KITCHEN LIGHTS	12	741	20/1	13	*	14	20/1	512	12	MECH./ELEC ROOM LIGHTS	1
2	EMERGENCY CALL RECEPT	12	180	20/1	15	*	16	20/1	500	12	SILVERSPHERE PANEL	6
2	FIRE ALARM EQUIPMENT	12	500	20/1	17	*	18	20/1	500	12	FIRE ALARM PANEL	6
6	AUTOMATIC DOOR	12	500	20/1	19	*	20	20/1	500	12	GENERATOR CHARGER	6
6	AUTOMATIC DOOR	12	500	20/1	21	*	22	20/1	500	12	GENERATOR BLOCK HEATER	3
6	AUTOMATIC DOOR	12	250	20/1	23	*	24	20/1	1092	12	DINING LIGHTS	1
1	DINING LIGHTS	12	900	20/1	25	*	26	20/1	1210	12	FOYER LIGHTS	1
1	THEATER ZONE 4 LIGHTS	12	104	20/1	27	*	28	20/1	500	12	KITCHEN FIRE SUPRESSION	6
1	ELEVATOR 1 CAB LIGHTS	12	500	20/1	29	*	30	20/1	500	12	AREA OF RESCUE PANEL	5
1	WING C LIGHTS (1ST/STAIRS)	10	724	20/1	31	*	32	20/1	624	12	CORE RESTROOMS	1
1	WING C LIGHTS (2ND/STAIRS)	10	668	20/1	33	*	34	20/1	1464	12	DINING LIGHTS	1
1	THEATER ZONE 5 LIGHTS	12	144	20/1	35	*	36	20/1	1397	12	FOYER/OFFICE LIGHTS	1
1	THEATER ZONE 1,2,3,6 LIGHTS	12	1250	20/1	37	*	38	20/1			SPARE	
6	AUTOMATIC DOOR	12	250	20/1	39	*	40	20/1			SPARE	
6	AUTOMATIC DOOR	12	250	20/1	41	*	42	20/1			SPARE	

Phase A	9179 VA	NOTES:	line-line voltage
Phase B	8292 VA	PROVIDE FEED THROUGH LUGS	208
Phase C	8103 VA		largest motor (va)
Total Connected	25574 VA		0

PANEL SCHEDULE

panel: GAR | mounting: SURFACE | location: VAN GAR | connected load amps: 25
voltage: 208Y/120V | phase: 3 | bus & main: 125A BUS 60A/3P MAIN | calculated load amps: 27

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
1	VAN GARAGE LIGHTS	12	887	20/1	1	*	2	20/1	900	12	VAN GARAGE DOOR OPENER	6
2	VAN GARAGE RECEPT.	12	540	20/1	3	*	4	20/1	900	12	VAN GARAGE DOOR OPENER	6
2	VAN GARAGE RECEPT.	12	540	20/1	5	*	6	20/1	900	12	VAN GARAGE DOOR OPENER	6
	SPACE					*	8	20/1	500	12	EXTERIOR LTG CONTROLLER	2
	SPACE					*	10				SPACE	
	SPACE					*	12				SPACE	
1	SITE SIGN LIGHTING	8	372	20/1	13	*	14				SPACE	
1	SITE LIGHTS - T	8	840	20/1	15	*	16				SPACE	
2	RECEPT. ON T FIXTURE	8	900	20/1	17	*	18				SPACE	
1	SITE LIGHTS - T	8	840	20/1	19	*	20				SPACE	
2	RECEPT. ON T FIXTURE	8	900	20/1	21	*	22				SPACE	
	SPARE				20/1	23	*	24			SPACE	

Phase A	3499 VA	NOTES:	line-line voltage
Phase B	3180 VA		208
Phase C	3240 VA		largest motor (va)
Total Connected	9019 VA		0

PANEL SCHEDULE

panel: K1 | mounting: RECESSED | location: OFFICE 168 | connected load amps: 173
voltage: 120/208 | phase: 3 | bus & main: 225A MLO | calculated load amps: 125

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
4	COFFEE BAR - CVO	12	180	20/1	1	*	2	15/2	1000	12	FCU-1	6
4	COFFEE WARMER - 77	12	1800	20/1	3	*	4	*	1000	12	*	6
4	PLATE LOWERATOR - 64	12	750	20/1	5	*	6	15/2	1000	12	FCU-2	6
4	PLATE LOWERATOR - 64	12	875	20/1	7	*	8	*	1000	12	*	6
4	PLATE LOWERATOR - 64	12	750	20/1	9	*	10	40/3	2834	8	STEAMER - 46	4
4	WARMING DRAWER - 60	12	900	20/1	11	*	12	*	2834	8	*	4
4	SLICER - 29	12	1176	20/1	13	*	14	*	2834	8	*	4
4	MOBILE REFRIGERATOR - 55	12	1080	20/1	15	*	16				SHUNT-TRIP SPACE	
4	HOT WELLS - 61	6	4004	50/2	17	*	18	30/1	1920	10	30 QT. MIXER - 31	4
4	*	6	4004	*	19	*	20				SHUNT-TRIP SPACE	
4	HEAT LAMP - 61	12	800	20/2	21	*	22	15/1	528	12	DISHWASHER EXHAUST FAN	6
4	*	12	800	*	23	*	24	20/2	468	12	DISPOSAL UNIT - 21	4
4	TOASTER - 59	12	1664	20/2	25	*	26	*	468	12	*	4
4	*	12	1664	*	27	*	28	20/1			SPARE	
4	REFRIGERATED TABLE - 65	12	1080	20/1	29	*	30	30/3	2450	10	BOOSTER - 17	4
4	U/C FREEZER - 66	12	888	20/1	31	*	32	*	2450	10	*	4
2	MECHANICAL WELL RECEPT.	12	180	20/1	33	*	34	*	2540	10	*	4
3	HEAT TAPE	12	1200	20/1	35	*	36	30/3	2991	10	DISHWASHER - 17	4
3	EDH-1	10	1667	20/2	37	*	38	*	2991	10	*	4
3	*	10	1667	*	39	*	40	*	2991	10	*	4
3	*	10	1667	*	41	*	42	20/1	1184	12	KITCHEN LIGHTS	1

Phase A	21197 VA	NOTES:	line-line voltage
Phase B	17834 VA		208
Phase C	23248 VA		largest motor (va)
Total Connected	62279 VA		0

PANEL SCHEDULE

panel: W4G | mounting: RECESSED | location: LAUNDRY 460 | connected load amps: 53
voltage: 208Y/120V | phase: 3 | bus & main: 225A MLO | calculated load amps: 54

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
7	#433 B - LIGHTS	12	600	20/1	1	*	2	20/1	1000	12	WASH. MACHINE	5
7	LIGHTS	12	600	20/1	3	*	4	20/1	1000	12	WASH. MACHINE	5
7	BATH RECEPT.	12	180	20/1	5	*	6	20/1	1000	12	GAS DRYER	5
7	MISC. RECEPT.	12	875	20/1	7	*	8	20/1	1000	12	GAS DRYER	5
7	MISC. RECEPT.	12	900	20/1	9	*	10	20/1	540	12	LAUNDRY/LINEN RECEPT.	2
7	PTAC	12	1410	20/2	11	*	12	20/1	688	12	LAUNDRY/LINEN/STOR LIGHTS/	1
7	*	12	1410	*	13	*	14	20/1	542	12	#429 A - LIGHTS	7
7	BASEBOARD	12	1000	20/1	15	*	16	20/1	180	12	BATH RECEPT.	7
2	LINEN RECEPT.	12	540	20/1	17	*	18	20/1	900	12	MISC RECEPT.	7
3	CORRIDOR WALL HEATER	12	1000	20/1	19	*	20	20/1	900	12	MISC RECEPT.	7
	SPACE				21	*	22	20/2	1410	12	PTAC	7
	SPACE				23	*	24	*	1410	12	*	7
	SPACE				25	*	26	20/1			SPARE	
	SPACE				27	*	28	20/1			SPARE	
	SPACE				29	*	30	20/1			SPARE	
	SPACE				31	*	32				SPACE	
	SPACE				33	*	34				SPACE	
	SPACE				35	*	36				SPACE	
	SPACE				37	*	38				SPACE	
	SPACE				39	*	40				SPACE	
	SPACE				41	*	42				SPACE	

Phase A	7327 VA	NOTES:	line-line voltage
Phase B	5630 VA		208
Phase C	6128 VA		largest motor (va)
Total Connected	19085 VA		0

PANEL SCHEDULE

panel: W4C | mounting: RECESSED | location: LAUNDRY 454 | connected load amps: 81
voltage: 208Y/120V | phase: 3 | bus & main: 225A MLO | calculated load amps: 82

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
7	#420 B - LIGHTS	12	500	20/1	1	*	2	20/1	1000	12	WASH. MACHINE	5
7	LIGHTS	12	500	20/1	3	*	4	20/1	1000	12	WASH. MACHINE	5
7	BATH RECEPT.	12	180	20/1	5	*	6	20/1	1000	12	GAS DRYER	5
7	MISC. RECEPT.	12	720	20/1	7	*	8	20/1	1000	12	GAS DRYER	5
7	MISC. RECEPT.	12	720	20/1	9	*	10	20/1	540	12	LAUNDRY RECEPT.	2
7	PTAC	12	1410	20/2	11	*	12	20/1	815	12	LAUN/LINEN/STOR LIGHTS/EF	1
7	*	12	1410	*	13	*	14	20/1	542	12	#421 A - LIGHTS	7
7	BASEBOARD	12	1000	20/1	15	*	16	20/1	180	12	BATH RECEPT.	7
7	#412 B - LIGHTS	12	500	20/1	17	*	18	20/1	900	12	MISC RECEPT.	7
7	LIGHTS	12	500	20/1	19	*	20	20/1	900	12	MISC RECEPT.	7
7	BATH RECEPT.	12	180	20/1	21	*	22	20/2	1410	12	PTAC	7
7	MISC. RECEPT.	12	720	20/1	23	*	24	*	1410	12	*	7
7	MISC. RECEPT.	12	720	20/1	25	*	26	20/1	876	10	WING B LIGHTS (1ST)	1
7	PTAC	12	1410	20/2	27	*	28	20/1	876	10	WING B LIGHTS (2ND)	1
7	*	12	1410	*	29	*	30	20/1	876	10	WING B LIGHTS (3RD)	1
7	BASEBOARD	12	1000	20/1	31	*	32	20/1	876	10	WING B LIGHTS (4TH)	1
	SPARE				20/1	33	*	34	20/1	900	12	MISC. RECEPT.	7
	SPARE				20/1	35	*	36	20/2	1410	12	PTAC	7
	SPACE					37	*	38	*	1410	12	*	7
	SPACE					39	*	40	20/1	750	12	BASEBOARD	7
	SPACE					41	*	42	20/1	540	12	LINEN/STOR RECEPT.	2

Phase A	10899 VA	NOTES:	line-line voltage
Phase B	9520 VA		208
Phase C	10970 VA		largest motor (va)
Total Connected	31389 VA		0

PANEL SCHEDULE

panel: W4D | mounting: RECESSED | location: LAUNDRY 454 | connected load amps: 87
voltage: 208Y/120V | phase: 3 | bus & main: 225A MLO | calculated load amps: 87

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
7	#411 B - LIGHTS	12	600	20/1	1	*	2	20/1	542	12	#409 A - LIGHTS	7
7	LIGHTS	12	600	20/1	3	*	4	20/1	180	12	BATH RECEPT.	7
7	BATH RECEPT.	12	180	20/1	5	*	6	20/1	900	12	MISC RECEPT.	7
7	MISC. RECEPT.	12	875	20/1	7	*	8	20/1	900	12	MISC RECEPT.	7
7	MISC. RECEPT.	12	900	20/1	9	*	10	20/2	1410	12	PTAC	7
7	PTAC	12	1410	20/2	11	*	12	*	1410	12	*	7
7	*	12	1410	*	13	*	14	20/1	542	12	#404 A - LIGHTS	7
7	BASEBOARD	12	1000	20/1	15	*	16	20/1	180	12	BATH RECEPT.	7
7	#410 B - LIGHTS	12	500	20/1	17	*	18	20/1	900	12	MISC RECEPT.	7
7	LIGHTS	12	500	20/1	19	*	20	20/1	900	12	MISC RECEPT.	7
7	BATH RECEPT.	12	180	20/1	21	*	22	20/2	1410	12	PTAC	7
7	MISC. RECEPT.	12	720	20/1	23	*	24	*	1410	12	*	7
7	MISC. RECEPT.	12	720	20/1	25	*	26	20/1	876	10	WING B LIGHTS (5TH)	1
7	PTAC	12	1410	20/2	27	*	28	20/1	600	12	LIGHTS	7
7	*	12	1410	*	29	*	30	20/1	180	12	BATH RECEPT.	7
7	BASEBOARD	12	1000	20/1	31	*	32	20/1	900	12	MISC. RECEPT.	7
	SPARE				20/1	33	*	34	20/1	900	12	MISC. RECEPT.	7
	SPARE				20/1	35	*	36	20/2	1410	12	PTAC	7
	SPACE					37	*	38	*	1410	12	*	7
	SPACE					39	*	40	20/1	750	12	BASEBOARD	7
	SPACE					41	*	42	20/1	540	12	LINEN/STOR RECEPT.	2

Phase A	8130 VA	NOTES:	line-line voltage
Phase B	7930 VA		208
Phase C	5622 VA		largest motor (va)
Total Connected	21682 VA		0

PANEL SCHEDULE

panel: W4A | mounting: RECESSED | location: CORRIDOR 453 | connected load amps: 60
voltage: 208Y/120V | phase: 3 | bus & main: 225A MLO | calculated load amps: 60

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
7	#416 B - LIGHTS	12	500	20/1	1	*	2	20/1	600	12	#415 B - LIGHTS	7
7	LIGHTS	12	500	20/1	3	*	4	20/1	600	12	LIGHTS	7
7	BATH RECEPT.	12	180	20/1	5	*	6	20/1	180	12	BATH RECEPT.	7
7	MISC. RECEPT.	12	720	20/1	7	*	8	20/1	900	12	MISC. RECEPT.	7
7	MISC. RECEPT.	12	720	20/1	9	*	10	20/1	900	12	MISC. RECEPT.	7
7	PTAC	12	1410	20/2	11	*	12	20/2	1410	12	PTAC	7
7	*	12	1410	*	13	*	14	*	1410	12	*	7
7	BASEBOARD	12	1000	20/1	15	*	16	20/1	1000	12	BASEBOARD	7
3	CORRIDOR WALL HEATER	12	1000	20/2	17	*	18	20/1	542	12	#414 A - LIGHTS	7
3	*	12	1000	*	19	*	20	20/1	180	12	BATH RECEPT.	7
2	CORRIDOR RECEPT	12	900	20/1	21	*	22	20/1	900	12	MISC RECEPT.	7
	SPARE				20/1	23	*	24	20/1	900	12	MISC RECEPT.	7
	SPACE				20/1	25	*	26	20/2	1410	12	PTAC	7
	SPACE				20/1	27	*	28	*	1410	12	*	7
	SPACE					29	*	30				SPACE	
	SPACE					31	*	32				SPACE	
	SPACE					33	*	34				SPACE	
	SPACE					35	*	36				SPACE	
	SPACE					37	*	38				SPACE	
	SPACE					39	*	40				SPACE	
	SPACE					41	*	42				SPACE	

Phase A	8465 VA	NOTES:	line-line voltage
Phase B	7310 VA		208
Phase C	4802 VA		largest motor (va)
Total Connected	20577 VA		0

PANEL SCHEDULE

panel: W4H | mounting: RECESSED | location: CORRIDOR 459 | connected load amps: 54
voltage: 208Y/120V | phase: 3 | bus & main: 225A MLO | calculated load amps: 54

	service	w/re	va	a/p	no.	a b c	no.	a/p	va	w/re	service	
7	#430 B - LIGHTS	12	500	20/1	1	*	2	20/1	600	12	#431 B - LIGHTS	7
7	LIGHTS	12	500	20/1	3	*	4	20/1	600	12	LIGHTS	7
7	BATH RECEPT.	12	180	20/1	5	*	6	20/1	180	12	BATH RECEPT.	7
7	MISC. RECEPT.	12	720	20/1	7	*	8	20/1	900	12	MISC. RECEPT.	7
7	MISC. RECEPT.	12	720	20/1	9	*	10	20/1	900	12	MISC. RECEPT.	7
7	PTAC	12	1410	20/2	11	*	12	20/2	1410	12	PTAC	7
7	*	12	1410	*	13	*	14	*	1410	12	*	7
7	BASEBOARD	12	1000	20/1	15	*	16	20/1	1000	12	BASEBOARD	7
3	CORRIDOR WALL HEATER	12	1000	20/2	17	*	18	20/1	542	12	#439 A - LIGHTS	7
3	*	12	1000	*	19	*	20	20/1	180	12	BATH RECEPT.	7
2	CORRIDOR RECEPT	12	900	20/1	21	*	22	20/1	900	12	MISC RECEPT.	7
	SPARE				20/1	23	*	24	20/1	900	12	MISC RECEPT.	7
	SP