DN01 **DO NOT** cut, notch or drill flanges

F06

F07-C

F07

B1

B10-A

Multi-Ply 1-3/4" Versa-Lam® - TrussLok® Connection
2 rows @ 24" o.c.

- All TrussLok® screws may be installed from one side of multi-ply Versa-Lam® beams.
- Bring underside of washer-head flush with wood surface. Do not countersink.

OJ-A

Boise I-Joist can be offset up to 3" to avoid vertical plumbing.

Products				
PlotID	Net Qty	Product	Length	Plies
FB1	2	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	32' 0"	1
FB2	2	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	20' 0"	1
FB3-2	4	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	20' 0"	2
FB4-2	4	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	14' 0"	2
FJ1	11	11-7/8" BCI® 60s-2.0 SP	20' 0"	1
FJ2	6	11-7/8" BCI® 60s-2.0 SP	10' 0"	1
FJ3	6	11-7/8" BCI® 60s-2.0 SP	8' 0"	1

Connector Summary				
PlotID	Qty	Manuf	Product	Flange
H1	4	NA	HHUS410	None
H2	18	NA	IUS2.37/11.88	None

DESIGN CRITERIA

DEFLECTION LIMITS		FLOOR LOADS	
Live Load	L/480	Live Load	40 psf
Total Load	L/240	Dead Load	10 psf

Design assumes 4% load sharing and sheathing is glued and nailed

Boise Cascade now offers:

Trex Elevations™
STEEL DECK FRAMING

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/26/13

Boise C

SALES PRESENTATION DRAWING
No structural or dimensional check has been made of this design drawings of the building, therefore purchaser is to check and approve all dimsensions, quantities, loads, and details carefully. This drawing has not been check by Boise Engineering.

760 Ocean Ave
Portland, ME

Hancock Lumber

BC FRAMER

File:12589

By: JMP

Date: 02/25/2013

Boise Cascade
270 Ocean Rd
Greenland, NH 03840

Sheet: 1/1