Truss Connector Total List		
Manuf	Product	Qty
	HUS28	23

truss Conectors / hangers
HUS 28
6-16d hanger
4-10d truss

ROOF TRUSS LAYOUT

SCALE: 1/4" = 1'-0"

TRUSSES @ 24"o.c. (MAX)

APPROVED TRUSS ANCHOR BY OTHERS

VALLEY DETAIL

APPROVAL REQUIRED.
NOT FOR CONSTRUCTION.

JOB SPECIFIC NOTES

A) ANY FRAMING NOT SHOWN ON THIS LAYOUT IS BY OTHERS.

B) ANY CONNECTION NOT SHOWN ON THIS LAYOUT IS BY OTHERS.

C) HANGERS SUPPLIED BY BOISE CASCADE ARE MANUFACTURED BY USP.

Roof Truss Layout
A-10

GENERAL NOTES:

1) FOR BRACING REQUIREMENTS & ERECTION INFORMATION SEE T.P.I. PUBLICATION BCSI-B2.

2) BRACING STOCK (2x4 MIN) NOT SUPPLIED BY BOISE CASCADE.

3) SEE TRUSS ENGINEERING FOR ADDITIONAL INFORMATION.

4) ALL DIMENSIONS, DESIGN LOADS & TRUSS QUANTITIES MUST BE VERIFIED PRIOR TO FABRICATION.

5) ADDITIONAL FRAMING AS REQUIRED BY OTHERS.

6) THIS DRAWING IS INTENDED TO SERVE AS A LAYOUT GUIDE FOR THE TRUSS ERECTION CREW TO ENSURE PROPER PLACEMENT & SPACING OF TRUSSES. THIS IS NOT A COMPLETE FRAMING PLAN.

7) FINAL APPROVAL OF THIS LAYOUT & THE TRUSS COMPONENTS TO BE SUPPLIED FOR COMPLIANCE WITH PROJECT SPECIFICATIONS REMAINS THE RESPONSIBILITY OF THE ARCHITECT & ENGINEER OF RECORD.

8) VALLEY BY CONTRACTOR; VALLEY MUST BE FRAMED TO ENSURE UNIFORM DISTRIBUTION OF LIVE & DEAD LOADS. TOP CHORDS OF THE TRUSSES BELOW MUST BE LATERALLY BRACED BY MEANS OF SHEATHING OR PURLINS @ 24"O.C. MAX.

9) SOME HANGERS AND UPLIFT CONNECTORS CANNOT BE PROPERLY INSTALLED AFTER SETTING TRUSSES AND/OR ROOF SHEATHING.

10) BOISE CASCADE WILL ASSUME NO RESPONSIBILITY FOR ANY DEVIATION FROM THE CONTENT OF THESE DRAWINGS WITH REGARDS TO ANY STRUCTURAL MEMBERS THAT ARE MADE WITHOUT WRITTEN AUTHORIZATION FROM BOISE CASCADE.

11) BOISE CASCADE WILL NOT ACCEPT ANY BACK CHARGES FOR REPAIRS OR MODIFICATIONS WITHOUT NOTIFICATION PRIOR TO WORK BEING DONE WITHOUT REASONABLE OPPORTUNITY TO REVIEW PROBLEM. BACK CHARGES MUST BE AGREED UPON BY ALL PARTIES PRIOR TO WORK BEING DONE.

Reviewed for Code Compliance
Inspection Services
Department of Public Safety
Date: 10/05/17

JOB #: 688107

1/1

DRAWN BY: BvB

SCALE: 1/4" = 1'-0"

DATE: 07/12/2017
REVISED: 9/19/2017

CUSTOMER: HAMMOND LUMBER

JOB NAME: JAKE SMALL/CHRIS FNL

ADDRESS: PORTLAND, ME.

LOADING CHART (psf)

TCLL = 46.2
(60# Ground Snow)
TCDL = 10.0
BCLL = 0.0
BCDL = 10.0

DIMENSION KEY

Feet Inches
12 6 8
Sixteenths

Boise Cascade Materials Distribution
"Structural Solutions"
20 Pomerleau Street
Biddeford, Maine 04005
PH 1-877-291-5276
FX 1-877-782-0999