

# Colby & Associates

## Daniel P. Colby

P O Box 125 ♦ Wiscasset, Maine 04578  
Phone (207)-882-9742 ♦ Fax (207)-882-9742

### General Notes

- 1) Property Information as supplied by owner, applicant, or representative. Therefore such information shall be verified as correct by the owner or applicant prior to signing the application. Property lines not shown herein are considered to be more than 50' from the disposal area.
- 2) Fill to be free of foreign debris and coarse sand to gravelly coarse sand texture with 4 - 8% passing a #200 sieve and shall contain less than 5% by volume of rocks greater than 3" in size. The top 4" in cover material to be suitable for the establishment of good vegetative cover and seeded or covered with a layer of 3" to 6" wood chips. If wood chips are to be used they shall be maintained to prevent erosion.
- 3) Work to be done in accordance with the rules.
- 4) No wells were apparent within 100' of the disposal area. Owner to verify before signing this application.
- 5) All work on disposal area to be performed under dry conditions.
- 6) Minimum separation distances required (unless reduced by variance)

Any well to disposal area.....	100'
Any well to septic tank.....	100'
Septic tank to foundation .....	8'
Septic Field to Full Foundation.....	20'
Septic Field to Slab or Frost Wall.....	15'

Other separation distances as per rules.
- 7) Fill shall be placed in 8" compacted lifts.
- 8) Remove vegetation and scarify original soil under entire disposal area and fill extensions before placing fill. Bottom 4" of fill shall be mixed with original ground to improve infiltration.
- 9) This Site Evaluation has been done in compliance with the Maine State Plumbing Code. The approval and or design may be subject to more restrictive local ordinances. The Local Plumbing inspector should be contacted for final review and approval.
- 10) Any questions should be directed to Daniel P. Colby at the above address .