 Agility#: Quote#: 692942

Boise Cascade Building Materials Distribution
Boise Structural Solutions

68 Industrial Park Rd
Saco Me, 04072

Tel: 877-291-5276
Fax: 877-782-0999

Customer: MEAU00 - HAMMOND LUMBER LMC 0114

282 POLAND ROAD
AUBURN, ME04210

Contact: KEVIN HACKETT
Email: KHACKETT@HAMMONDLUMBER.COM
Phone: (207)-7844009 Fax: (207)-7827780

Job Name: BRUSH & HAMMER -- CARSON

ICE POND RD
PORTLAND, ME

RESURGAM CITY OF PORTLAND, MAINE
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 04/05/18

Prepared By:	Date Quoted:	Delivery Date:	Last Revised:	Price Protected Until:
SAMANTHA EXT 2761	01/19/2018			**01/26/2018**

ROOF TRUSSES **Designed per: IBC2009/TPI2007 Code.**

PROFILE	LBL	QTY / PLY	OVRALL LGTH / WEIGHT	NET SPAN	PITCH TOP	PITCH BOT	TYPE	SPC	OVERHANG LEFT	OVERHANG RIGHT	CUT	LOADING TLL-TDL-BLL-BDL / Heel Height Left	Heel Height Right	CANTILEVER LEFT	CANTILEVER RIGHT	BRG SIZE LEFT	BRG SIZE RIGHT		
A692942-0001	001	1	22-00-00	22-00-00	7.00	0.00	GESI	24	00-00-00	00-00-00	P	46.2-10-0-10 Grnd Snow=60		00-00-00	00-00-00	20-00-00	00-00-00		
		1	87 lbs									00-06-00	00-06-00			**BRG#:**	1		
A692942-0002	002	2	22-00-00	20-00-00	7.00	0.00	COMMON	24	00-00-00	00-00-00	P	46.2-10-0-10 Grnd Snow=60		01-00-00	01-00-00	00-05-08	00-05-08		
		1	84 lbs									00-06-00	00-06-00			**BRG#:**	2		
A692942-0003	003	2	36-00-00	34-00-00	7.00	0.00	GESTR	24	00-00-00	00-00-00	P	46.2-10-0-10 Grnd Snow=60		01-00-00	01-00-00	00-05-08	00-05-08		
		1	283 lbs									00-06-00	00-06-00			**BRG#:**	2		
A692942-0004	004	9	36-00-00	34-00-00	7.00	0.00	FINK	24	00-00-00	00-00-00	P	46.2-10-0-10 Grnd Snow=60		01-00-00	01-00-00	00-05-08	00-05-08		
		1	170 lbs									00-06-00	00-06-00			**BRG#:**	2		
A692942-0006	006	1	29-06-00	29-06-00	7.00	0.00	GESI	24	00-00-00	00-00-00	P	46.2-10-0-10 Grnd Snow=60		00-00-00	00-00-00	29-06-00	00-00-00		
		1	154 lbs									00-06-00	00-06-00			**BRG#:**	1		
A692942-0007	007	9	29-06-00	27-06-00	7.00	0.00	COMMON	24	00-00-00	00-00-00	P	46.2-10-0-10 Grnd Snow=60		01-00-00	01-00-00	00-05-08	00-05-08		
		1	129 lbs									00-06-00	00-06-00			**BRG#:**	2		

Total Weight: 3666 lbs

Report Date/Time: 1/19/2018 1:02:47 PM

Boise Cascade
Building Materials
Distribution
Boise Structural Solutions

68 Industrial Park Rd
Saco Me, 04072

Tel: 877-291-5276
Fax: 877-782-0999

Customer: MEAU00 - HAMMOND LUMBER LMC 0114

282 POLAND ROAD
AUBURN, ME04210

Contact: KEVIN HACKETT
Email: KHACKETT@HAMMONDLUMBER.COM
Phone: (207)-7844009 Fax: (207)-7827780

Job Name: BRUSH & HAMMER -- CARSON

ICE POND RD
PORTLAND, ME

CITY OF PORTLAND, MAINE RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 04/05/18

Prepared By:	Date Quoted:	Delivery Date:	Last Revised:	Price Protected Until:
SAMANTHA EXT 2761	01/19/2018			**01/26/2018**

Quote Source: BSS PLAN TAKE OFF

Job Notes To Customer:

Plan Date:

Special Instructions For Design:

SUB-TOTAL:	
DISCOUNTS:	
GRAND TOTAL:	

****** QUANTITY CHANGES WILL EFFECT PRICES* MAXIMUM UNLOADING TIME IS 1 HOUR***
TRUSS SYMBOLS CONCEPTUAL ONLY NOT FOR DESIGN
****** ALL TRUSSES ARE CUSTOM BUILT AND CANNOT BE RETURNED**
UNLESS SPECIFICALLY NOTED ON THIS QUOTE PRICE DOES NOT INCLUDE:
TREATED LUMBER, SEALED LAYOUTS, BRACING AND / OR HANDLING DRAWINGS
METAL HARDWARE, ENGINEERED LUMBER (LVL,I-JOISTS, ETC.)

BSS PHONES NOW FULLY OPERATIONAL, YOU MAY NOW DIAL ASSOCIATE NUMBERS DIRECT.
SORRY IT TOOK SO LONG AND FOR THE INCONVENIENCE.