

Gervais

- Specify appropriate fire separation construction methods have been taken (R302.6)
5/8" Sheet Rock on common wall and ceiling of attached garage
Sprinkler System of High Tech Fire Protection

All walls or just one wall?

TABLE R302.6
DWELLING/GARAGE SEPARATION

SEPARATION		MATERIAL
From the residence and attics	YES = 5/8 inch	Not less than 1/2-inch gypsum board or equivalent applied to the garage side
From all habitable rooms above the garage	↑	Not less than 5/8-inch Type X gypsum board or equivalent
Structure(s) supporting floor/ceiling assemblies used for separation required by this section	N/A	Not less than 1/2-inch gypsum board or equivalent
Garages located less than 3 feet from a dwelling unit on the same lot	↓	Not less than 1/2-inch gypsum board or equivalent applied to the interior side of exterior walls that are within this area

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm.

5/8" gypsum board will be used on the interior common wall between the attached garage and the home AND on the ceiling of the garage

See Attachment 2