

## Gervais

---

- How do you access the attic area of both the house and garage?  
Attic access to house is via the walk in closet on 2<sup>nd</sup> floor in Master Bedroom.  
Attic access to the garage will be centered in garage ceiling.

Show in drawings. Show dimensions

Please see Attachment 2 with additional information to include request.

- Provide header schedule for openings requiring headers.  
All headers under a 6' rough opening will be 2X10 boxed with insulation.  
All header over 6' rough opening will be 3-ply 2X10 with 2-ply ½" plywood and double jacks.

single 2x10?

All headers under a 6' rough opening will be boxed: two (2) 2X10 with 2X6 top and bottom and insulation in the middle.

All header over 6' rough opening will be 3-ply 2X10 with 2-ply ½" plywood and double jacks.