



389 Congress St.Rm 315
Portland, ME 04101
Phone: (207)874-8700
Fax: (207)874-8716

facsimile transmittal

To: John & Joseph Leasure **From:** Mike Nugent

Fax: 799-5432 **Date:** May 13, 2003

Phone: 767-4830 **Pages:** 1

Re: Ocean Ridge units 1,2,3 & 4

- Urgent For Review Please Comment Please Reply Please Recycle

Thanks for the quick response.

With regard to the type of construction (5A or B), if you opt for the 5B designation, you'll have to have the 13R Sprinkler System monitored in compliance with Section 924.1 Method 1. Any thoughts??

According to Lt. McDougall, NFPA 13R systems do not have heads in enclosed spaces such as floor/ceiling assemblies, if this is the case draft stopping will be required, can you address this?

STC Issue—Do **all** of the tenant separation assemblies have an STC of 45 or greater?

Thanks again!

