

420-A-1

2001-0160

383 Presumpscot St.

Building Addition

383 Presumpscot St. INC.

**CITY OF PORTLAND, MAINE  
DEVELOPMENT REVIEW APPLICATION  
PLANNING DEPARTMENT PROCESSING FORM  
Planning Copy**

2001-0160  
Application I. D. Number  
  
06/26/2001  
Application Date

383 Presumpscot Street Inc  
Applicant  
474 Lafayette St, Yarmouth, ME 04096  
Applicant's Mailing Address  
Fisher, Jim  
Consultant/Agent  
Agent Ph: (207)871-1290 Agent Fax:  
Applicant or Agent Daytime Telephone, Fax

Presumpscot St. 1250 SqFt Addition  
Project Name/Description  
383 - 383 Presumpscot St, Portland, Maine  
Address of Proposed Site  
423 A001001  
Assessor's Reference: Chart-Block-Lot

Proposed Development (check all that apply):  New Building  Building Addition  Change Of Use  Residential  Office  Retail  
 Manufacturing  Warehouse/Distribution  Parking Lot  Other (specify) \_\_\_\_\_

1250 SqFT  
Proposed Building square Feet or # of Units      Acreage of Site      Zoning

**Check Review Required:**

Site Plan (major/minor)       Subdivision # of lots \_\_\_\_\_       PAD Review       14-403 Streets Review  
 Flood Hazard       Shoreland       Historic Preservation       DEP Local Certification  
 Zoning Conditional Use (ZBA/PB)       Zoning Variance       Other \_\_\_\_\_

Fees Paid:    Site Plan      Subdivision      Engineer Review      \$6,033.28      Date    10/12/2001

**Planning Approval Status:**

Reviewer Sarah Hopkins

Approved       Approved w/Conditions See Attached       Denied

Approval Date 09/25/2001      Approval Expiration 09/25/2002      Extension to \_\_\_\_\_       Additional Sheets Attached  
 OK to Issue Building Permit      Sarah Hopkins      11/01/2001  
signature      date

Performance Guarantee       Required\*       Not Required

\* No building permit may be issued until a performance guarantee has been submitted as indicated below

<input checked="" type="checkbox"/> Performance Guarantee Accepted	<u>11/01/2001</u> date	<u>\$335,213.56</u> amount	<u>09/25/2003</u> expiration date
<input type="checkbox"/> Inspection Fee Paid	_____ date	_____ amount	
<input type="checkbox"/> Building Permit Issue	_____ date		
<input type="checkbox"/> Performance Guarantee Reduced	_____ date	_____ remaining balance	_____ signature
<input type="checkbox"/> Temporary Certificate of Occupancy	_____ date	<input type="checkbox"/> Conditions (See Attached)	_____ expiration date
<input type="checkbox"/> Final Inspection	_____ date	_____ signature	
<input type="checkbox"/> Certificate Of Occupancy	_____ date		
<input type="checkbox"/> Performance Guarantee Released	_____ date	_____ signature	
<input type="checkbox"/> Defect Guarantee Submitted	_____ submitted date	_____ amount	_____ expiration date
<input type="checkbox"/> Defect Guarantee Released	_____ date	_____ signature	

**PLANNING BOARD REPORT #41-01**

**PRESUMPCOT STREET INTERMODAL FACILITY  
SITE PLAN REVIEW  
STORMWATER PERMIT REVIEW  
OCTOBER CORPORATION, APPLICANT**

Submitted to:

Portland Planning Board  
Portland, Maine

September 11, 2001

## I. INTRODUCTION

The October Corporation proposes to construct a park and ride lot/intermodal facility at 383 Presumpscot Street. The development site is located between Presumpscot Street and the St. Lawrence railroad. The facility will be constructed in three phases, for a total of 181 parking spaces and a 1250 square foot commuter station. The site is 4.08 acres and zoned Moderate Impact Industrial (IM).

The October Corporation will use this parking lot as a shuttle lot for employees located at the new office complex at the Pineland Center in New Gloucester, as well as workers in the October Corporation's downtown buildings. The facility will be serviced by a transit provider, and potentially by commuter rail service along the St. Lawrence line in the future.

## II. SUMMARY OF FINDINGS

Zone:	IM
Surrounding Uses:	Industrial
Land Area:	4.08 acres
Parking Spaces	
Phase I	109 space parking lot
Phase II	1250 sq. ft. commuter station
Phase III	72 additional spaces

## III. STAFF REVIEW

This development has been reviewed by staff for conformance with the review standards of the Site Plan Ordinance and Chapters 500 and 502 of the Maine DEP Regulations

### 1/2. Traffic

#### Vehicular Circulation

Traffic will enter the site from two curb cuts along Presumpscot Street. The parking area will be located off the horseshoe access drive that traverses the property. Landscaped islands will be installed between the rows of parking.

The applicant's engineer has submitted a site distance calculation for the proposed entrances and found that the available site distance exceeds the City's required distance for a 35 mph zone.

The applicant was also asked by the City Traffic Engineer to evaluate the proposal's impact on the capacity of the Washington Ave/Presumpscot intersection. The study found that there would be no significant degradation in the intersection's level of service and that the LOS would continue to operate at a level "B" during the morning peak hour and a level of "C" in the afternoon.

## Pedestrian Safety

Since the last workshop on this item, the applicant has withdrawn its request for a sidewalk and curb waiver. Sidewalk, esplanade, and curb are proposed for the frontage of the property. Also, a pedestrian crosswalk is shown leading to the proposed Phase II shelter and a sidewalk and curb is indicated along the front of the shelter.

The City Traffic Engineer has reviewed the plans and traffic study. Mr. Ash's comments are included as Attachment 7c.

- 3/4. Bulk, location or height of proposed structures will not cause health or safety problems and minimize to the extent feasible diminutions in the value to neighboring properties.

The 1250 sq. ft. transit depot will be a single story with a standing seam metal roof. The building will house restrooms, a waiting room, office/storage area, and a mechanical room.

## 5. Sewers, Sanitary and Storm Drains, Water

Currently, the site is relatively flat with a slight slope toward the railroad property. The southern portion of the site drains toward a ravine containing a small stream.

A stormwater management report has been submitted which describes the post development stormwater rate of flow to be less than the predevelopment condition. The total build out of the site will result in an impervious surface of 1.57 acres.

Catchbasins have been proposed throughout the entire parking lot to catch run off and direct flows to a vortechincs 7000 structure.

A potential condition of approval:

- That an executed drainage maintenance agreement for the Vortechincs unit be provided by the applicant and approved by Corporation Counsel, prior to commencement of site work.

Electric and telephone lines exist on overhead poles along Presumpscot Street. These lines will be routed underground to the site. Since a sewer line does not exist along this portion of Presumpscot Street, the applicant proposes to install a subsurface wastewater disposal system on site. The septic system will be reviewed when a building permit is applied for.

The City's Reviewing Engineer has reviewed the plans and stormwater management report submitted by the applicant. Mr. Bushey's comments are included as Attachment 7b.

The Public Works Department has reviewed the plans and stormwater management and construction details. Mr. Lombardo's comments are included as Attachment 7a.

6/7. Landscaping

The landscaping plan for the entire site includes rows of Honey Locust, Pin Oak, Callery Pear, and Flowering Crab around and throughout the parking lot. Junipers and Lilacs are also proposed near the driveway entrances.

Since the last workshop on this item, the applicant has added a sidewalk, esplanade, and curb along the frontage of the site. The newly proposed esplanade allows an area along the curb for the planting of street trees. The applicant proposes to stagger the trees 20ft on center, on either side of the sidewalk. This design should provide an attractive streetscape along this stretch of Presumpscot Street.

8. Erosion and Sedimentation

Silt fence is shown around the perimeter of disturbed area along the southern portion of the site. Erosion control measures and details have been included in the plan and include hay bale barriers around the catchbasins, bark mulch sediment barriers, and construction entrance specifications.

9. Lighting

A revised lighting plan has been submitted by the applicant and is attached to this memo. 16ft high 250-watt high-pressure sodium lights have been proposed. According to the photometrics submitted, there will be no light spillover onto adjacent properties. The revised lighting plan has lowered the poles significantly (from 25 ft to 16 ft) and reduced the wattage of the lights.

10. Fire

The Fire Department has reviewed the proposal and has found emergency access to be sufficient.

11. Municipal Infrastructure

The construction of a sidewalk is an important aspect of this plan and is consistent with the City's planned infrastructure.

12. Financial and Technical Capacity

Information on financial and technical capacity has been submitted and is included as Attachment 5.

12. Natural resources including groundwater, surface water, habitat wetlands, unusual natural areas, and wildlife and fisheries.

There is a stream that traverses the southern portion of the site. All improvements and grading has been setback from the ravine and the stormwater will be cleaned and slowed down before entering the ravine. Otherwise, there are no known unusual or protected areas included in this parcel.

#### IV. MOTIONS FOR THE BOARD TO CONSIDER

On the basis of plans and materials submitted by the applicant and on the basis of information contained in Planning Report #41-01:

1. The Presumpscot Street Intermodal Facility site plan is in conformance with the Site Plan Ordinance of the Land Use Code.


potential condition of approval:

That an executed drainage maintenance agreement for the Vortechmics unit be provided by the applicant and approved by Corporation Counsel, prior to commencement of site work.

2. The Presumpscot Street Intermodal Facility site plan is in conformance with Chapters 500 and 502 of the Maine DEP Regulations

#### Attachments

1. Vicinity Map
2. Project Narrative
3. Stormwater Report
4. Subsurface Conditions Report
5. Traffic Study
6. Financial Capacity
7. Staff Comments
  - a. Public Works
  - b. Reviewing Engineer
  - c. Traffic Engineer
8. Site Plans/Building Elevations





**383 PRESUMPCOT STREET  
APPLICATION FOR SITE PLAN APPROVAL  
BY OCTOBER CORPORATION**

The October Corporation, P.O. Box 17516, Portland, Maine 04112-8516, is requesting site plan approval for the development of a intermodal transfer facility on the property it owns at 383 Presumpscot Street in Portland, Maine. The October Corporation (a wholly owned subsidiary of the Libra Foundation) is currently developing an office park in New Gloucester and owns several office buildings in downtown Portland. The proposed facility will provide an opportunity to utilize a mass transportation system for the commuter traffic associated with the Corporation's projects. October Corporation is currently investigating arrangements with area bussing firms. The parcel's location adjacent to the St. Lawrence railroad would also provide an opportunity for commuter rail service in the future.

The subject parcel is approximately 4.08 acres in size, with 650 feet of frontage on Presumpscot Street. The rear of the property borders the St. Lawrence railroad property. The site has historically been used by various contracting firms. The site is gently sloping towards the rear of the property and towards the southern boundary. A ravine, which carries stormwater from this section of Presumpscot Street to the ocean, is located on the south side of the property.

The site plan depicts the potential for a future build-out of the property. Initially, a 109-space parking lot would be constructed, along with a bus drop-off and loading area. The existing driveway entrance to the site would serve as one entrance to the parking lot, and a second entrance would be created approximately 250 feet south of the existing entrance. If the demand exists, an additional 72 spaces can be added on the north side of the parking facility. The site plan also depicts a commuter station of 1250 square feet, consisting of a small waiting room, a ticket booth, and a rest room. The station would be constructed once the facility's demand is established.

Power and telephone service exist on overhead poles along Presumpscot Street. Underground conduits for these services will be brought onto the site during the construction of the first phase of the parking lot. The Portland Water District has a 10-inch main within the Presumpscot Street

right-of-way and currently has a service on-site. The wastewater generated from the facility is estimated to be approximately 550 gallons per day. The public sewer is located approximately 400 feet south of the parcel and as a result of the grades on Presumpscot Street, the sewer main cannot be extended to serve the site. An on-site subsurface wastewater disposal system will be utilized to serve the future commuter station. The location of the system is shown on the site plan and a HHE-200 form is included with this application. Solid waste generated at the site will be minimal, a cleaning service will dispose of this at the end of each business day.

The proposed project will not exceed the threshold of creating three acres of impervious area and thus will not require a Maine Department of Environmental Protection (MDEP) Site Location Permit. The only wetlands that exist on the site are located within the ravine along the southern property line. There are no wetlands being impacted by the proposed project.

Over the years, the site has been filled and graded and thus there are no unusual natural areas, wildlife or fisheries habitats on the site. The soils are mapped as a Buxton silty loam. Test pits were excavated on the site to determine the depth of fill placed on the site. The test pit locations are shown on the site plan and a copy of the test pit logs are included with this application. The soils are suitable for the proposed project. Temporary and permanent erosion control measures are included on the plans.

The stormwater discharge from the site will be collected by catch basins and transported via the storm drainpipes to Vortech's Model 7000 for sediment removal prior to discharge to the ravine located along the southern property boundary.

In accordance with the submittal requirements included with the Site Plan, are elevations of the future building, a landscaping plan, a lighting plan a boundary survey, a storm water management plan, copies of the deeds and a copy of the Libra Foundation statement of Financial Position 2000.

**CITY OF PORTLAND, MAINE  
SITE PLAN CHECKLIST**

Intermodal Transfer Facility 353 Presumpscott St  
Project Name, Address of Project

I.d. Number

Submitted () & Date	Item	Required Information	Section 14-525 (b,c)
<u>6/26/01</u>	(1)	Standard boundary survey (stamped by a registered surveyor, at a scale of not less than 1 inch to 100 feet and including:	1
<u>6/26/01</u>	(2)	Name and address of applicant and name of proposed development	a
<u>6/26/01</u>	(3)	Scale and north points	b
<u>6/26/01</u>	(4)	Boundaries of the site	c
<u>6/26/01</u>	(5)	Total land area of site	d
<u>6/26/01</u>	(6)	Topography - existing and proposed (2 feet intervals or less)	e
	(7)	Plans based on the boundary survey including:	2
<u>6/26/01</u>	(8)	Existing soil conditions	a
<u>6/26/01</u>	(9)	Location of water courses, marshes, rock outcroppings and wooded areas	b
<u>6/26/01</u>	(10)	Location, ground floor area and grade elevations of building and other structures existing and proposed, elevation drawings of exterior facades, and materials to be used	c
<u>6/26/01</u>	(11)	Approximate location of buildings or other structures on parcels abutting the site	d
<u>6/26/01</u>	(12)	Location of on-site waste receptacles	e
<u>6/26/01</u>	(13)	Public utilities	e
<u>6/26/01</u>	(14)	Water and sewer mains	e
<u>6/26/01</u>	(15)	Culverts, drains, existing and proposed, showing size and directions of flows	e
<u>6/26/01</u>	(16)	Location and dimensions, and ownership of easements, public or private rights-of-way, both existing and proposed	f
<u>6/26/01</u>	(17)	Location and dimensions of on-site pedestrian and vehicular accessways	g
<u>6/26/01</u>	(18)	Parking areas	g
<u>6/26/01</u>	(19)	Loading facilities	g
<u>6/26/01</u>	(20)	Design of ingress and egress of vehicles to and from the site onto public streets	g
<u>6/26/01</u>	(21)	Curb and sidewalks	g
<u>6/26/01</u>	(22)	Landscape plan showing:	h
<u>6/26/01</u>	(23)	Location of existing proposed vegetation	h
<u>6/26/01</u>	(24)	Type of vegetation	h
<u>6/26/01</u>	(25)	Quantity of plantings	h
<u>6/26/01</u>	(26)	Size of proposed landscaping	h
<u>6/26/01</u>	(27)	Existing areas to be preserved	h
<u>6/26/01</u>	(28)	Preservation measures to be employed	h
<u>6/26/01</u>	(29)	Details of planting and preservation specifications	h
<u>N/A</u>	(30)	Location and dimensions of all fencing and screening	i
<u>Location 6/26/01</u>	(31)	Location and intensity of outdoor lighting system	j
	(32)	Location of fire hydrants, existing and proposed	k
<u>6/26/01</u>	(33)	Written statement	c
<u>6/26/01</u>	(34)	Description of proposed uses to be located on site	l
<u>6/26/01</u>	(35)	Quantity and type of residential, if any	l
<u>6/26/01</u>	(36)	Total land area of the site	b2
<u>6/26/01</u>	(37)	Total floor area and ground coverage of each proposed building and structure	b2
	(38)	General summary of existing and proposed easements or other burdens	c3
<u>6/26/01</u>	(39)	Method of handling solid waste disposal	4

<u>6/26/01</u>	(40)	Applicant's evaluation of availability of off-site public facilities, including sewer, water and streets	5
<u>6/26/01</u>	(41)	Description of any problems of drainage or topography, or a representation that there are none	6
	(42)	An estimate of the time period required for completion of the development	7
<u>6/26/01</u>	(43)	A list of all state and federal regulatory approvals to which the development may be subject	8
<u>N/A</u>	(44)	The status of any pending applications	8
<u>N/A</u>	(45)	Anticipated timeframe for obtaining such permits	h8
<u>N/A</u>	(46)	A letter of non jurisdiction	h8
<u>6/26/01</u>	(47)	Evidence of financial and technical capability to undertake and complete the development including a letter from a responsible financial institution stating that it has reviewed the planned development and would seriously consider financing it when approved.	

Note: Depending on the size and scope of the proposed development, the Planning Board or Planning Authority may request additional information, including (but not limited to):

- drainage patterns and facilities;
- erosion and sedimentation controls to be used during construction;
- a parking and/or traffic study;
- a noise study;
- an environmental impact study;
- a sun shadow study;
- a study of particulates and any other noxious emissions; and
- a wind impact analysis.

Other comments:

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

**STORMWATER MANAGEMENT PLAN  
383 PRESUMPSCOT STREET  
PORTLAND, MAINE**

**A. INTRODUCTION**

This stormwater management plan for proposed development of a transportation intermodel facility at 383 Presumpscot Street in Portland, Maine was designed to comply with the Maine Department of Environmental Protection (MDEP) Rules for stormwater quantity as outlined in 06-096 CMP, Chapter 500.3 Stormwater Management and using three general objectives of MDEP's Stormwater Management for Maine Best Management Practices (MDEP BMP)(MDEP, 1995):

1. effective drainage
2. flood prevention
3. erosion control

As designed, peak runoff rates for post-development conditions at the site will be less than those from the pre-development conditions.

The pre- and post-development surface water peak runoff rates were evaluated for the watershed in which the intermodel facility development is included. Stormwater flows were calculated for 2-, 10-, and 25-year/24-hour storm events with Type III Soil Conservation Service rainfall distribution and Type 2 antecedent moisture conditions, using HydroCAD computer modeling system by Applied Microcomputer Systems of Chocorua, New Hampshire.

**B. PROJECT DESCRIPTION**

The October Corporation (a wholly owned subsidiary of the Libra Foundation) of Portland, Maine owns a parcel of land at 383 Presumpscot Street in Portland, Maine. The subject parcel is approximately 4.1 acres. The rear of the property borders the St. Lawrence and Atlantic Railroad property. Various contracting firms have historically used the site. The site slopes gently to the

rear of the property and toward a ravine that carries storm water located at the south end of the property. The property is currently vacant and there are two garages remaining on the site.

Proposed site development includes construction of a 171-space parking lot and a 3000 square foot building.

The total existing impervious area within the site is approximately 0.5 acres in pre-development. The intermodel facility project will result in an impervious area of approximately 1.57 acres.

### C. SITE WATERSHEDS


The proposed intermodel facility site is situated in the Casco Bay Watershed. The intermodel facility watershed drains to small-unnamed tributaries, which flow eastward approximately 500 feet to their confluence with Casco Bay.

Surficial soils in the watersheds were mapped by the SCS as Paxton, Hollis, and Buxton series soils. For stormwater modeling purposes these soils were modeled as hydrologic soil group (HSG) C soils (see Figure 1).

An upgradient watershed conveys water to the ravine on the south side of the intermodel facility property. This upgradient watershed is located on the west side of Presumpscot Street and extends to the top of Graves Hill as shown on Figure 2. Pre- and post-development conditions for the intermodel facility site are shown on Drawings D-100 and D-101.

#### Intermodel Facility Watershed Stormwater Flows

The study area for the intermodel facility watershed consists of approximately 67.5 acres in pre-development and post-development conditions as indicated on Figure 2 and Drawings D-100 and D-101. The area of study consists of two points of analysis for storm water flows.



MAP DESIGNATION	NAME	HYDROLOGIC SOIL GROUP
BuB	BUXTON, SILT LOAM	C
BuC2	BUXTON, SILT LOAM	C
HrB	HOLLIS, FINE SANDY LOAM	C
HrC	HOLLIS, FINE SANDY LOAM	C
HsC	HOLLIS, VERY ROCKY FINE SANDY LOAM	C
HsE	HOLLIS, VERY ROCKY FINE SANDY LOAM	C
PbB	PAXTON, FINE SANDY LOAM	C

REFERENCE: SOIL SURVEY OF CUMBERLAND COUNTY, MAINE BY U.S. DEPT. OF AGRICULTURE, AUGUST 1974. MAPS 76 & 82.

FIGURE 1  
 MEDIUM INTENSITY SOILS MAP  
 OCTOBER CORPORATION  
 INTERMODAL TRANSPORTATION FACILITY  
 PRESUMPSCOT STREET  
 PORTLAND, MAINE



**SME**  
 Sevee & Maher Engineers, Inc.

are shown in Drawing D-100. The catchment boundaries and  $T_c$  routing for post-development site conditions are shown in Drawing D-101.

**TABLE 1**  
**SUMMARY OF STORMWATER ROUTING CONDITIONS**  
**PRESUMPCOT STATION**

**PRE-DEVELOPMENT**

Analysis Point	Catchment Area	Area (acres)	$C_N$ (weighted)	$T_c^*$ (min)	Peak Flow** (cfs) (2/10/25-yr storm)
1	1	1.69	85	16.6	2.2/4.3/5.3
2	2	3.24	86	25.2	46.2/108.8/140.8
	217	8.32	72	23.9	
	218	9.46	71	23.9	
	219	44.8	78	19.6	

**POST-DEVELOPMENT**

Analysis Point	Catchment Area	Area (acres)	$C_N$ (weighted)	$T_c^*$ (min)	Peak Flow** (cfs) (2/10/25-yr storm)
1	1	1.05	75	16.5	0.80/1.90/2.51
2	201-219	See HydroCAD Data	See HydroCAD Data	See HydroCAD Data	45.4/107.6/139.4

**Notes**

\*  $T_c$  is to subcatchment downgradient boundary or detention pond, as applicable.

\*\* Peak flow of analysis point after routing through detention ponds and/or reaches.

As indicated in Table 1, the post-development peak rates of runoff at analysis points 1 and 2 are less than those of pre-development conditions. The decrease in SC-1 peak flow rates is accomplished by decreasing the area of SC-1 in post-development conditions. The decrease in SC-2 peak flow rates is due to allowing peak flows from the site to leave the watershed prior to the peak flows from the upgradient watershed.



#### D. PROPOSED DRAINAGE FACILITIES

Surface water at the site will be collected in catch basins, conveyed via the storm drain pipes to a vortex for sediment removal prior to discharge to the ravine located along the southern property border. Locations of catch basins, piping, and the vortex system are shown on Drawing D-101. Catch Basins will consist of 4-foot diameter pre-cast concrete structures. Storm drains will consist of 12, 15, and 18-inch diameter PVC Pipe. The piping system was sized to handle projected flows during the 24-hour/25-year rainfall event. Pipes were also sized to allow from a minimum flow rate of 3.0 feet/second during a 2-year storm event to limit the buildup of grit and sediment in the piping. A Vortech Model 7000 storm water treatment system will be installed to provide removal of grit and suspended solids from storm water prior to discharge to the stream in the ravine.

The design capacity of stormwater drainage structures was based on SCS TR-20 methodology. Pipes were sized using the HydroCAD. Results of pipe sizing are indicated on HydroCAD printouts in Appendix B. Water quality worksheets are contained in Appendix C.



*Sevee & Maher Engineers, Inc.*  
*Waste Management and Hydrogeologic Consultants*

April 10, 2001

00015.05  
010409pu.doc

Mr. Paul Ureneck  
Boulos Property Management  
One Canal Plaza  
Portland ME 04101

Subject: Subsurface Conditions, 373 Presumpscot Street Property  
Portland, Maine

Dear Paul:

The purpose of this letter is to describe the subsurface conditions encountered in test pits made at the 373 Presumpscot Street Property (i.e., site) on April 6, 2001. Test pits were made to evaluate fill thickness and presence/nonpresence of granular materials suitable for parking lot construction. A total of 20 test pits were excavated using a backhoe supplied by White Bros. Construction of Westbrook, Maine. The test pits were identified as test pits TP-101 through TP-120. The approximate locations of the test pits with respect to the site property boundaries and existing site structures are shown on Figure 1.

The site is generally flat and has two wood frame buildings located along its back (east) side. The south side of the site is filled land as evidenced by abrupt changes in topography and vegetation. The back of the property is paralleled by the Canadian National Railway. The front (west) side of the property is paralleled by Presumpscot Street. The north and south sides of the property are abutted by private ownership.

The native soils encountered at the site consisted of brown and gray silty clays. Where the native silty clays were observed, they were estimated to be medium to stiff in terms of consistency. At several site locations the native silty clay was overlain by clayey fill soil mixed with wood, masonry, pavement, and other debris. Groundwater, in the form of seepage along the test pit sidewalls, was observed within the fill materials. At test pit locations TP-102 and TP-103 a slight oily odor was detected along with oil sheen presence on the test pit seepage. The test pit depths varied from approximately 2 to 8 feet. The deeper test pits generally exhibited the greatest thickness of fill. Essentially, no granular materials suitable for parking lot construction were encountered in the test pits. Table 1 summarizes the soil conditions encountered in the test pits. Excavation of each test pit was typically halted once native soils were encountered in effort to minimize disturbance of the foundation soils for future parking lot construction. Upon completion,

each test pit was backfilled in layers and tamped with the backhoe bucket to obtain compaction.

TABLE 1

Test Pit	Fill Thickness (feet)	Fill Description
TP-101	3.5	Soft brown clayey soil intermixed with pavement, cinders and ash
TP-102	6+	Soft clayey soil intermixed with concrete, wood and rubble
TP-103	5+	Soft clayey soil with many cobbles and small boulders, heavy seepage
TP-104	0	No fill observed (stiff native silty clay)
TP-105	1	Soft brown silty soil
TP-106	NA	Pipe trench with pipe buried 18 inches below ground surface and stone backfill
TP-107	0.5	Soft brown clayey soil intermixed with sand and gravel
TP-108	3+	Soft clayey soil mixed with rubble and large fragments of concrete
TP-109	3	Soft clayey soil intermixed with rubble
TP-110	0.5	Sand and gravel intermixed with clayey soil
TP-111	0.5	Sand and gravel intermixed with clayey soil
TP-112	1	Soft clayey soil and buried wooden log
TP-113	0	No fill observed (stiff native silty clay)
TP-114	2	Soft clayey soil
TP-115	4.5	Soft clayey soil intermixed with wood debris
TP-116	6	Soft clayey soil intermixed with wood debris
TP-117	2.5	Edge of leachfield, 18 inches sand over 12+ inches stone
TP-118	1	Leachfield distribution box, buried below 12 inches stone
TP-119	0.5	Concrete septic tank
TP-120	1	Soft clayey soil

Three buried drainage features were encountered as part of the test pit activities.

1. A leachfield (approximately 18 inches of sand over 12+ inches of stone) and a concrete septic tank (estimated 750 to 1,000 gallons) were encountered adjacent to the east side of the larger of the two site buildings. The approximate location of the tank and leachfield are shown on Figure 1. A concrete distribution box was encountered separating the leachfield and tank. The distribution box was left marked in the field by three concrete blocks. No visible damage was sustained by the leachfield, distribution box, septic tank, or associated piping as result of the test pitting activities. A small portion of the leachfield (north end) was excavated and no pipes were encountered in that area.
2. A catch basin was identified on the front (west) side of the larger site building. An 8- to 10-inch outlet pipe was observed running approximately south from the catch basin at a depth of about 2 feet. The

**CURTIS WALTER STEWART**  
A r c h i t e c t s434 Cumberland Avenue  
Portland ME 04101-2325

Benedict B. Walter, Vice President

Phone: 207.774.4441  
Fax: 207.774.4016  
E-mail: BWalter@CWSArch.com

September 6, 2001

Sarah Hopkins  
Senior Planner  
Department of Planning and Urban Development  
389 Congress Street  
Portland ME 04101Re: Presumpscot Street Intermodal Facility  
Site Lighting Design Summary

Dear Sarah,

The site lighting design for the above referenced project was based on the City of Portland Lighting Standards, specifically as follows:

## 4. SPECIFIC STANDARDS

- A. **Uniformity:** Some portions of the site are not lighted and have virtually no foot candles of light level. Of the site area to be lighted, the lowest light level is 0.35 fc and the highest is 1.70 fc. This equates to a uniformity ratio of approximately 5 to 1, well below the maximum ratio of 20 to 1.
- B. **Minimum:** 0.35 fc (at area of the site to be illuminated)  
**Maximum:** 1.70 fc  
**Average:** 1.15 (Approximate)
- C. **Fixture Height:** 18' above finish grade
- D. **Light Trespass:** The site lights are full cut-off luminaires which will allow virtually no light trespass in excess of 0.1 fc with the exception of one small area facing Presumpscot Street. This area, however, is also illuminated by street lighting and thus no negative impact will be realized. This will not cause glare to passing drivers.
- E. **Wattage:** 250 Watt bulbs
- F. **Light Quality:** Metal Halide

In summary, we believe this site lighting scheme meets and exceeds the intent of the Lighting Standards of the City of Portland.

Very truly yours,

CURTIS WALTER STEWART ARCHITECTS

Benedict B. Walter, Architect  
Vice President

**From:** Anthony Lombardo  
**To:** Sarah Hopkins  
**Date:** Fri, Jul 6, 2001 1:05 PM  
**Subject:** 383 Presumpscot St...Intermodal Transportation Facility

I have reviewed the application and plans dated 6/26/01 and offer the following comments:

1. The applicant needs to contact Carol Merritt of Public Works regarding the potential costs associated with a Street Opening Permit (required with any work within the public right of way). This section of road may have been paved within the last 5 years, as a result, additional fees may be required.
2. The applicant needs to provide a paved sidewalk, at least 5 feet wide, and an esplanade along the frontage of the property.

**From:** Larry Ash  
**To:** Sarah Hopkins  
**Date:** Thu, Sep 6, 2001 5:49 AM  
**Subject:** Intermodal Transfer Facility on Presumpscot Street

Sarah: I have reviewed the traffic report on the proposed Intermodal Transfer Facility and have no traffic related issues.

outlet pipe apparently turns southeast at some distance from the catch basin to discharge near the edge of the eastern property boundary. The approximate location of the catch basin and outlet pipe are shown on Figure 1.

3. A buried concrete tank was observed adjacent to the front of the building. Based on inspection of the tank interior (through the tank accessway), several pipes connect to the tank which appeared to enter the tank from direction(s) parallel to the west wall of the building.

Thank you for allowing Sevee & Maher Engineers, Inc. to assist you in understanding the subsurface conditions at the 373 Presumpscot Street Property. If we can be of any further assistance, or if we can clarify any of the information presented herein, please do not hesitate to contact us.

Respectfully,

SEVEE & MAHER ENGINEERS, INC.

Matthew W. Muzzy, P.E.  
Geo-Environmental Engineer

cc: Robert Arsenault (SME)



*Sevee & Maher Engineers, Inc.*  
Waste Management and Hydrogeologic Consultants

August 14, 2001

00013.07  
0108131a.doc

City of Portland  
Attn: Mr. Larry Ash  
Traffic Engineering Division  
65 Hanover Street  
Portland, ME 04101

Portland, Maine

Subject: October Corp.  
Intermodal Transfer Facility  
Traffic Study

Dear Mr. Ash:

In response to our telephone conversation of June 28, 2001 concerning October Corporation's proposed intermodal transfer facility on Presumpscot Street, we offer the following information for your review:

- 1. Sight distance at the project entrances:

Sevee & Maher Engineers, Inc. (SME) has measured the available sight distance at each proposed entrance. Sight distance was measured at a point 10 feet from the edge of travelway to the centerline of the opposing lane(s), assuming a height of eye of 3.5 feet and a height of object of 4.25 feet. The available sight distance from each entrance is as follows:

	Available Site Distance	
	<u>Left</u>	<u>Right</u>
North Entrance/Exit	>750'	>950'
South Entrance/Exit	530'	>1200'

The measured sight distance exceeds the City's sight distance standard of 513 feet for a posted speed limit of 35 mph, as specified in Section III, paragraph 4, Traffic Design Standards and Guidelines of the "City of Portland, Maine Technical and Design Standards and Guidelines," March 2000.



2. Impact on Intersection Capacity of Washington Avenue and Presumpscot Street:

SME conducted turning movement counts at Washington Avenue and Presumpscot Street from 6:00 AM to 9:00 AM, and from 3:00 PM to 6:00 PM on Tuesday, July 10, 2001. Because of late afternoon thunderstorms which caused numerous accidents and traffic delays, the afternoon count was repeated from 4:00 PM to 6:00 PM on Wednesday, July 18, 2001. Traffic generation from the project site was based on rates outlined in the 6<sup>th</sup> Edition of "ITE Trip Generation", Land Use 090; Park and Ride Lot with Bus Shuttle. It is expected that this facility (171 parking spaces) will generate 113 PM peak hour trips, and 109 AM peak hour trips. Based on the traffic distributions at Washington Avenue and studies conducted for the Pineland Center in New Gloucester, it was assumed that 15 new trips would be generated from/to Washington Avenue, 17 new trips would result on Presumpscot Street from Falmouth, with the remainder of the trips diverted from existing traffic on Washington Avenue.

Peak hour volumes were increased by 2 percent to account for traffic growth from 2001 to 2002. The morning and afternoon peak hour performance for 2002 was calculated for both the "Build" and "No-build" 2002 conditions. It was found that no significant degradation in the intersection's level of service will result from this project. The intersection will continue to operate at a Level of Service (LOS) B (AM) and C (PM). Performance charts, assumptions, and analyses are attached.

The traffic analysis was prepared through the combined efforts of Sevee & Maher Engineers, Inc. and HNTB of Westbrook, Maine. SME conducted turning movement counts, compiled intersection configuration data and performed the traffic generation and distribution analysis. HNTB reviewed the information compiled by SME and provided the peak hour performance analysis.

3. Presumpscot Street Truck Traffic:

Based on the turning movement counts, existing truck traffic on Presumpscot Street is as follows:


	<u>No. Trucks</u>	<u>% of Total Traffic</u>
AM (6-9)	101	9.4
PM (4-6)	43	6.1

Enclosed is a copy of site plans for Phase I of the project.

If you have any questions or require additional information, please contact me.

Sincerely,

SEVEE & MAHER ENGINEERS, INC.

A handwritten signature in black ink, appearing to read "John R. Kennedy". The signature is fluid and cursive, with a large loop at the end.

John R. Kennedy, P.E.

Enclosures

**SME**

*Sevee & Maher Engineers, Inc.*  
Waste Management and Hydrogeologic Consultants  
Cumberland Center, Maine

## TELEPHONE MEMORANDUM

Job No. 00013.07

DATE: June 28, 2001

BETWEEN: Larry Ash, city of Portland Traffic Engineer

AND: John Kennedy, SME

SUBJECT: PRESUMPSCOT STREET – TRAFFIC IMPACTS

---

Explained to Larry that October Corporation had submitted a site plan application for an intramodal transfer facility on Presumpscot Street. Use to be for car/bus transfer of October Corporation/Boulos Properties employees to work in downtown Portland. Also, use for rail transportation for commuters from Portland, South Portland, and Cape Elizabeth to work in Pineland, New Gloucester. At this time, majority of usage would be bussing of commuter traffic to downtown.

### Larry's Concerns.

1. Sight distance of project entrance (SME believes OK on this).
2. Ability of Presumpscot Street/Washington Avenue to handle additional traffic and/or change in turning movement. May be a simple matter of striping and modification of signal timing. Current Washington Avenue traffic is 20,000 vehicles per day. Recommends that a local traffic engineer review the intersection impact.
3. Also, elementary school is located on Presumpscot Street. However, there are crossing guides on Washington and Presumpscot Street.
4. Large number of trucks on Presumpscot Street.
5. Neighborhood is well organized.

Document2



## Statement of Financial Position 2000

Year Ended December 31, 2000

### ASSETS

Investments, at market	\$ 54,163,218
Cash and cash equivalents	100,451
Beneficial interest in trust	157,558,327
Federal excise tax receivable	54,528
Program-related investments	8,458,063
Assets held in title-holding corporation	73,735,541
Property and equipment, net of accumulated depreciation of \$83,955 at December 31, 2000	309,902
Other assets	135,752
<b>TOTAL ASSETS</b>	<b>\$294,515,782</b>

### LIABILITIES

Payables and other liabilities	\$ 26,460
Deferred federal excise tax	118,000
<b>TOTAL LIABILITIES</b>	<b>144,460</b>

### NET ASSETS

Unrestricted net assets	294,371,322
<b>TOTAL LIABILITIES AND NET ASSETS</b>	<b>\$ 294,515,782</b>

[Arts, Culture & Humanities](#) | [Education](#) | [Environment](#) | [Health](#) |  
[Human Services](#) | [Other](#) | [Public/Society Benefit](#) | [Activities 2000](#) |  
Allocation Across Fields

7a

**From:** Anthony Lombardo  
**To:** Sarah Hopkins  
**Date:** Fri, Jul 6, 2001 1:05 PM  
**Subject:** 383 Presumpscot St... Intermodal Transportation Facility

I have reviewed the application and plans dated 6/26/01 and offer the following comments:

1. The applicant needs to contact Carol Merritt of Public Works regarding the potential costs associated with a Street Opening Permit (required with any work within the public right of way). This section of road may have been paved within the last 5 years, as a result, additional fees may be required.
2. The applicant needs to provide a paved sidewalk, at least 5 feet wide, and an esplanade along the frontage of the property.

7c

**From:** Larry Ash  
**To:** Sarah Hopkins  
**Date:** Thu, Sep 6, 2001 5:49 AM  
**Subject:** Intermodal Transfer Facility on Presumpscot Street

Sarah: I have reviewed the traffic report on the proposed Intermodal Transfer Facility and have no traffic related issues.

**MEMORANDUM**

**DATE:** September 5, 2001  
**TO:** Sarah Hopkins, Senior Planner  
**FROM:** Stephen R. Bushey, P.E.  
**SUBJECT:** Intermodal Transfer Facility

---

I have reviewed the materials dated 8/17/01 for the above project and find that they are in substantial conformance with the City's rules and regulations. The project is subject to the provisions of 38 M.R.S.A. Section 420-D and Chapters 500 and 502 of the MEDEP Regulations. Pursuant to the City of Portland's Delegated review authority the following Findings of Facts is made:

**Stormwater Quantity Standards:**

The stormwater quantity plan submitted by the applicant has been reviewed by the City staff and the findings are as follows:

- A. Peak flow from the site and peak flow of Receiving waters:  
The applicant has proposed a closed stormwater collection systems that, based on the estimates or pre and post development stormwater runoff flows obtained by using the SCS TR-20 methodology, results in post development flows being at or below pre-development levels from the site as well as in the receiving waters below.
- B. Maintenance:  
All components of the stormwater collection system will be maintained by the applicant in compliance with State and Local Standards.
- C. Discharge to Freshwater Wetlands:  
Freshwater wetlands will receive stormwater in the same manner as before the development

**Stormwater Quality Standards:**

The proposed project includes the installation of a Vortech Model 7000 stormwater treatment system to remove grit and suspended solids from stormwater prior to discharge to the stream on the ravine. The installation of these measures will meet the requirements of the State and local standards for the treatment of stormwater runoff.

Based on these findings the City of Portland concludes the pursuant to 38 M.S.R.A Section 420-D and chapters 500 and 502 of the MEDEP regulations and The City's Technical Standards:

- A. The applicant has made adequate provision to ensure that the development will meet the stormwater quantity and quality standards for : (1) Peak flow from the site and the receiving water; (2) Maintenance; and (3) Discharge to freshwater wetlands.

Therefore, I recommend the project be presented to the Portland Planning Board for approval, assuming no other issues from Staff or the Board.

If you have any questions please call.



10/2/01

TO: SARAH HORKINS 756-8258

FROM: KIM FARAR, BOULOS

Thank you so much for your  
help in expediting this! I'll wait  
to hear from you on the amt.  
needed for the perf. guarantee  
& the inspection fee.

Kim 871-1290  
653-8528

DEPARTMENT OF Planning and Urban Development  
 SUBDIVISION/SITE DEVELOPMENT

COST ESTIMATE OF IMPROVEMENTS TO BE COVERED BY PERFORMANCE GUARANTEE

Name of Project: Inter-Modal Transfer Facility - Phase I Date: \_\_\_\_\_  
 Address/Location: Presumpscot  
 Developer: October Corporation  
 Form of Performance Guarantee: \_\_\_\_\_  
 Type of Development: Subdivision Site Plan (Major/Minor): \_\_\_\_\_

TO BE FILLED OUT BY THE APPLICANT:

Item	PUBLIC			PRIVATE		
	Quantity	Unit Cost	Subtotal	Quantity	Unit Cost	Subtotal
1. STREET/SIDEWALK						
Road	N/A	N/A	N/A	N/A	N/A	N/A
Granite Curbing	560 LF	22.00	12,320.00	296 LF	22.00	6,512.00
Sidewalks	311 SY	15.65	4,867.15	156 SY	15.65	2,441.30
Esplanades	400 SY	2.95	1,180.00	N/A	N/A	N/A
Monuments	N/A	N/A	N/A	N/A	N/A	N/A
Street Lighting	N/A	N/A	N/A	N/A	N/A	N/A
Street Opening Repairs	183 SY	40.00	7,320.00	N/A	N/A	N/A
Other	N/A	N/A	N/A	N/A	N/A	N/A
2. EARTH WORK						
Cut	N/A	N/A	N/A	2450 CY	6.00	14,700.00
Fill	N/A	N/A	N/A	2300 CY	7.75	17,825.00
3. SANITARY SEWER						
Manholes						
Piping						
Connections						
Main Line Piping						
House Sewer Service Piping						
Pump Stations						
Other						
4. WATER MAINS						
	N/A	N/A	N/A	250 LF	25.00	6,250.00
5. STORM DRAINAGE						
Manholes						
Catchbasins	N/A	N/A	N/A	N/A	N/A	N/A
Piping	1 EA	2350.00	2,350.00	15 EA	2350.00	35,250.00
Detention Basin	20 LF	31.00	620.00	270 LF	33.00	8,910.00
Stormwater Quality Units				N/A	N/A	N/A
Other R.P.Rap				1 EA	3500.00	3,500.00
				65 CY	45.00	2,925.00

Note: Sewer Work in Phase II

5. SITE LIGHTING	N/A	N/A	N/A	10 ea	2,730 <sup>00</sup>	27,300 <sup>00</sup>
7. EROSION CONTROL						
Silt Fence	150 LF	3.00	450 <sup>00</sup>	670 LF	3.00	2,010 <sup>00</sup>
Check Dams	N/A			64	40.00	2,400 <sup>00</sup>
Ripe Inlet/Outlet Protection	N/A			N/A		
Level Lip Spreader	N/A			N/A		
Slope Stabilization	N/A			N/A		
Geotextile	N/A			N/A		
Hay Bale Barriers	N/A			N/A		
Catch Basin Inlet Protection	N/A			1 SEA	90.00	1,350 <sup>00</sup>
	N/A			N/A		
8. RECREATION AND OPEN SPACE AMENITIES	?					
9. LANDSCAPING			2,086 <sup>00</sup>			20,139 <sup>00</sup>
(Attach breakdown of plant materials, quantities, and unit costs) SEE Attachment #1						
10. MISCELLANEOUS			2,120 <sup>00</sup>			10,011 <sup>00</sup>
SEE Attachment #2						
TOTAL:		33,549 <sup>65</sup>			301,663 <sup>80</sup>	
GRAND TOTAL:						335,213.55

INSPECTION FEE (to be filled out by the City)

	PUBLIC	PRIVATE	TOTAL
A: 2.0% of totals:	670.99	6,024.27	6,695.26
or			
B: Alternative Assessment:			
Assessed by:	J.R.		
(name)		(name)	

### Attachment #1

Key	Quantity	Botanical Name	Common Name	Size	Condition
A	29	Geaia Tricantata Inermis	Embured Thornless, Honey Locust	3' cal	-
B	15	Q. Palustris	Pin Oak	2 1/2 - 3' cal	-
C	17	Pyrus Calleryana "Bradford"	Bradford Callery Pear	2 1/2 - 3' cal	-
D	9	Malus Snow Drift	Flowering Crab	2 1/2' cal.	-
E	8	Syringa Vulgaris	Common Lilac	6' h.	-
F	15	J. Chinensis Pfizeriana	Chinese Juniper	3' sp.	-
<p>Notes</p> <ol style="list-style-type: none"> <li>Existing trees to remain prior to clearing. Contractor shall request architect to walk site to approve trees to be removed.</li> <li>4" loam &amp; seed at disturbed areas bark mulch at planting beds.</li> </ol>					

	Public			Private		
	qty	Unit cost	total	qty	Unit cost	total
<u>Arceas</u>	<u>7</u>	<u>298.00</u>	<u>2,086.00</u>	<u>63</u>	<u>298.00</u>	<u>18,774.00</u>
<u>Lilac</u>				<u>3</u>	<u>215.00</u>	<u>645.00</u>
<u>Juniper</u>				<u>15</u>	<u>50.00</u>	<u>750.00</u>

Attachment #2

<u>Item</u>	<u>PUBLIC</u>			<u>PRIVATE</u>		
	<u>Quantity</u>	<u>Unit Cost</u>	<u>Subtotal</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Subtotal</u>
Clearing	N/A			1 L.S.	\$1,000.00	\$1,000.00
Stumping	N/A			35 c.y.s.	\$15.00	\$525.00
Sub-base gravel for Parking & Roadways	70 c.y.s.	\$11.75	\$822.50	2650 c.y.s	\$11.75	\$31,137.50
Base Gravel for Parking & Roadways	14 c.y.s.	\$18.00	\$252.00	530 c.y.s.	\$18.00	\$9,540.00
Binder Pvt.	18 ts.	\$36.50	\$657.00	498 ts.	\$36.50	\$18,177.00
Finish Pvt.	9 ts.	\$37.00	\$333.00	359 ts.	\$37.00	\$13,283.00
Exc. & Bfill for Site Elect. Items	8 L.F.	\$7.00	\$56.00	967 L.F.	\$7.00	\$5,769.00
Striping	N/A			1 L.S.	\$1,300.00	\$1,300.00
Stabilized Construction Entrances	N/A			2 ea.	\$1,500.00	\$3,000.00
Loam for Site	N/A			780 c.y.s.	\$18.00	\$14,040.00
Seed & Mulch Site	N/A			56 units	\$40.00	\$2,240.00

## MEMORANDUM

**DATE:** September 5, 2001  
**TO:** Sarah Hopkins, Senior Planner  
**FROM:** Stephen R. Bushey, P.E.  
**SUBJECT:** Intermodal Transfer Facility

---

I have reviewed the materials dated 8/17/01 for the above project and find that they are in substantial conformance with the City's rules and regulations. The project is subject to the provisions of 38 M.R.S.A. Section 420-D and Chapters 500 and 502 of the MEDEP Regulations. Pursuant to the City of Portland's Delegated review authority the following Findings of Facts is made:

### Stormwater Quantity Standards:

The stormwater quantity plan submitted by the applicant has been reviewed by the City staff and the findings are as follows:

- A. Peak flow from the site and peak flow of Receiving waters:  
The applicant has proposed a closed stormwater collection systems that, based on the estimates or pre and post development stormwater runoff flows obtained by using the SCS TR-20 methodology, results in post development flows being at or below pre-development levels from the site as well as in the receiving waters below.
- B. Maintenance:  
All components of the stormwater collection system will be maintained by the applicant in compliance with State and Local Standards.
- C. Discharge to Freshwater Wetlands:  
Freshwater wetlands will receive stormwater in the same manner as before the development

### Stormwater Quality Standards:

The proposed project includes the installation of a Vortech Model 7000 stormwater treatment system to remove grit and suspended solids from stormwater prior to discharge to the stream on the ravine. The installation of these measures will meet the requirements of the State and local standards for the treatment of stormwater runoff.

Based on these findings the City of Portland concludes the pursuant to 38 M.S.R.A Section 420-D and chapters 500 and 502 of the MEDEP regulations and The City's Technical Standards:

- A. The applicant has made adequate provision to ensure that the development will meet the stormwater quantity and quality standards for : (1) Peak flow from the site and the receiving water; (2) Maintenance; and (3) Discharge to freshwater wetlands.

Therefore, I recommend the project be presented to the Portland Planning Board for approval, assuming no other issues from Staff or the Board.

If you have any questions please call.

PROFESSIONAL SERVICES AGREEMENT

OCTOBER CORPORATION  
373 PRESUMSCOT STREET SITE  
C/O BOULOS PROPERTY MANAGEMENT  
ONE CANAL PLAZA  
PORTLAND, MAINE USA  
and  
FIELD SERVICES, INC.  
PORTLAND, MAINE USA

ARTICLE 1

PARTIES TO AND PURPOSE OF THE AGREEMENT

- 1.1 On November 26, 2001, this Professional Services Agreement (Agreement) is made between Field Services, Inc. (CONTRACTOR), with principal offices located at Portland, Maine, USA, and Boulos Property Management for OCTOBER CORPORATION (OWNER), with principal offices located at Portland, Maine, USA.
- 1.2 The purpose of this Agreement is to authorize Field Services, Inc. to inspect and maintain the Vortechincs Model 7000 Stormwater Treatment System (STS) at 373 Presumscot Street, Portland, Maine, on behalf of the OWNER; to authorize Field Services, Inc. to represent the OWNER to the governing regulatory authority concerning issues related to the inspection and maintenance of the STS; and to bind both parties to the terms herein.

ARTICLE 2

RESPONSIBILITIES OF FIELD SERVICES, INC. (CONTRACTOR)

The CONTRACTOR will:

- 2.1 Designate a specific representative who will be responsible for the administration and monitoring of this agreement, and who will act as liaison with Boulos Property Management/October Corp. (OWNER) and regulatory agencies.
- 2.2 Perform inspection and/or maintenance activities in accordance with previously accepted proposals and/or plans referenced herein or attached.
- 2.3 Use its best professional judgment concerning the execution of the site inspection and/or maintenance work schedule considering



**FSI PROFESSIONAL SERVICES AGREEMENT # 935**

**November 2001**

local weather cycles, site access, labor disputes, etc. beyond its control.

- 2.4 To the best of its professional ability, represent the OWNER in a truthful and responsible manner to the regulatory authority.
- 2.5 During the course of the execution of the annual inspection and maintenance program, make observations of system defects beyond the scope of the annual inspection and maintenance program and make recommendations for their remedy.
- 2.6 With authorization from the OWNER, enter into agreements with qualified subcontractors to provide specific maintenance or construction services beyond the scope of services in this Agreement as may be required to assure proper function of the facilities.
- 2.7 Give prompt written notice to OWNER whenever Field Services, Inc. observes or otherwise becomes aware of any defect in this Agreement.

**ARTICLE 3**

**RESPONSIBILITIES OF BOULOS/OCTOBER CORP. (OWNER)**

The OWNER will:

- 3.1 Designate a specific representative who will be responsible for the administration and monitoring of this agreement, and who will act as liaison with Field Services, Inc. and regulatory agencies.
- 3.2 Provide Field Services, Inc. with two (2) copies of the Site Stormwater Treatment System Operation and Maintenance Plan, and two copies of the Design Plans of the Stormwater Treatment System prepared for the site. If Field Services, Inc. has developed the O&M Plan for this site, this paragraph does not apply.
- 3.3 Guarantee access to the property, grant approval for use of private hydrants, and make all provisions for Field Services, Inc. to enter upon public and private lands as required for Field Services, Inc. to perform its services under this Agreement.
- 3.4 Give prompt written notice to Field Services, Inc. whenever the OWNER observes or otherwise becomes aware of any defect in the services of this Agreement.
- 3.5 Provide any legal services which may be necessary to implement the AGREEMENT.

**ARTICLE 4**  
**PROJECT SCHEDULE**

The CONTRACTOR will begin work upon execution of this Agreement and will conduct the required inspection and maintenance in accordance with the schedules defined in the site O&M Plan, or any modification thereto.

**ARTICLE 5**  
**COMPENSATION**

The CONTRACTOR shall be compensated for services in accordance with the following schedule:

A. Stormwater Treatment System Compliance Program

Annual Inspection/Reporting/Recordkeeping/Cleaning	\$1,050.00
Sediment Disposal	\$100.00/ton

B. Administrative & Management Services outside the STS Compliance Program shall be compensated as follows\*:

Consulting Rate \$ 95.00/hour or quoted fixed price

\*Consulting services including, but not limited to, modifying site drawings and O&M plans, negotiating with regulatory authorities, and construction or special project management will be provided as needed and only at OWNER's request, and are not included in this AGREEMENT.

**ARTICLE 6**  
**PAYMENT**

Payment for services rendered by Field Services, Inc. shall be in accordance with the following:

6.1 Invoices will be submitted by Field Services, Inc. at least annually at completion of the work and will document the services provided during the period. If documentation of services is not satisfactory to the OWNER, Field Services, Inc. shall be notified within five (5) working days of receipt of invoice.

6.2 Payment shall be made by the OWNER within thirty (30) days of receipt of the invoice.

6.3 Payments due Field Services, Inc. under this AGREEMENT shall be subject to interest of one and one-half percent (1-1/2%) per month commencing thirty (30) days after the date of invoice.

**ARTICLE 7**  
**INSURANCE**

The CONTRACTOR shall, during the performance of the work contemplated in the Agreement, keep in force at least the following insurance:

COMMERCIAL GENERAL LIABILITY (per Occur):

General Aggregate	\$2,000,000
Products-COMP/OP AGG	\$2,000,000
Personal & ADV Injury	\$1,000,000
Each Occurrence	\$1,000,000

WORKERS COMP: AS REQUIRED BY MAINE LAW  
AUTOMOBILE LIABILITY: AS REQUIRED BY MAINE LAW

**ARTICLE 8**  
**GENERAL CONSIDERATIONS**

8.1 The CONTRACTOR shall notify the OWNER'S designated representative of any upcoming inspection at least seven days prior to the inspection.

8.2 The CONTRACTOR shall maintain all inspection logs, reports, and data on file at his office for a period of 5 years, and shall make such records available during regular working hours for inspection by the OWNER or appropriate designated agencies. The CONTRACTOR shall make a report of completed maintenance and/or inspection to the regulatory authority as prescribed in the site O&M Plan.

8.3 The CONTRACTOR shall comply with all local, State and Federal safety rules and regulations which may apply to any services provided under this Agreement, and shall hold the OWNER harmless from any and all liability and claims which may result from Field Services, Inc.'s operations.

8.4 The term of the Agreement shall be THREE years, except that the OWNER will have the option to extend the Agreement for an additional TWO years, subject to a mutually agreeable adjustment to the compensation schedule.

**ARTICLE 9**  
**TERMINATION OF AGREEMENT**

This AGREEMENT may be terminated by either party by thirty (30) days' written notice to the other party without cause; by mutual written agreement to the parties; or by either party on one day's written notice to the other in the event of substantial failure to perform in accordance with the terms hereof by the other party through no fault of the terminating party. If this AGREEMENT is terminated, Field Services,

Inc. shall be paid for the extent of services performed by him to the effective date of termination.

ARTICLE 10  
DELEGATION OF DUTIES

Neither the OWNER nor Field Services, Inc. shall delegate his duties in this AGREEMENT without the written consent of the other party.

ARTICLE 11  
EXTENT OF AGREEMENT


This AGREEMENT represents the entire agreement for RECURRING INSPECTION AND MAINTENANCE services to be rendered at this site between the OWNER and Field Services, Inc. and supersedes all prior negotiations, representations or agreements, either written or oral, unless attached to this AGREEMENT.

ARTICLE 12  
GOVERNING LAW

The terms of this AGREEMENT shall be construed and interpreted under, and all respective rights and duties of the parties shall be governed by, the laws of the State of Maine.

IN WITNESS WHEREOF the authorized parties hereto have made and executed this Agreement as of the day and year first written above.

OCTOBER CORP. c/o BOULOS PROPERTY  
MANAGEMENT  
(OWNER):


by 

PAUL UREBECK, VP  
Printed Name/Title

12/7/01  
Date

Agent, October Corp

FIELD SERVICES, INC.  
(CONTRACTOR):

by 

Alan S. Lyscars, President  
Printed Name/Title

11/26/01  
Date

FSI PROFESSIONAL SERVICES AGREEMENT # 935  
November 2001

ATTACHED BY REFERENCE

1. PRESUMSCOT STREET BUDGET PROPOSAL, Field Services, Inc., NOVEMBER 12, 2001.



**CITY OF PORTLAND**

October 11, 2001

Morris Fisher  
CB Richard Ellis/TheBoulos Co.  
One Canal Plaza  
Portland, ME 04101

re: 383 Presumpscot Street Intermodal Facility CBL: 420 A001001

Dear Mr. Fisher:

On September 25, 2001, the Portland Planning Board approved the site plan for the intermodal facility/parking lot at 383 Presumpscot Street. Since the Planning Board's approval, the Planning Department has received a request from you to begin site work due to timing concerns. We have received and approved your cost estimate for the performance guarantee and are waiting for the final paperwork to be submitted, in addition to the inspection fee.

Under the authority granted in Section 14-540(b)(2), your contractor may commence site work after holding a preconstruction meeting with our Development Review Coordinator, Jay Reynolds. You may reach Mr. Reynolds at 874-8632.

We look forward to receiving and processing the performance guarantee paperwork early next week.

Sincerely,

Alexander Jaegerman,  
Chief Planner

cc.: — Sarah Hopkins, Development Review Services Manager  
P. Samuel Hoffses, Building Inspector  
Marge Schmuckal, Zoning Administrator  
Tony Lombardo, Project Engineer  
Jay Reynolds, Development Review Coordinator  
William Bray, Director of Public Works  
Jeff Tarling, City Arborist  
Penny Littell, Associate Corporation Counsel  
Lt. Gaylen McDougall, Fire Prevention  
Inspection Department  
Lee Urban, Director of Economic Development  
Don Hall, Appraiser, Assessor's Office  
Susan Doughty, Assessor's Office  
Approval Letter File

**CB**  **Richard Ellis**  
Boulos Property Management

One Canal Plaza  
Portland, ME 04101  
207.871.1290 Tel  
207.772.2647 Fax  
www.boulos.com

December 12, 2001

Ms. Sarah Hopkins  
Planning Department  
City of Portland  
389 Congress Street  
Portland, ME 04101

RE: Intermodal Transfer Facility  
273 Presumpscot Street


Dear Sarah:

Enclosed please find a copy of the maintenance agreement October Corporation has executed with Field Services, Inc., for maintenance of the Vortechincs unit at the above referenced property.

I understand you needed a copy of this contract for your records.

Please let me know if you have any questions.

Sincerely,



KIM A. FARRAR  
Development Coordinator

Encl.

**SITE REVIEW  
PRE-APPLICATION**

**383 PRESUMPCOT STREET  
PORTLAND, MAINE**

**OCTOBER CORPORATION  
PORTLAND, MAINE**

**JUNE 2001**

***SME***



*Sevee & Maher Engineers, Inc.*  
*Waste Management and Hydrogeologic Consultants*  
*Cumberland Center, Maine*





## Statement of Financial Position 2000

Year Ended December 31, 2000

### ASSETS

Investments, at market	\$ 54,163,218
Cash and cash equivalents	100,451
Beneficial interest in trust	157,558,327
Federal excise tax receivable	54,528
Program-related investments	8,458,063
Assets held in title-holding corporation	73,735,541
Property and equipment, net of accumulated depreciation of \$83,955 at December 31, 2000	309,902
Other assets	<u>135,752</u>
<b>TOTAL ASSETS</b>	<b><u>\$294,515,782</u></b>

### LIABILITIES

Payables and other liabilities	\$ 26,460
Deferred federal excise tax	118,000
<b>TOTAL LIABILITIES</b>	<b><u>144,460</u></b>

### NET ASSETS

Unrestricted net assets	<u>294,371,322</u>
<b>TOTAL LIABILITIES AND NET ASSETS</b>	<b><u>\$ 294,515,782</u></b>

Arts, Culture & Humanities | Education | Environment | Health |  
 Human Services | Other | Public/Society Benefit | Activities 2000 |  
Allocation Across Fields

**383 PRESUMPCOT STREET  
APPLICATION FOR SITE PLAN APPROVAL  
BY OCTOBER CORPORATION**

The October Corporation, P.O. Box 17516, Portland, Maine 04112-8516, is requesting site plan approval for the development of a intermodal transfer facility on the property it owns at 383 Presumpscot Street in Portland, Maine. The October Corporation (a wholly owned subsidiary of the Libra Foundation) is currently developing an office park in New Gloucester and owns several office buildings in downtown Portland. The proposed facility will provide an opportunity to utilize a mass transportation system for the commuter traffic associated with the Corporation's projects. October Corporation is currently investigating arrangements with area bussing firms. The parcel's location adjacent to the St. Lawrence railroad would also provide an opportunity for commuter rail service in the future.

The subject parcel is approximately 4.08 acres in size, with 650 feet of frontage on Presumpscot Street. The rear of the property borders the St. Lawrence railroad property. The site has historically been used by various contracting firms. The site is gently sloping towards the rear of the property and towards the southern boundary. A ravine, which carries stormwater from this section of Presumpscot Street to the ocean, is located on the south side of the property.

The site plan depicts the potential for a future build-out of the property. Initially, a 109-space parking lot would be constructed, along with a bus drop-off and loading area. The existing driveway entrance to the site would serve as one entrance to the parking lot, and a second entrance would be created approximately 250 feet south of the existing entrance. If the demand exists, an additional 72 spaces can be added on the north side of the parking facility. The site plan also depicts a commuter station of 1250 square feet, consisting of a small waiting room, a ticket booth, and a rest room. The station would be constructed once the facility's demand is established.

Power and telephone service exist on overhead poles along Presumpscot Street. Underground conduits for these services will be brought onto the site during the construction of the first phase of the parking lot. The Portland Water District has a 10-inch main within the Presumpscot Street

right-of-way and currently has a service on-site. The wastewater generated from the facility is estimated to be approximately 550 gallons per day. The public sewer is located approximately 400 feet south of the parcel and as a result of the grades on Presumpscot Street, the sewer main cannot be extended to serve the site. An on-site subsurface wastewater disposal system will be utilized to serve the future commuter station. The location of the system is shown on the site plan and a HHE-200 form is included with this application. Solid waste generated at the site will be minimal, a cleaning service will dispose of this at the end of each business day.

The proposed project will not exceed the threshold of creating three acres of impervious area and thus will not require a Maine Department of Environmental Protection (MDEP) Site Location Permit. The only wetlands that exist on the site are located within the ravine along the southern property line. There are no wetlands being impacted by the proposed project.

Over the years, the site has been filled and graded and thus there are no unusual natural areas, wildlife or fisheries habitats on the site. The soils are mapped as a Buxton silty loam. Test pits were excavated on the site to determine the depth of fill placed on the site. The test pit locations are shown on the site plan and a copy of the test pit logs are included with this application. The soils are suitable for the proposed project. Temporary and permanent erosion control measures are included on the plans.

The stormwater discharge from the site will be collected by catch basins and transported via the storm drainpipes to Vortech's Model 7000 for sediment removal prior to discharge to the ravine located along the southern property boundary.

In accordance with the submittal requirements included with the Site Plan, are elevations of the future building, a landscaping plan, a lighting plan a boundary survey, a storm water management plan, copies of the deeds and a copy of the Libra Foundation statement of Financial Position 2000.

**CITY OF PORTLAND, MAINE  
SITE PLAN CHECKLIST**

Intermodal Transfer Facility 393 Presumpscott St  
Project Name, Address of Project

I.d. Number

Submitted () & Date	Item	Required Information	Section 14-525 (b,c)
<u>6/26/01</u>	(1)	Standard boundary survey (stamped by a registered surveyor, at a scale of not less than 1 inch to 100 feet and including:	l
<u>6/26/01</u>	(2)	Name and address of applicant and name of proposed development	a
<u>6/26/01</u>	(3)	Scale and north points	b
<u>6/26/01</u>	(4)	Boundaries of the site	c
<u>6/26/01</u>	(5)	Total land area of site	d
<u>6/26/01</u>	(6)	Topography - existing and proposed (2 feet intervals or less)	e
	(7)	Plans based on the boundary survey including:	2
<u>6/26/01</u>	(8)	Existing soil conditions	a
<u>6/26/01</u>	(9)	Location of water courses, marshes, rock outcroppings and wooded areas	b
<u>6/26/01</u>	(10)	Location, ground floor area and grade elevations of building and other structures existing and proposed, elevation drawings of exterior facades, and materials to be used	c
<u>6/26/01</u>	(11)	Approximate location of buildings or other structures on parcels abutting the site	d
<u>6/26/01</u>	(12)	Location of on-site waste receptacles	e
<u>6/26/01</u>	(13)	Public utilities	e
<u>6/26/01</u>	(14)	Water and sewer mains	e
<u>6/26/01</u>	(15)	Culverts, drains, existing and proposed, showing size and directions of flows	e
<u>6/26/01</u>	(16)	Location and dimensions, and ownership of easements, public or private rights-of-way, both existing and proposed	f
<u>6/26/01</u>	(17)	Location and dimensions of on-site pedestrian and vehicular accessways	g
<u>6/26/01</u>	(18)	Parking areas	g
<u>6/26/01</u>	(19)	Loading facilities	g
<u>6/26/01</u>	(20)	Design of ingress and egress of vehicles to and from the site onto public streets	g
<u>6/26/01</u>	(21)	Curb and sidewalks	g
<u>6/26/01</u>	(22)	Landscape plan showing:	h
<u>6/26/01</u>	(23)	Location of existing proposed vegetation	h
<u>6/26/01</u>	(24)	Type of vegetation	h
<u>6/26/01</u>	(25)	Quantity of plantings	h
<u>6/26/01</u>	(26)	Size of proposed landscaping	h
<u>6/26/01</u>	(27)	Existing areas to be preserved	h
<u>6/26/01</u>	(28)	Preservation measures to be employed	h
<u>6/26/01</u>	(29)	Details of planting and preservation specifications	h
<u>N/A</u>	(30)	Location and dimensions of all fencing and screening	i
<u>Location 6/26/01</u>	(31)	Location and intensity of outdoor lighting system	j
	(32)	Location of fire hydrants, existing and proposed	k
<u>6/26/01</u>	(33)	Written statement	c
<u>6/26/01</u>	(34)	Description of proposed uses to be located on site	l
<u>6/26/01</u>	(35)	Quantity and type of residential, if any	l
<u>6/26/01</u>	(36)	Total land area of the site	b2
<u>6/26/01</u>	(37)	Total floor area and ground coverage of each proposed building and structure	b2
	(38)	General summary of existing and proposed easements or other burdens	c3
<u>6/26/01</u>	(39)	Method of handling solid waste disposal	4

<u>6/26/01</u>	(40)	Applicant's evaluation of availability of off-site public facilities, including sewer, water and streets	5
<u>6/26/01</u>	(41)	Description of any problems of drainage or topography, or a representation that there are none	6
	(42)	An estimate of the time period required for completion of the development	7
<u>6/26/01</u>	(43)	A list of all state and federal regulatory approvals to which the development may be subject	8
<u>N/A</u>	(44)	The status of any pending applications	8
<u>N/A</u>	(45)	Anticipated timeframe for obtaining such permits	h8
<u>N/A</u>	(46)	A letter of non jurisdiction	h8
<u>6/26/01</u>	(47)	Evidence of financial and technical capability to undertake and complete the development including a letter from a responsible financial institution stating that it has reviewed the planned development and would seriously consider financing it when approved.	

Note: Depending on the size and scope of the proposed development, the Planning Board or Planning Authority may request additional information, including (but not limited to):

- drainage patterns and facilities;
- erosion and sedimentation controls to be used during construction;
- a parking and/or traffic study;
- a noise study;

- an environmental impact study;
- a sun shadow study;
- a study of particulates and any other noxious emissions; and
- a wind impact analysis.

Other comments:

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

**STORMWATER MANAGEMENT PLAN  
383 PRESUMPCOT STREET  
PORTLAND, MAINE**

**A. INTRODUCTION**

This stormwater management plan for proposed development of a transportation intermodal facility at 383 Presumpscot Street in Portland, Maine was designed to comply with the Maine Department of Environmental Protection (MDEP) Rules for stormwater quantity as outlined in 06-096 CMP, Chapter 500.3 Stormwater Management and using three general objectives of MDEP's Stormwater Management for Maine Best Management Practices (MDEP BMP)(MDEP, 1995):

1. effective drainage
2. flood prevention
3. erosion control

As designed, peak runoff rates for post-development conditions at the site will be less than those from the pre-development conditions.

The pre- and post-development surface water peak runoff rates were evaluated for the watershed in which the intermodal facility development is included. Stormwater flows were calculated for 2-, 10-, and 25-year/24-hour storm events with Type III Soil Conservation Service rainfall distribution and Type 2 antecedent moisture conditions, using HydroCAD computer modeling system by Applied Microcomputer Systems of Chocorua, New Hampshire.

**B. PROJECT DESCRIPTION**

The October Corporation (a wholly owned subsidiary of the Libra Foundation) of Portland, Maine owns a parcel of land at 383 Presumpscot Street in Portland, Maine. The subject parcel is approximately 4.1 acres. The rear of the property borders the St. Lawrence and Atlantic Railroad property. Various contracting firms have historically used the site. The site slopes gently to the

rear of the property and toward a ravine that carries storm water located at the south end of the property. The property is currently vacant and there are two garages remaining on the site.

Proposed site development includes construction of a 171-space parking lot and a 3000 square foot building.

The total existing impervious area within the site is approximately 0.5 acres in pre-development. The intermodel facility project will result in an impervious area of approximately 1.57 acres.

### **C. SITE WATERSHEDS**


The proposed intermodel facility site is situated in the Casco Bay Watershed. The intermodel facility watershed drains to small-unnamed tributaries, which flow eastward approximately 500 feet to their confluence with Casco Bay.

Surficial soils in the watersheds were mapped by the SCS as Paxton, Hollis, and Buxton series soils. For stormwater modeling purposes these soils were modeled as hydrologic soil group (HSG) C soils (see Figure 1).

An upgradient watershed conveys water to the ravine on the south side of the intermodel facility property. This upgradient watershed is located on the west side of Presumpscot Street and extends to the top of Graves Hill as shown on Figure 2. Pre- and post-development conditions for the intermodel facility site are shown on Drawings D-100 and D-101.

#### **Intermodel Facility Watershed Stormwater Flows**

The study area for the intermodel facility watershed consists of approximately 67.5 acres in pre-development and post-development conditions as indicated on Figure 2 and Drawings D-100 and D-101. The area of study consists of two points of analysis for storm water flows.



MAP DESIGNATION	NAME	HYDROLOGIC SOIL GROUP
BuB	BUXTON, SILT LOAM	C
BuC2	BUXTON, SILT LOAM	C
HrB	HOLLIS, FINE SANDY LOAM	C
HrC	HOLLIS, FINE SANDY LOAM	C
HsC	HOLLIS, VERY ROCKY FINE SANDY LOAM	C
HsE	HOLLIS, VERY ROCKY FINE SANDY LOAM	C
PbB	PAXTON, FINE SANDY LOAM	C

REFERENCE: SOIL SURVEY OF CUMBERLAND COUNTY, MAINE BY U.S. DEPT. OF AGRICULTURE, AUGUST 1974. MAPS 76 & 82.

FIGURE 1  
 MEDIUM INTENSITY SOILS MAP  
 OCTOBER CORPORATION  
 INTERMODAL TRANSPORTATION FACILITY  
 PRESUMPCOT STREET  
 PORTLAND, MAINE



**SME**  
 Sevee & Maher Engineers, Inc.



are shown in Drawing D-100. The catchment boundaries and  $T_c$  routing for post-development site conditions are shown in Drawing D-101.

**TABLE 1**  
**SUMMARY OF STORMWATER ROUTING CONDITIONS**  
**PRESUMPCOT STATION**

**PRE-DEVELOPMENT**

Analysis Point	Catchment Area	Area (acres)	$C_N$ (weighted)	$T_c^*$ (min)	Peak Flow** (cfs) (2/10/25-yr storm)
1	1	1.69	85	16.6	2.2/4.3/5.3
2	2	3.24	86	25.2	46.2/108.8/140.8
	217	8.32	72	23.9	
	218	9.46	71	23.9	
	219	44.8	78	19.6	

**POST-DEVELOPMENT**

Analysis Point	Catchment Area	Area (acres)	$C_N$ (weighted)	$T_c^*$ (min)	Peak Flow** (cfs) (2/10/25-yr storm)
1	1	1.05	75	16.5	0.80/1.90/2.51
2	201-219	See HydroCAD Data	See HydroCAD Data	See HydroCAD Data	45.4/107.6/139.4

Notes

\*  $T_c$  is to subcatchment downgradient boundary or detention pond, as applicable.

\*\* Peak flow of analysis point after routing through detention ponds and/or reaches.

As indicated in Table 1, the post-development peak rates of runoff at analysis points 1 and 2 are less than those of pre-development conditions. The decrease in SC-1 peak flow rates is accomplished by decreasing the area of SC-1 in post-development conditions. The decrease in SC-2 peak flow rates is due to allowing peak flows from the site to leave the watershed prior to the peak flows from the upgradient watershed.

#### **D. PROPOSED DRAINAGE FACILITIES**

Surface water at the site will be collected in catch basins, conveyed via the storm drain pipes to a vortex for sediment removal prior to discharge to the ravine located along the southern property border. Locations of catch basins, piping, and the vortex system are shown on Drawing D-101. Catch Basins will consist of 4-foot diameter pre-cast concrete structures. Storm drains will consist of 12, 15, and 18-inch diameter PVC Pipe. The piping system was sized to handle projected flows during the 24-hour/25-year rainfall event. Pipes were also sized to allow from a minimum flow rate of 3.0 feet/second during a 2-year storm event to limit the buildup of grit and sediment in the piping. A Vortech Model 7000 storm water treatment system will be installed to provide removal of grit and suspended solids from storm water prior to discharge to the stream in the ravine.

The design capacity of stormwater drainage structures was based on SCS TR-20 methodology. Pipes were sized using the HydroCAD. Results of pipe sizing are indicated on HydroCAD printouts in Appendix B. Water quality worksheets are contained in Appendix C.

# SME

*Sevee & Maher Engineers, Inc.*  
*Waste Management and Hydrogeologic Consultants*

April 10, 2001

00015.05  
010409pu.doc

Mr. Paul Ureneck  
Boulos Property Management  
One Canal Plaza  
Portland ME 04101

Subject: Subsurface Conditions, 373 Presumpscot Street Property  
Portland, Maine

Dear Paul:

The purpose of this letter is to describe the subsurface conditions encountered in test pits made at the 373 Presumpscot Street Property (i.e., site) on April 6, 2001. Test pits were made to evaluate fill thickness and presence/nonpresence of granular materials suitable for parking lot construction. A total of 20 test pits were excavated using a backhoe supplied by White Bros. Construction of Westbrook, Maine. The test pits were identified as test pits TP-101 through TP-120. The approximate locations of the test pits with respect to the site property boundaries and existing site structures are shown on Figure 1.

The site is generally flat and has two wood frame buildings located along its back (east) side. The south side of the site is filled land as evidenced by abrupt changes in topography and vegetation. The back of the property is paralleled by the Canadian National Railway. The front (west) side of the property is paralleled by Presumpscot Street. The north and south sides of the property are abutted by private ownership.

The native soils encountered at the site consisted of brown and gray silty clays. Where the native silty clays were observed, they were estimated to be medium to stiff in terms of consistency. At several site locations the native silty clay was overlain by clayey fill soil mixed with wood, masonry, pavement, and other debris. Groundwater, in the form of seepage along the test pit sidewalls, was observed within the fill materials. At test pit locations TP-102 and TP-103 a slight oily odor was detected along with oil sheen presence on the test pit seepage. The test pit depths varied from approximately 2 to 8 feet. The deeper test pits generally exhibited the greatest thickness of fill. Essentially, no granular materials suitable for parking lot construction were encountered in the test pits. Table 1 summarizes the soil conditions encountered in the test pits. Excavation of each test pit was typically halted once native soils were encountered in effort to minimize disturbance of the foundation soils for future parking lot construction. Upon completion,

each test pit was backfilled in layers and tamped with the backhoe bucket to obtain compaction.

TABLE 1

Test Pit	Fill Thickness (feet)	Fill Description
TP-101	3.5	Soft brown clayey soil intermixed with pavement, cinders and ash
TP-102	6+	Soft clayey soil intermixed with concrete, wood and rubble
TP-103	5+	Soft clayey soil with many cobbles and small boulders, heavy seepage
TP-104	0	No fill observed (stiff native silty clay)
TP-105	1	Soft brown silty soil
TP-106	NA	Pipe trench with pipe buried 18 inches below ground surface and stone backfill
TP-107	0.5	Soft brown clayey soil intermixed with sand and gravel
TP-108	3+	Soft clayey soil mixed with rubble and large fragments of concrete
TP-109	3	Soft clayey soil intermixed with rubble
TP-110	0.5	Sand and gravel intermixed with clayey soil
TP-111	0.5	Sand and gravel intermixed with clayey soil
TP-112	1	Soft clayey soil and buried wooden log
TP-113	0	No fill observed (stiff native silty clay)
TP-114	2	Soft clayey soil
TP-115	4.5	Soft clayey soil intermixed with wood debris
TP-116	6	Soft clayey soil intermixed with wood debris
TP-117	2.5	Edge of leachfield, 18 inches sand over 12+ inches stone
TP-118	1	Leachfield distribution box, buried below 12 inches stone
TP-119	0.5	Concrete septic tank
TP-120	1	Soft clayey soil

Three buried drainage features were encountered as part of the test pit activities.

1. A leachfield (approximately 18 inches of sand over 12+ inches of stone) and a concrete septic tank (estimated 750 to 1,000 gallons) were encountered adjacent to the east side of the larger of the two site buildings. The approximate location of the tank and leachfield are shown on Figure 1. A concrete distribution box was encountered separating the leachfield and tank. The distribution box was left marked in the field by three concrete blocks. No visible damage was sustained by the leachfield, distribution box, septic tank, or associated piping as result of the test pitting activities. A small portion of the leachfield (north end) was excavated and no pipes were encountered in that area.
2. A catch basin was identified on the front (west) side of the larger site building. An 8- to 10-inch outlet pipe was observed running approximately south from the catch basin at a depth of about 2 feet. The

outlet pipe apparently turns southeast at some distance from the catch basin to discharge near the edge of the eastern property boundary. The approximate location of the catch basin and outlet pipe are shown on Figure 1.

3. A buried concrete tank was observed adjacent to the front of the building. Based on inspection of the tank interior (through the tank accessway), several pipes connect to the tank which appeared to enter the tank from direction(s) parallel to the west wall of the building.

Thank you for allowing Sevee & Maher Engineers, Inc. to assist you in understanding the subsurface conditions at the 373 Presumpscot Street Property. If we can be of any further assistance, or if we can clarify any of the information presented herein, please do not hesitate to contact us.

Respectfully,

SEVEE & MAHER ENGINEERS, INC.

Matthew W. Muzzy, P.E.  
Geo-Environmental Engineer

cc: Robert Arsenault (SME)

**SITE REVIEW PRE-APPLICATION  
MULTI-FAMILY/ATTACHED SINGLE FAMILY DWELLINGS/TWO-FAMILY DWELLING  
OR COMMERCIAL STRUCTURES AND ADDITIONS THERETO**

In the interest of processing your application in the quickest possible manner, please complete the Information below for Site Plan Review

**Note: If you or the property owner owes real estate or personal property taxes or user charges on ANY PROPERTY within the City, payment arrangements must be made before permits of any kind are accepted.**

**Applicant:** October Corporation

**Application Date:** June 26, 2001

**Applicant's Mailing Address:** P.O. Box 17516, Portland, ME 04112

**Consultant/Agent:** Morris Fisher, Boulos Property Management  
Robert Arsenault, P.E. Sevee & Maher Engineers, Inc.

**Project Name/Description:** Intermodal Transfer Facility

**Applicant/Agent Daytime Telephone and FAX:** Fisher: 871-1290  
Arsenault: 829-5016

**Address of Proposed Site:** Presumpscot Street, Portland, Maine

**Assessor's Reference, Chart #, Block, Lot#:** 420-A-001

**Proposed Development (check all that apply):**  New Building  Building Addition  Change of Use  
 Residential  Office  Retail  Manufacturing  Warehouse/Distribution  
 Other (specify) Parking lot

**Proposed Building Square Footage and/or # of Units:** 1250 SF

**Acreage of Site:** 4.08 ac

**Zoning:**

**You must include the following with your application:**

1. A Copy of Your Deed or Purchase and Sale Agreement
2. Nine (9) sets of Site Plan packages containing the information found in the attached sample plans and checklist. (Section 14-522 of the Zoning Ordinance outlines the process, copies are available for review at the counter, photocopies are \$0.25 per page)

I hereby certify that I am the Owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his/her authorized agent. I agree to conform to all applicable laws of this jurisdiction. In addition, if an approval for the proposed project or use described in this application is issued, I certify that the Code Official's authorized representative shall have the authority to enter all areas covered by this approval at any reasonable hour to enforce the provisions of the codes applicable to this approval.

**Signature of applicant:**

October Corporation

By: Boulos Property Management, Agent

By: Morris Fisher, President

June 26, 2001

\_\_\_\_\_  
(Morris Fisher)

**Site Review Fee: Major \$500.00/Minor \$400.00**

**This application is for site review ONLY, a Building Permit application and associated fees will be required prior to construction.**

UU 1 1 1

RR 1 0 1 3 / 1 6 U 2 U

**QUIT CLAIM DEED WITH COVENANT**

KNOW ALL BY THESE PRESENTS, That 383 PRESUMPSCOT STREET, INC., a Maine corporation, with a place of business in Yarmouth, Cumberland County, Maine ("Grantor"), for consideration paid, grants to OCTOBER CORPORATION, a Maine nonprofit corporation, whose mailing address is Three Canal Plaza, Portland, Maine 04112 ("Grantee"), with Quitclaim Covenant, the land and buildings in Portland, Cumberland County, Maine, described more particularly as follows:

A certain lot or parcel of land situated on the easterly sideline of Presumpscot Street in Portland, Cumberland County, Maine, as depicted on a plan entitled "Plan of Land at Presumpscot Street Portland, Maine," dated November 27, 1995 and prepared for Timothy E. Sanders by Land Use Consultants, Inc., being more particularly described as follows:

Commencing at a 5/8 inch rebar with cap marked PLS 1155, which rebar is not depicted on the above-referenced plan, on the easterly sideline of Presumpscot Street, at the southwesterly corner of lot described in a deed from Timothy E. Sanders to Lucie Wing Couture dated November 13, 1996 and recorded in Cumberland County Registry of Deeds in Book 12815, Page 292, thence,

MAINE REAL ESTATE TAX PAID

- S 14°-52'-06" W      A distance of one fifty-one and 00/100 (151.00') feet, along Presumpscot Street, to a stake as depicted on the above referenced plan and the Point of Beginning; thence,
- S 76°-54'-50" E      A distance of two hundred ninety six and 82/100 (296.82') feet to the westerly sideline of the Canadian National Railway Company easement or land; thence,
- S 20°-42'-24" W      A distance of six hundred six and 88/100 (606.88') feet, along the westerly sideline of said Canadian National Railway Company easement or land to a point; thence,
- N 61°-53'-41" W      A distance of two hundred forty one and 36/100 (241.36') feet to Presumpscot Street; thence,
- N 14°-52'-06" E      A distance of five hundred thirty nine and 23/100 (539.23') feet along Presumpscot Street to the Point of Beginning.

The above said metes and bounds contain a total area of 3.50 acres, or 152,617 square feet more or less.

TOGETHER WITH all right, title and interest in and to reversionary rights, if any, in and to said railroad right-of-way of that portion of the Grand Trunk Railroad lying adjacent to the above-described land, later the Canadian National Railway Company., SUBJECT TO said railroad right of way.

TOGETHER WITH all right, title and interest in and to the portion of Presumpscot Street lying adjacent to the above-described land.

IN WITNESS WHEREOF, the said 383 Presumpscot Street, Inc. has caused this instrument to be sealed with its corporate seal and signed in its corporate name by Timothy E. Sanders, its President, this 26<sup>th</sup> day of March, 2001.


383 PRESUMPCOT STREET, INC., a  
Maine corporation

By: *Timothy E. Sanders*  
Timothy E. Sanders  
Its President

STATE OF MAINE  
COUNTY OF CUMBERLAND, ss.

On March 26, 2001, personally appeared the above-named Timothy E. Sanders, President of said corporation in his said capacity, and acknowledged the foregoing to be his free act and deed and the free act and deed of said 383 Presumpscot Street, Inc.

Before me,



SEAL

*Janet D. Eustis*  
Notary Public  
Printed Name: Janet D. Eustis

SEAL

RECEIVED  
RECORDED REGISTRY OF DEEDS  
2001 MAR 28 PM 1:22

CUMBERLAND COUNTY  
*John B. O'Brien*



001924Z

BR1513/10022

QUITCLAIM DEED WITHOUT COVENANT  
RELEASE DEED

KNOW ALL BY THESE PRESENTS, That 383 PRESUMPSCOT STREET, INC., a Maine corporation, with a place of business in Yarmouth, Cumberland County, Maine ("Grantor"), for consideration paid, releases to OCTOBER CORPORATION, a Maine nonprofit corporation, whose mailing address is Three Canal Plaza, Portland, Maine 04112 ("Grantee"), the land in Portland, Cumberland County, Maine, described as follows:

MAINE REAL ESTATE TAX PAID

A certain lot or parcel of land situated on the easterly side of Presumpscot Street in Portland, Cumberland County, Maine, being the "AREA OF UNKNOWN OWNERSHIP" as depicted on a plan entitled "Plan of Land at Presumpscot Street, Portland, Maine," dated November 27, 1995 and prepared for Timothy E. Sanders by Land Use Consultants, Inc., and more particularly described as follows:

Commencing at a 5/8 inch rebar with cap marked PLS 1155, which rebar is not depicted on the above referenced plan, on the easterly sideline of Presumpscot Street, being the southwesterly corner of lot described in a deed from Timothy E. Sanders to Lucie Wing Couture dated November 13, 1996 and recorded in said Registry of Deeds in Book 12815, Page 292; thence,

- S 14°-52'-06" W      A distance of six hundred ninety and 23/100 (690.23') feet, along the easterly sideline of Presumpscot Street, to said "AREA OF UNKNOWN OWNERSHIP" and the Point of Beginning; thence,
- S 61°-53'-41" E      A distance of two hundred forty one and 36/100 (241.36') feet along land formerly of Timothy E. Sanders to the westerly sideline of the Canadian National Railway Company easement or land; thence,
- S 20°-42'-24" W      A distance of one hundred five and 93/100 (105.93') feet, along the westerly sideline of the Canadian National Railway Company easement or

land, to a one inch iron pipe at the northeasterly corner of land now or formerly of Patrick and Victoria E. Miele; thence,

N 62°-48'-28" W A distance of two hundred thirty one and 24/100 (231.24') feet, along northerly sideline of said Miele land, to Presumpscot Street; thence,

N 25°-08'-05" E A distance of nine and 75/100 (9.75') feet, along Presumpscot Street to an angle point on said Presumpscot Street; thence,

N 14°-52'-06" E A distance of one hundred one and 70/100 (101.70') feet, along Presumpscot Street to the Point of Beginning.


The above said metes and bounds contain a total area of 0.58 acres, or 25,203 square feet more or less.

TOGETHER WITH all right, title and interest in and to reversionary rights, if any, in and to said railroad right-of-way of that portion of the Grand Trunk Railroad lying adjacent to the above-described land, later the Canadian National Railway Company, SUBJECT TO said railroad right of way.

TOGETHER WITH all right, title and interest in and to the portion of Presumpscot Street lying adjacent to the above-described land.

IN WITNESS WHEREOF, the said 383 Presumpscot Street, Inc. has caused this instrument to be sealed with its corporate seal and signed in its corporate name by Timothy E. Sanders, its President, this 26<sup>th</sup> day of March, 2001.

383 PRESUMPCOT STREET, INC., a  
Maine corporation

By:   
Timothy E. Sanders  
Its President

SEAL

DR. O J. S. T. S.

STATE OF MAINE  
COUNTY OF CUMBERLAND, ss.

On March 26, 2001, personally appeared the above-named Timothy E. Sanders, President of said corporation in his said capacity, and acknowledged the foregoing to be his free act and deed and the free act and deed of said 383 Presumpscot Street, Inc.

Before me,



Notary Public


Printed Name: Janet D. Eustis

sanders.jfw.Release Deed Unknown Owners Parcel

SEAL

RECEIVED  
RECORDED REGISTRY OF DEEDS  
2001 MAR 28 PM 1:24

CUMBERLAND COUNTY



730

# SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION

Maine Department of Human Services  
Division of Health Engineering, Station 10  
(207) 287-6672 FAX (207) 287-4172

<b>PROPERTY LOCATION</b>		<b>&gt;&gt; Caution: Permit Required -- Attach in Space Below &lt;&lt;</b>	
City, Town, or Plantation	Portland	The Subsurface Wastewater Disposal System <i>shall not</i> be installed until a Permit is attached HERE by the Local Plumbing Inspector. The Permit shall authorize the owner or installer to install the disposal system in accordance with this application and the Maine Subsurface Wastewater Disposal Rules.	
Street or Road	Presumpscoot Trce		
Subdivision, Lot #			
<b>OWNER/APPLICANT INFORMATION</b>			
Name (last, first, MI)	October Comp <span style="float:right">Owner Applicant</span>		
Mailing Address of	c/o Sewer, Water Div. P.O. Box 85A Amherst NH 03021		
<input type="checkbox"/> Owner <input checked="" type="checkbox"/> Applicant			
Daytime Tel. #	829-5016	Municipal Tax Map # _____ Lot # _____	
<b>Owner or Applicant Statement</b>		<b>Caution: Inspections Required</b>	
I state that the information submitted is correct to the best of my knowledge and understand that any falsification is reason for the Department and/or Local Plumbing Inspector to deny a Permit.		I have inspected the installation authorized above and found it to be in compliance with the Subsurface Wastewater Disposal Rules Application.	
Signature of Owner or Applicant _____ Date _____		Local Plumbing Inspector Signature _____ (1st) Date Approved _____ _____ (2nd) Date Approved _____	

PERMIT INFORMATION		
<b>TYPE OF APPLICATION</b>	<b>THIS APPLICATION REQUIRES</b>	<b>DISPOSAL SYSTEM COMPONENT(S)</b>
1. <input type="checkbox"/> First Time System 2. <input checked="" type="checkbox"/> Replacement System Type Replaced: <u>UAC</u> Year Installed: <u>UAC</u> 3. <input type="checkbox"/> Expanded System a. <input type="checkbox"/> One-time exempted b. <input type="checkbox"/> Non-exempted 4. <input type="checkbox"/> Experimental System 5. <input type="checkbox"/> Seasonal Conversion	1. <input checked="" type="checkbox"/> No Rule Variance 2. <input type="checkbox"/> First Time System Variance a. <input type="checkbox"/> Local Plumbing Inspector Approval b. <input type="checkbox"/> State & Local Plumbing Inspector Approval 3. Replacement System Variance a. <input type="checkbox"/> Local Plumbing Inspector Approval b. <input type="checkbox"/> State & Local Plumbing Inspector Approval 4. <input type="checkbox"/> Minimum Lot Size Variance 5. <input type="checkbox"/> Seasonal Conversion Approval	1. <input checked="" type="checkbox"/> Complete Non-engineered System 2. <input type="checkbox"/> Primitive System (graywater & alt toilet) 3. <input type="checkbox"/> Alternative Toilet, specify: _____ 4. <input type="checkbox"/> Non-Engineered Treatment Tank (only) 5. <input type="checkbox"/> Holding Tank, _____ gallons 6. <input type="checkbox"/> Non-engineered Disposal Field (only) 7. <input type="checkbox"/> Separated Laundry System 8. <input type="checkbox"/> Complete Engineered System (2000 gpd or more) 9. <input type="checkbox"/> Engineered Treatment Tank (only) 10. <input type="checkbox"/> Engineered Disposal Field (only) 11. <input type="checkbox"/> Pre-treatment, specify: _____ 12. <input type="checkbox"/> Miscellaneous components
<b>SIZE OF PROPERTY</b>	<b>DISPOSAL SYSTEM TO SERVE</b>	<b>TYPE OF WATER SUPPLY</b>
<u>3.3 ac</u> <input type="checkbox"/> sq. ft. <input checked="" type="checkbox"/> acres	1. <input type="checkbox"/> Single Family Dwelling Unit, No. of Bedrooms: _____ 2. <input type="checkbox"/> Multiple Family Dwelling, No. of Units: _____ 3. <input checked="" type="checkbox"/> Other: <u>Bus Station Terminal</u> SPECIFY _____	1. <input type="checkbox"/> Drilled Well 2. <input type="checkbox"/> Dug Well 3. <input type="checkbox"/> Private 4. <input checked="" type="checkbox"/> Public 5. <input type="checkbox"/> Other: _____
<b>SHORELAND ZONING</b>		
<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		

DESIGN DETAILS (SYSTEM LAYOUT SHOWN ON PAGE 3)			
<b>TREATMENT TANK</b>	<b>DISPOSAL FIELD TYPE &amp; SIZE</b>	<b>GARBAGE DISPOSAL UNIT</b>	<b>DESIGN FLOW</b>
1. <input checked="" type="checkbox"/> Concrete a. <input checked="" type="checkbox"/> Regular b. <input type="checkbox"/> Low Profile 2. <input type="checkbox"/> Plastic 3. <input type="checkbox"/> Other: _____ CAPACITY <u>2000</u> gallons	1. <input type="checkbox"/> Stone Bed 2. <input type="checkbox"/> Stone Trench 3. <input checked="" type="checkbox"/> Proprietary Device a. <input type="checkbox"/> Cluster array c. <input type="checkbox"/> Linear b. <input checked="" type="checkbox"/> Regular load d. <input type="checkbox"/> H-20 load 4. <input type="checkbox"/> Other: _____ SIZE <u>2925</u> sq. ft. <input type="checkbox"/> lin. ft.	1. <input checked="" type="checkbox"/> No 3. <input type="checkbox"/> Maybe 2. <input type="checkbox"/> Yes >> Specify one below: a. <input type="checkbox"/> Multi-compartment Tank b. <input type="checkbox"/> Tanks in Series c. <input type="checkbox"/> Increase in Tank Capacity d. <input type="checkbox"/> Filter on Tank Outlet	<u>545</u> gallons per day BASED ON: 1. <input checked="" type="checkbox"/> Table 501.1 (dwelling unit(s)) 2. <input type="checkbox"/> Table 501.2 (other facilities) SHOW CALCULATIONS - for other facilities - <u>100 passengers x 5 gpd</u> <u>3 employees x 15 gpd</u> <u>545 gpd</u> 3. <input type="checkbox"/> Section 503.0 (meter readings) ATTACH WATER-METER DATA
<b>SOIL DATA &amp; DESIGN CLASS</b>	<b>DISPOSAL FIELD SIZING</b>	<b>PUMPING</b>	
PROFILE CONDITION DESIGN <u>9/C1/1</u> at Observation Hole # <u>101</u> Depth <u>15</u> " Elevation _____ OF MOST LIMITING SOIL FACTOR	1. <input type="checkbox"/> Small -- 2.0 sq. ft./gpd 2. <input type="checkbox"/> Medium -- 2.6 sq. ft./gpd 3. <input type="checkbox"/> Medium-Large -- 3.3 sq. ft./gpd 4. <input type="checkbox"/> Large -- 4.1 sq. ft./gpd 5. <input checked="" type="checkbox"/> Extra Large -- 5.0 sq. ft./gpd	1. <input type="checkbox"/> Not Required 2. <input checked="" type="checkbox"/> May Be Required 3. <input type="checkbox"/> Required >> Specify only for engineered or experimental systems: DOSE: _____ gallons	

### SITE EVALUATOR STATEMENT

I Certify that on 6/13/01 (date) I completed a site evaluation on this property and state that the data reported are accurate and that the proposed system is in compliance with the State of Maine Subsurface Wastewater Disposal Rules (10-144A CMR 241).

William J. Hampson 263 6/13/01  
Site Evaluator Signature SE # Date

William J. Hampson 773-8650  
Site Evaluator Name Printed Telephone #

SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION

Department of Human Services  
Division of Health Engineering  
(207) 287-5672 FAX (207) 287-6172

Town/City/Plantation  
Portland


Street, Road, Subdivision  
Presumpscot Street

Owner's Name  
October Camp

SITE PLAN

Scale 1" = 100' Ft.  
or as shown

SITE LOCATION PLAN  
(Map from Maine Atlas  
recommended)



SOIL DESCRIPTION AND CLASSIFICATION (Location of Observation Holes Shown Above)

Observation Hole TP 1  Test Pit  Boring  
" Depth of Organic Horizon Above Mineral Soil

DEPTH BELOW MINERAL SOIL SURFACE (INCHES)	Texture	Consistency	Color	Mottling
0	Silt loam	Friable	Dull Brown	
10	Silt loam	Friable	Brown	
20	Silty clay	Firm	gray	Common
30	loam			distinct
40				
50				

Soil Classification: 9 C  
 Slope: 0 %  
 Limiting Factor: 15 "  
 Ground Water  
 Restrictive Layer  
 Bedrock  
 Pit Depth

Observation Hole       Test Pit  Boring  
" Depth of Organic Horizon Above Mineral Soil

DEPTH BELOW MINERAL SOIL SURFACE (INCHES)	Texture	Consistency	Color	Mottling
0				
10				
20				
30				
40				
50				

Soil Classification:       
 Slope:      %  
 Limiting Factor:      "  
 Ground Water  
 Restrictive Layer  
 Bedrock  
 Pit Depth

Matthew J. Hampshire  
Site Evaluator Signature

263  
SE =

6/18/01  
Date

730

Department of Human Services  
Division of Health Engineering  
(207) 287-5672 FAX (207) 287-4172

# SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION

Town, City, Plantation  
*Dartmouth*


Street, Road, Subdivision  
*Presumpscot Street*

Owner's Name  
*October Corp*

## SUBSURFACE WASTEWATER DISPOSAL PLAN

*2 1/2" Trunk*

SCALE 1" = 30 FT



*Parking lot - Access Area*

Note: Materials and installation shall be in accordance with existing Subsurface Wastewater Disposal Rules used 0700 as amended.

### FILL REQUIREMENTS

Depth of Fill (Upslope)	<u>22</u>
Depth of Fill (Downslope)	<u>22</u>

LOAM & SEED


### CONSTRUCTION ELEVATIONS

Finished Grade Elevation	_____
Top of Distribution Pipe or Proprietary Device	_____
Bottom of Disposal Area	_____


### ELEVATION REFERENCE POINT

Location & Description	<i>rail 43"</i>
Reference Elevation	<i>0"</i>

### DISPOSAL AREA CROSS SECTION



SCALE:  
VERTICAL: 1" = 3'  
HORIZONTAL: 1" = 5'



*Murray J. Hampton*  
Site Evaluator Signature

*263*  
SE #

*6/18/01*  
Date

**STORMWATER MANAGEMENT PLAN  
383 PRESUMPCOT STREET  
PORTLAND, MAINE**

**JUNE 2001**



**SME**

*Sevee & Maher Engineers, Inc.*  
Waste Management and Hydrogeologic Consultants  
Cumberland Center, Maine

## TABLE OF CONTENTS

<u>Section No.</u>	<u>Title</u>	<u>Page No.</u>
A.	INTRODUCTION .....	1
B.	PROJECT DESCRIPTION .....	1
C.	SITE WATERSHEDS .....	2
D.	PROPOSED DRAINAGE FACILITIES .....	5


### LIST OF APPENDICES

APPENDIX A	STORMWATER MANAGEMENT EXISTING CONDITIONS ANALYSIS
APPENDIX B	STORMWATER MANAGEMENT POST-DEVELOPMENT ANALYSIS and STORM DRSIN PIPE SIZING
APPENDIX C	WATER QUALITY WORKSHEETS
APPENDIX D	RIPRAP APRONS
APPENDIX E	PROJECT DRAWINGS





APPENDIX A

STORMWATER MANAGEMENT  
EXISTING CONDITIONS ANALYSIS



UPGRADIENT WATERSHED



**Drainage Diagram for EXISTING CONDITIONS**  
Prepared by Sevee & Maher Engineers, Inc. 6/19/01  
HydroCAD® 5.96 s/n 001260 © 1986-2001 Applied Microcomputer Systems

**EXISTING CONDITIONS**

Type III 24-hr Rainfall=3.00" (AMC=2)

Prepared by Sevee &amp; Maher Engineers, Inc.

Page 1

HydroCAD® 5.96 s/n 001260 © 1986-2001 Applied Microcomputer Systems

6/20/01

**Subcatchment 1S: Subcatchment SC-1**

Runoff = 2.24 cfs @ 12.20 hrs, Volume= 0.208 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=3.00" (AMC=2)

Area (ac)	CN	Description
1.320	86	Open Space (Poor, C)
0.250	73	Woods (C)
0.070	89	Gravel Drive
0.030	98	Impervious Roof
0.020	98	Impervious Pavement
1.690	85	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.5	100	0.0300	0.1		<b>Sheet Flow, Segment A-B</b> Grass: Dense n= 0.240 P2= 3.00"
3.8	250	0.0240	1.1		<b>Shallow Concentrated Flow, Segment B-C</b> Short Grass Pasture Kv= 7.0 fps
0.3					<b>Direct Entry, Segment C-D</b>
16.6	350	Total			

**Subcatchment 2S: SUBCATCHMENT SC-2**

Runoff = 3.83 cfs @ 12.31 hrs, Volume= 0.417 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=3.00" (AMC=2)

Area (ac)	CN	Description
2.280	86	Open Space (Poor, C)
0.440	73	Woods (Fair, C)
0.220	89	Gravel Drive (C)
0.200	98	Impervious Pavement
0.100	98	Impervious Roof
3.240	86	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.7	100	0.0200	0.1		<b>Sheet Flow, Segment A-B</b> Grass: Dense n= 0.240 P2= 3.00"
2.5	140	0.0180	0.9		<b>Shallow Concentrated Flow, Segment B-C</b> Short Grass Pasture Kv= 7.0 fps
2.8	120	0.0050	0.7		<b>Shallow Concentrated Flow, Segment C-D</b> Nearly Bare & Untilled Kv= 10.0 fps
4.2	250	0.0200	1.0		<b>Shallow Concentrated Flow, Segment D-E</b> Short Grass Pasture Kv= 7.0 fps
0.3	50	0.3000	2.7		<b>Shallow Concentrated Flow, Segment E-F</b> Woodland Kv= 5.0 fps
0.7					<b>Direct Entry, Segment F-G (STWC,135,0.022)</b>
25.2	660	Total			

### Subcatchment 217S: Subcatchment SC-217

Runoff = 4.42 cfs @ 12.33 hrs, Volume= 0.504 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
 Type III 24-hr Rainfall=3.00" (AMC=2)

Area (ac)	CN	Description
6.490	70	Woods (Good,C)
1.530	74	Open Space (Good,C)
0.200	98	Impervious Road
0.100	98	Impervious Roof
8.320	72	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.4	100	0.0500	0.1		<b>Sheet Flow, Segment A-B</b> Woods: Light underbrush n= 0.400 P2= 3.00"
4.8	500	0.1200	1.7		<b>Shallow Concentrated Flow, Segment B-C</b> Woodland Kv= 5.0 fps
3.7					<b>Direct Entry, Segment C-D (STWC,750,0.025)</b>
23.9	600	Total			

### Subcatchment 218S: Subcatchment SC-218

Runoff = 4.65 cfs @ 12.34 hrs, Volume= 0.537 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
 Type III 24-hr Rainfall=3.00" (AMC=2)

Area (ac)	CN	Description
9.260	70	Woods (Good,C)
0.200	98	Impervious Road
9.460	71	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.4	100	0.0500	0.1		<b>Sheet Flow, Segment A-B</b> Woods: Light underbrush n= 0.400 P2= 3.00"
4.8	500	0.1200	1.7		<b>Shallow Concentrated Flow, Segment B-C</b> Woodland Kv= 5.0 fps
3.7					<b>Direct Entry, Segment C-D (STWC,750,0.025)</b>
23.9	600	Total			

## Subcatchment 219S: Subcatchment SC-219

Runoff = 38.67 cfs @ 12.24 hrs, Volume= 3.854 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=3.00" (AMC=2)

Area (ac)	CN	Description
27.400	70	Woods (Good,C)
17.000	91	Urban Industrial Area (C)
0.400	98	Impervious Road
44.800	78	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.7	100	0.1000	0.1		Sheet Flow, Segment A-B
5.0	450	0.0900	1.5		Woods: Light underbrush n= 0.400 P2= 3.00" Shallow Concentrated Flow, Segment B-C
0.6	225	0.1000	6.4		Woodland Kv= 5.0 fps Shallow Concentrated Flow, Segment C-D
2.3					Paved Kv= 20.3 fps Direct Entry, Segment D-E (STWC,450,0.02)
19.6	775	Total			

### Reach 2170R: Reach From Route 9 to Presumpscot Street

Inflow = 4.42 cfs @ 12.33 hrs, Volume= 0.504 af  
Outflow = 4.05 cfs @ 12.57 hrs, Volume= 0.495 af, Atten= 9%, Lag= 14.4 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 3.4 fps, Min. Travel Time= 7.7 min  
Avg. Velocity = 1.6 fps, Avg. Travel Time= 17.2 min

Peak Depth= 0.29'  
Capacity at bank full= 84.51 cfs  
4.00' x 2.00' deep channel, n= 0.035 Length= 1,600.0' Slope= 0.0400 1/  
Side Slope Z-value= 0.3 1'

### Reach 2180R: Reach From Route 9 to Parking Lot

Inflow = 4.65 cfs @ 12.34 hrs, Volume= 0.537 af  
Outflow = 4.54 cfs @ 12.39 hrs, Volume= 0.535 af, Atten= 2%, Lag= 3.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 4.8 fps, Min. Travel Time= 1.5 min  
Avg. Velocity = 2.3 fps, Avg. Travel Time= 3.3 min

Peak Depth= 0.43'  
Capacity at bank full= 59.33 cfs  
2.00' x 2.00' deep channel, n= 0.035 Length= 450.0' Slope= 0.0600 1/  
Side Slope Z-value= 0.5 1'

### Reach 2181R: Reach Parking Lot to CB

Inflow = 4.54 cfs @ 12.39 hrs, Volume= 0.535 af  
Outflow = 4.51 cfs @ 12.41 hrs, Volume= 0.534 af, Atten= 1%, Lag= 1.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 6.2 fps, Min. Travel Time= 0.7 min  
Avg. Velocity = 2.7 fps, Avg. Travel Time= 1.5 min

Peak Depth= 0.15'  
Capacity at bank full= 94.31 cfs  
5.00' x 1.00' deep channel, n= 0.013 Length= 250.0' Slope= 0.0400 '/  
Side Slope Z-value= 0.1 '/

### Reach 2182R: Reach CB to Presump St. Culvert

Inflow = 4.51 cfs @ 12.41 hrs, Volume= 0.534 af  
Outflow = 4.41 cfs @ 12.45 hrs, Volume= 0.533 af, Atten= 2%, Lag= 2.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 8.5 fps, Min. Travel Time= 1.4 min  
Avg. Velocity = 4.5 fps, Avg. Travel Time= 2.6 min

Peak Depth= 0.51'  
Capacity at bank full= 17.99 cfs  
18.0" Diameter Pipe n= 0.012 Length= 700.0' Slope= 0.0250 '/

### Reach 2183R: Culvert Accross Presumpscot Street

Inflow = 42.50 cfs @ 12.28 hrs, Volume= 4.882 af  
Outflow = 42.46 cfs @ 12.28 hrs, Volume= 4.881 af, Atten= 0%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 14.8 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 7.2 fps, Avg. Travel Time= 0.2 min

Peak Depth= 1.18'  
Capacity at bank full= 172.33 cfs  
42.0" Diameter Pipe n= 0.012 Length= 100.0' Slope= 0.0250 '/

### Reach 2184R: Stream Reach Pres. St. to AP-2

Inflow = 42.46 cfs @ 12.28 hrs, Volume= 4.881 af  
Outflow = 42.32 cfs @ 12.31 hrs, Volume= 4.875 af, Atten= 0%, Lag= 1.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 7.0 fps, Min. Travel Time= 0.6 min  
Avg. Velocity = 3.2 fps, Avg. Travel Time= 1.4 min

Peak Depth= 1.17'  
Capacity at bank full= 415.56 cfs  
4.00' x 4.00' deep channel, n= 0.035 Length= 265.0' Slope= 0.0350 '/'  
Side Slope Z-value= 1.0 '/'

### Reach AP-2: (new node)

Inflow = 46.15 cfs @ 12.31 hrs, Volume= 5.291 af  
Outflow = 46.15 cfs @ 12.31 hrs, Volume= 5.291 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

**EXISTING CONDITIONS**

Type III 24-hr Rainfall=4.70" (AMC=2)

Prepared by Sevee &amp; Maher Engineers, Inc.

Page 1

HydroCAD® 5.96 s/n 001260 © 1986-2001 Applied Microcomputer Systems

6/20/01

**Subcatchment 1S: Subcatchment SC-1**

Runoff = 4.33 cfs @ 12.19 hrs, Volume= 0.408 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=4.70" (AMC=2)

Area (ac)	CN	Description
1.320	86	Open Space (Poor, C)
0.250	73	Woods (C)
0.070	89	Gravel Drive
0.030	98	Impervious Roof
0.020	98	Impervious Pavement
1.690	85	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.5	100	0.0300	0.1		<b>Sheet Flow, Segment A-B</b> Grass: Dense n= 0.240 P2= 3.00"
3.8	250	0.0240	1.1		<b>Shallow Concentrated Flow, Segment B-C</b> Short Grass Pasture Kv= 7.0 fps
0.3					<b>Direct Entry, Segment C-D</b>
16.6	350	Total			

**Subcatchment 2S: SUBCATCHMENT SC-2**

Runoff = 7.29 cfs @ 12.30 hrs, Volume= 0.806 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=4.70" (AMC=2)

Area (ac)	CN	Description
2.280	86	Open Space (Poor, C)
0.440	73	Woods (Fair, C)
0.220	89	Gravel Drive (C)
0.200	98	Impervious Pavement
0.100	98	Impervious Roof
3.240	86	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.7	100	0.0200	0.1		<b>Sheet Flow, Segment A-B</b> Grass: Dense n= 0.240 P2= 3.00"
2.5	140	0.0180	0.9		<b>Shallow Concentrated Flow, Segment B-C</b> Short Grass Pasture Kv= 7.0 fps
2.8	120	0.0050	0.7		<b>Shallow Concentrated Flow, Segment C-D</b> Nearly Bare & Untilled Kv= 10.0 fps
4.2	250	0.0200	1.0		<b>Shallow Concentrated Flow, Segment D-E</b> Short Grass Pasture Kv= 7.0 fps
0.3	50	0.3000	2.7		<b>Shallow Concentrated Flow, Segment E-F</b> Woodland Kv= 5.0 fps
0.7					<b>Direct Entry, Segment F-G (STWC,135,0.022)</b>
25.2	660	Total			



### Subcatchment 217S: Subcatchment SC-217

Runoff = 11.69 cfs @ 12.31 hrs, Volume= 1.252 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
 Type III 24-hr Rainfall=4.70" (AMC=2)

Area (ac)	CN	Description
6.490	70	Woods (Good,C)
1.530	74	Open Space (Good,C)
0.200	98	Impervious Road
0.100	98	Impervious Roof
8.320	72	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.4	100	0.0500	0.1		<b>Sheet Flow, Segment A-B</b> Woods: Light underbrush n= 0.400 P2= 3.00"
4.8	500	0.1200	1.7		<b>Shallow Concentrated Flow, Segment B-C</b> Woodland Kv= 5.0 fps
3.7					<b>Direct Entry, Segment C-D (STWC,750,0.025)</b>
23.9	600	Total			

### Subcatchment 218S: Subcatchment SC-218

Runoff = 12.72 cfs @ 12.31 hrs, Volume= 1.366 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
 Type III 24-hr Rainfall=4.70" (AMC=2)

Area (ac)	CN	Description
9.260	70	Woods (Good,C)
0.200	98	Impervious Road
9.460	71	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.4	100	0.0500	0.1		<b>Sheet Flow, Segment A-B</b> Woods: Light underbrush n= 0.400 P2= 3.00"
4.8	500	0.1200	1.7		<b>Shallow Concentrated Flow, Segment B-C</b> Woodland Kv= 5.0 fps
3.7					<b>Direct Entry, Segment C-D (STWC,750,0.025)</b>
23.9	600	Total			

## Subcatchment 219S: Subcatchment SC-219

Runoff = 86.91 cfs @ 12.23 hrs, Volume= 8.515 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=4.70" (AMC=2)

Area (ac)	CN	Description
27.400	70	Woods (Good,C)
17.000	91	Urban Industrial Area (C)
0.400	98	Impervious Road
44.800	78	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.7	100	0.1000	0.1		<b>Sheet Flow, Segment A-B</b> Woods: Light underbrush n= 0.400 P2= 3.00"
5.0	450	0.0900	1.5		<b>Shallow Concentrated Flow, Segment B-C</b> Woodland Kv= 5.0 fps
0.6	225	0.1000	6.4		<b>Shallow Concentrated Flow, Segment C-D</b> Paved Kv= 20.3 fps
2.3					<b>Direct Entry, Segment D-E (STWC,450,0.02)</b>
19.6	775	Total			

### Reach 2170R: Reach From Route 9 to Presumpscot Street

Inflow = 11.69 cfs @ 12.31 hrs, Volume= 1.252 af  
Outflow = 11.16 cfs @ 12.47 hrs, Volume= 1.239 af, Atten= 5%, Lag= 9.7 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 4.9 fps, Min. Travel Time= 5.4 min  
Avg. Velocity = 2.0 fps, Avg. Travel Time= 13.6 min

Peak Depth= 0.55'  
Capacity at bank full= 84.51 cfs  
4.00' x 2.00' deep channel, n= 0.035 Length= 1,600.0' Slope= 0.0400 '/'  
Side Slope Z-value= 0.3 '/'

### Reach 2180R: Reach From Route 9 to Parking Lot

Inflow = 12.72 cfs @ 12.31 hrs, Volume= 1.366 af  
Outflow = 12.55 cfs @ 12.34 hrs, Volume= 1.363 af, Atten= 1%, Lag= 1.9 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 6.6 fps, Min. Travel Time= 1.1 min  
Avg. Velocity = 2.9 fps, Avg. Travel Time= 2.6 min

Peak Depth= 0.80'  
Capacity at bank full= 59.33 cfs  
2.00' x 2.00' deep channel, n= 0.035 Length= 450.0' Slope= 0.0600 '/'  
Side Slope Z-value= 0.5 '/'

### Reach 2181R: Reach Parking Lot to CB

Inflow = 12.55 cfs @ 12.34 hrs, Volume= 1.363 af  
Outflow = 12.34 cfs @ 12.35 hrs, Volume= 1.362 af, Atten= 2%, Lag= 0.8 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 9.0 fps, Min. Travel Time= 0.5 min  
Avg. Velocity = 3.5 fps, Avg. Travel Time= 1.2 min

Peak Depth= 0.28'  
Capacity at bank full= 94.31 cfs  
5.00' x 1.00' deep channel, n= 0.013 Length= 250.0' Slope= 0.0400 '/  
Side Slope Z-value= 0.1 '/

### Reach 2182R: Reach CB to Presump St. Culvert

Inflow = 12.34 cfs @ 12.35 hrs, Volume= 1.362 af  
Outflow = 12.23 cfs @ 12.39 hrs, Volume= 1.360 af, Atten= 1%, Lag= 2.5 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 11.0 fps, Min. Travel Time= 1.1 min  
Avg. Velocity = 5.4 fps, Avg. Travel Time= 2.2 min

Peak Depth= 0.91'  
Capacity at bank full= 17.99 cfs  
18.0" Diameter Pipe n= 0.012 Length= 700.0' Slope= 0.0250 '/

### Reach 2183R: Culvert Accross Presumpscot Street

Inflow = 102.10 cfs @ 12.26 hrs, Volume= 11.113 af  
Outflow = 101.99 cfs @ 12.26 hrs, Volume= 11.112 af, Atten= 0%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 18.6 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 8.5 fps, Avg. Travel Time= 0.2 min

Peak Depth= 1.94'  
Capacity at bank full= 172.33 cfs  
42.0" Diameter Pipe n= 0.012 Length= 100.0' Slope= 0.0250 '/

### Reach 2184R: Stream Reach Pres. St. to AP-2

Inflow = 101.99 cfs @ 12.26 hrs, Volume= 11.112 af  
Outflow = 101.57 cfs @ 12.28 hrs, Volume= 11.103 af, Atten= 0%, Lag= 1.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 9.0 fps, Min. Travel Time= 0.5 min  
Avg. Velocity = 3.8 fps, Avg. Travel Time= 1.2 min

Peak Depth= 1.92'  
Capacity at bank full= 415.56 cfs  
4.00' x 4.00' deep channel, n= 0.035 Length= 265.0' Slope= 0.0350 '/  
Side Slope Z-value= 1.0 '/

### Reach AP-2: (new node)

Inflow = 108.84 cfs @ 12.29 hrs, Volume= 11.909 af  
Outflow = 108.84 cfs @ 12.29 hrs, Volume= 11.909 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

**EXISTING CONDITIONS**

Type III 24-hr Rainfall=5.50" (AMC=2)

Prepared by Sevee &amp; Maher Engineers, Inc.

Page 1

HydroCAD® 5.96 s/n 001260 © 1986-2001 Applied Microcomputer Systems

6/20/01

**Subcatchment 1S: Subcatchment SC-1**

Runoff = 5.33 cfs @ 12.19 hrs, Volume= 0.507 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
1.320	86	Open Space (Poor, C)
0.250	73	Woods (C)
0.070	89	Gravel Drive
0.030	98	Impervious Roof
0.020	98	Impervious Pavement
1.690	85	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.5	100	0.0300	0.1		<b>Sheet Flow, Segment A-B</b> Grass: Dense n= 0.240 P2= 3.00"
3.8	250	0.0240	1.1		<b>Shallow Concentrated Flow, Segment B-C</b> Short Grass Pasture Kv= 7.0 fps
0.3					<b>Direct Entry, Segment C-D</b>
16.6	350	Total			

**Subcatchment 2S: SUBCATCHMENT SC-2**

Runoff = 8.94 cfs @ 12.30 hrs, Volume= 0.997 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
2.280	86	Open Space (Poor, C)
0.440	73	Woods (Fair, C)
0.220	89	Gravel Drive (C)
0.200	98	Impervious Pavement
0.100	98	Impervious Roof
3.240	86	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.7	100	0.0200	0.1		<b>Sheet Flow, Segment A-B</b> Grass: Dense n= 0.240 P2= 3.00"
2.5	140	0.0180	0.9		<b>Shallow Concentrated Flow, Segment B-C</b> Short Grass Pasture Kv= 7.0 fps
2.8	120	0.0050	0.7		<b>Shallow Concentrated Flow, Segment C-D</b> Nearly Bare & Untilled Kv= 10.0 fps
4.2	250	0.0200	1.0		<b>Shallow Concentrated Flow, Segment D-E</b> Short Grass Pasture Kv= 7.0 fps
0.3	50	0.3000	2.7		<b>Shallow Concentrated Flow, Segment E-F</b> Woodland Kv= 5.0 fps
0.7					<b>Direct Entry, Segment F-G (STWC,135,0.022)</b>
25.2	660	Total			

### Subcatchment 217S: Subcatchment SC-217

Runoff = 15.53 cfs @ 12.30 hrs, Volume= 1.655 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
6.490	70	Woods (Good,C)
1.530	74	Open Space (Good,C)
0.200	98	Impervious Road
0.100	98	Impervious Roof
8.320	72	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.4	100	0.0500	0.1		<b>Sheet Flow, Segment A-B</b> Woods: Light underbrush n= 0.400 P2= 3.00"
4.8	500	0.1200	1.7		<b>Shallow Concentrated Flow, Segment B-C</b> Woodland Kv= 5.0 fps
3.7					<b>Direct Entry, Segment C-D (STWC,750,0.025)</b>
23.9	600	Total			

### Subcatchment 218S: Subcatchment SC-218

Runoff = 17.01 cfs @ 12.30 hrs, Volume= 1.815 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
9.260	70	Woods (Good,C)
0.200	98	Impervious Road
9.460	71	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.4	100	0.0500	0.1		<b>Sheet Flow, Segment A-B</b> Woods: Light underbrush n= 0.400 P2= 3.00"
4.8	500	0.1200	1.7		<b>Shallow Concentrated Flow, Segment B-C</b> Woodland Kv= 5.0 fps
3.7					<b>Direct Entry, Segment C-D (STWC,750,0.025)</b>
23.9	600	Total			

## Subcatchment 219S: Subcatchment SC-219

Runoff = 111.19 cfs @ 12.23 hrs, Volume= 10.917 af

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
27.400	70	Woods (Good,C)
17.000	91	Urban Industrial Area (C)
0.400	98	Impervious Road
44.800	78	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.7	100	0.1000	0.1		Sheet Flow, Segment A-B
5.0	450	0.0900	1.5		Woods: Light underbrush n= 0.400 P2= 3.00"
0.6	225	0.1000	6.4		Shallow Concentrated Flow, Segment B-C Woodland Kv= 5.0 fps
2.3					Shallow Concentrated Flow, Segment C-D Paved Kv= 20.3 fps
19.6	775	Total			Direct Entry, Segment D-E (STWC,450,0.02)

### Reach 2170R: Reach From Route 9 to Presumpscot Street

Inflow = 15.53 cfs @ 12.30 hrs, Volume= 1.655 af  
Outflow = 14.95 cfs @ 12.44 hrs, Volume= 1.640 af, Atten= 4%, Lag= 8.7 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 5.4 fps, Min. Travel Time= 4.9 min  
Avg. Velocity = 2.1 fps, Avg. Travel Time= 12.6 min

Peak Depth= 0.66'  
Capacity at bank full= 84.51 cfs  
4.00' x 2.00' deep channel, n= 0.035 Length= 1,600.0' Slope= 0.0400 '/'  
Side Slope Z-value= 0.3 '/'

### Reach 2180R: Reach From Route 9 to Parking Lot

Inflow = 17.01 cfs @ 12.30 hrs, Volume= 1.815 af  
Outflow = 16.81 cfs @ 12.33 hrs, Volume= 1.812 af, Atten= 1%, Lag= 1.8 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 7.2 fps, Min. Travel Time= 1.0 min  
Avg. Velocity = 3.1 fps, Avg. Travel Time= 2.4 min

Peak Depth= 0.96'  
Capacity at bank full= 59.33 cfs  
2.00' x 2.00' deep channel, n= 0.035 Length= 450.0' Slope= 0.0600 '/'  
Side Slope Z-value= 0.5 '/'

### Reach 2181R: Reach Parking Lot to CB

Inflow = 16.81 cfs @ 12.33 hrs, Volume= 1.812 af  
Outflow = 16.71 cfs @ 12.34 hrs, Volume= 1.810 af, Atten= 1%, Lag= 0.6 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 10.1 fps, Min. Travel Time= 0.4 min  
Avg. Velocity = 3.8 fps, Avg. Travel Time= 1.1 min

Peak Depth= 0.33'  
Capacity at bank full= 94.31 cfs  
5.00' x 1.00' deep channel, n= 0.013 Length= 250.0' Slope= 0.0400 '/  
Side Slope Z-value= 0.1 '/

### Reach 2182R: Reach CB to Presump St. Culvert

Inflow = 16.71 cfs @ 12.34 hrs, Volume= 1.810 af  
Outflow = 16.37 cfs @ 12.38 hrs, Volume= 1.808 af, Atten= 2%, Lag= 2.4 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 11.5 fps, Min. Travel Time= 1.0 min  
Avg. Velocity = 5.7 fps, Avg. Travel Time= 2.0 min

Peak Depth= 1.13'  
Capacity at bank full= 17.99 cfs  
18.0" Diameter Pipe n= 0.012 Length= 700.0' Slope= 0.0250 '/

### Reach 2183R: Culvert Accross Presumpscot Street

Inflow = 132.62 cfs @ 12.25 hrs, Volume= 14.364 af  
Outflow = 132.48 cfs @ 12.26 hrs, Volume= 14.363 af, Atten= 0%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 19.7 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 8.9 fps, Avg. Travel Time= 0.2 min

Peak Depth= 2.30'  
Capacity at bank full= 172.33 cfs  
42.0" Diameter Pipe n= 0.012 Length= 100.0' Slope= 0.0250 '/

### Reach 2184R: Stream Reach Pres. St. to AP-2

Inflow = 132.48 cfs @ 12.26 hrs, Volume= 14.363 af  
Outflow = 131.89 cfs @ 12.28 hrs, Volume= 14.353 af, Atten= 0%, Lag= 1.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 9.6 fps, Min. Travel Time= 0.5 min  
Avg. Velocity = 4.0 fps, Avg. Travel Time= 1.1 min

Peak Depth= 2.21'  
Capacity at bank full= 415.56 cfs  
4.00' x 4.00' deep channel, n= 0.035 Length= 265.0' Slope= 0.0350 '/  
Side Slope Z-value= 1.0 '/



### Reach AP-2: (new node)

Inflow = 140.80 cfs @ 12.28 hrs, Volume= 15.350 af  
Outflow = 140.80 cfs @ 12.28 hrs, Volume= 15.350 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

**HYDROCAD WORKSHEET - EXISTING CONDITIONS**

**TIME OF CONCENTRATION (T<sub>c</sub>) - DIRECT ENTRY**

**SUBCATCHMENT**                      SC-1

CHANNEL FLOW		SEGMENT ID			
		C - D			
1	SURFACE DESCRIPTION	GWW			
2	FLOW LENGTH, L (ft)	80			
3	CHANNEL SLOPE, s (ft/ft)	0.088			
4	VELOCITY FROM NEH 4, V (ft/s)	4.2			
5	T <sub>t</sub> = L/60 V, (min)	0.3			

<b>TOTAL T<sub>t</sub>, (min)</b>	<b>0.3</b>
-----------------------------------	------------

**SUBCATCHMENT**                      SC-2

CHANNEL FLOW		SEGMENT ID			
		FG			
1	SURFACE DESCRIPTION	STWC			
2	FLOW LENGTH, L (ft)	135			
3	CHANNEL SLOPE, s (ft/ft)	0.022			
4	VELOCITY FROM NEH 4, V (ft/s)	3.1			
5	T <sub>t</sub> = L/60 V, (min)	0.7			

<b>TOTAL T<sub>t</sub>, (min)</b>	<b>0.7</b>
-----------------------------------	------------

**SUBCATCHMENT**                      SC-217

CHANNEL FLOW		SEGMENT ID			
		C - D			
1	SURFACE DESCRIPTION	STWC			
2	FLOW LENGTH, L (ft)	750			
3	CHANNEL SLOPE, s (ft/ft)	0.025			
4	VELOCITY FROM NEH 4, V (ft/s)	3.4			
5	T <sub>t</sub> = L/60 V, (min)	3.7			

<b>TOTAL T<sub>t</sub>, (min)</b>	<b>3.7</b>
-----------------------------------	------------

SUBCATCHMENT

SC-218

CHANNEL FLOW

		SEGMENT ID			
		C-D			
1	SURFACE DESCRIPTION	STWC			
2	FLOW LENGTH, L (ft)	750			
3	CHANNEL SLOPE, s (ft/ft)	0.025			
4	VELOCITY FROM NEH 4, V (ft/s)	3.4			
5	Tt = L/60 V, (min)	3.7			

TOTAL Tt, (min)	3.7
-----------------	-----

SUBCATCHMENT

SC-219

CHANNEL FLOW


		SEGMENT ID			
		D - E			
1	SURFACE DESCRIPTION	STWC			
2	FLOW LENGTH, L (ft)	450			
3	CHANNEL SLOPE, s (ft/ft)	0.02			
4	VELOCITY FROM NEH 4, V (ft/s)	3.2			
5	Tt = L/60 V, (min)	2.3			

TOTAL Tt, (min)	2.3
-----------------	-----


APPENDIX B

STORMWATER MANAGEMENT  
POST-DEVELOPMENT ANALYSIS

STORM DRAIN PIPE SIZING



**Drainage Diagram for PROPOSED CONDITIONS**  
 Prepared by Sevee & Maher Engineers, Inc. 6/20/01  
 HydroCAD® 5.96 s/n 001260 © 1986-2001 Applied Microcomputer Systems



**PROPOSED CONDITIONS**

Type III 24-hr Rainfall=5.50" (AMC=2)

Prepared by Sevee & Maher Engineers, Inc.

Page 1

HydroCAD® 5.96 s/n 001260 © 1986-2001 Applied Microcomputer Systems

6/21/01

**Subcatchment 1S: SUBCATCHMENT SC-1**

Runoff = 2.51 cfs @ 12.19 hrs, Volume= 0.232 af

$R_2 = 0.8 \text{ cfs}$   
 $R_{10} = 1.93 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
0.250	73	WOODS (FAIR, C)
0.070	89	GRAVEL RR ROW C
0.030	98	Impervious Roof
0.700	74	Open Space (Good, C)
1.050	75	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.5	110	0.0300	0.1		Sheet Flow, Segment A-B Grass: Dense n= 0.240 P2= 3.00"
2.7	200	0.0300	1.2		Shallow Concentrated Flow, Segment B-C Short Grass Pasture Kv= 7.0 fps
0.3					Direct Entry, Segment C-D (GWW,80,0.075)
16.5	310	Total			

**Subcatchment 201S: Subcatchment SC-201**

Runoff = 1.39 cfs @ 11.99 hrs; Volume= 0.102 af

$R_2 = 0.72 \text{ cfs}$   
 $R_{10} = 1.17 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
0.230	98	Impervious Pavement
0.030	74	Open Space (good, C)
0.260	95	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.6	95	0.0100	1.0		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.5	57	0.0100	2.0		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
2.1	152	Total			

1/21

**Subcatchment 202S: Subcatchment SC-202**

Runoff = 1.60 cfs @ 11.99 hrs. Volume= 0.113 af

$R_2 = 0.78 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 1.34 \text{ cfs}$

Area (ac)	CN	Description
0.220	98	Impervious Pavement
0.100	74	Open Areas (Good, C)
0.320	91	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.5	130	0.0200	1.4		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.2	25	0.0100	2.0		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
1.7	155	Total			

**Subcatchment 203S: Subcatchment SC-203**

Runoff = 1.05 cfs @ 11.98 hrs, Volume= 0.084 af

$R_2 = 0.57 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.90 \text{ cfs}$

Area (ac)	CN	Description
0.200	98	Impervious Pavement

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9	65	0.0200	1.2		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.2	30	0.0100	2.0		Shallow Concentrated Flow, Segment C-D Paved Kv= 20.3 fps
1.1	95	Total			

**Subcatchment 204S: Subcatchment SC-204**

Runoff = 0.76 cfs @ 11.99 hrs, Volume= 0.059 af

$R_2 = 0.41 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.65 \text{ cfs}$

Area (ac)	CN	Description
0.140	98	Impervious Roof and Pavement

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.3	10	0.0100	0.6		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
2.0	155	0.0040	1.3		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
2.3	165	Total			

**Subcatchment 205S: Subcatchment SC-205**

Runoff = 0.65 cfs @ 11.99 hrs, Volume= 0.048 af

$R_c = 0.34 \text{ cfs}$

$R_{10} = 0.55 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
0.110	98	Impervious Pavement
0.010	74	Open Areas (Good, C)
0.120	96	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.3	10	0.0100	0.6		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
1.8	135	0.0040	1.3		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
2.1	145	Total			

**Subcatchment 206S: Subcatchment SC-206**

Runoff = 0.59 cfs @ 11.98 hrs, Volume= 0.044 af

$R_2 = 0.29 \text{ cfs}$

$R_{10} = 0.49 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
0.090	98	Impervious Pavement
0.030	74	Open Space (Good, C)
0.120	92	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.6	34	0.0150	1.0		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.2	33	0.0150	2.5		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
0.8	67	Total			

**Subcatchment 207S: Subcatchment SC-207**

Runoff = 0.52 cfs @ 11.98 hrs, Volume= 0.040 af

$R_2 = 0.27 \text{ cfs}$

$R_{10} = 0.44 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

Area (ac)	CN	Description
0.090	98	Impervious Pavement
0.010	74	Open Space (Good, C)
0.100	96	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.5	35	0.0300	1.3		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.5	80	0.0150	2.5		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
1.0	115	Total			

3/27



**Subcatchment 208S: Subcatchment SC-208**

Runoff = 0.49 cfs @ 11.98 hrs, Volume= 0.037 af

$R_2 = 0.25 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.42 \text{ cfs}$

Area (ac)	CN	Description
0.080	98	Impervious Pavement
0.020	74	Open Space (Good, C)
0.100	93	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.5	30	0.0200	1.0		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.3	38	0.0150	2.5		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
0.8	68	Total			

**Subcatchment 209S: Subcatchment SC-209**

Runoff = 0.56 cfs @ 11.98 hrs, Volume= 0.042 af

$R_2 = 0.29 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.47 \text{ cfs}$

Area (ac)	CN	Description
0.090	98	Impervious Pavement
0.020	74	Open Area (Good, C)
0.110	94	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.5	35	0.0300	1.3		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.6	85	0.0150	2.5		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
1.1	120	Total			

**Subcatchment 210S: Subcatchment SC-210**

Runoff = 0.46 cfs @ 11.98 hrs, Volume= 0.035 af

$R_2 = 0.24 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.39 \text{ cfs}$

Area (ac)	CN	Description
0.080	98	Impervious Pavement
0.010	74	Open Area (Good, C)
0.090	95	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.5	43	0.0300	1.3		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.4	70	0.0200	2.9		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
0.9	113	Total			

4/2

### Subcatchment 211S: Subcatchment SC-211

Runoff = 0.57 cfs @ 11.98 hrs, Volume= 0.041 af

$R_2 = 0.27 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.48 \text{ cfs}$

Area (ac)	CN	Description
0.080	98	Impervious Pavement
0.040	74	Open Space (Good, C)
0.120	90	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.5	43	0.0300	1.3		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.4	75	0.0200	2.9		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
0.9	118	Total			

### Subcatchment 212S: Subcatchment SC-212

Runoff = 0.45 cfs @ 11.97 hrs, Volume= 0.035 af

$R_2 = 0.24 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.38 \text{ cfs}$

Area (ac)	CN	Description
0.080	98	Impervious Pavement
0.010	74	Open Space (Good, C)
0.090	95	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.5	43	0.0300	1.3		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.2	43	0.0300	3.5		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
0.7	86	Total			

### Subcatchment 213S: Subcatchment SC-213

Runoff = 0.68 cfs @ 11.98 hrs, Volume= 0.050 af

$R_2 = 0.33 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.57 \text{ cfs}$

Area (ac)	CN	Description
0.100	98	Impervious Pavement
0.040	74	Open Space (Good, C)
0.140	91	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.5	43	0.0300	1.3		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.5	80	0.0200	2.9		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
1.0	123	Total			

**Subcatchment 214S: Subcatchment SC-214**

Runoff = 2.10 cfs @ 12.00 hrs, Volume= 0.144 af

$R_2 = 0.95 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 1.73 \text{ cfs}$

Area (ac)	CN	Description
0.260	98	Impervious Pavement
0.180	74	Open Space (Good, C)
0.440	88	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.5	20	0.0100	0.7		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
1.7	300	0.0200	2.9		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
1.0					Direct Entry, Segment C-D (PA,170,0.02)
3.2	320	Total			

**Subcatchment 215S: Subcatchment SC-215**

Runoff = 0.73 cfs @ 11.98 hrs, Volume= 0.059 af

$R_2 = 0.40 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.62 \text{ cfs}$

Area (ac)	CN	Description
0.140	98	Impervious Pavement

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.4	25	0.0200	1.0		Sheet Flow, Segment A-B Smooth surfaces n= 0.011 P2= 3.00"
0.6	115	0.0220	3.0		Shallow Concentrated Flow, Segment B-C Paved Kv= 20.3 fps
1.0	140	Total			

**Subcatchment 216S: Subcatchment SC-216**

Runoff = 2.35 cfs @ 12.27 hrs, Volume= 0.245 af

$R_2 = 0.75 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 1.80 \text{ cfs}$

Area (ac)	CN	Description
0.710	74	Open Space (Good, C)
0.310	73	Woods (Fair, C)
0.050	89	RR Gravel ROW C
0.040	98	Impervious Roofs
1.110	75	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
18.7	95	0.0100	0.1		Sheet Flow, Segment A-B Grass: Dense n= 0.240 P2= 3.00"
3.7					Direct Entry, Segment B-C (GWW,220,0.005)
0.1					Direct Entry, Segment C-D (STWC,75,0.24)
22.5	95	Total			

*C/*

**Subcatchment 217S: Subcatchment SC-217**

Runoff = 15.53 cfs @ 12.30 hrs, Volume= 1.655 af

$R_2 = 4.42 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 11.69 \text{ cfs}$

Area (ac)	CN	Description
6.490	70	Woods (Good,C)
1.530	74	Open Space (Good,C)
0.200	98	Impervious Road
0.100	98	Impervious Roof
8.320	72	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.4	100	0.0500	0.1		<b>Sheet Flow, Segment A-B</b> Woods: Light underbrush n= 0.400 P2= 3.00"
4.8	500	0.1200	1.7		<b>Shallow Concentrated Flow, Segment B-C</b> Woodland Kv= 5.0 fps
3.7					<b>Direct Entry, Segment C-D (STWC,750,0.025)</b>
23.9	600	Total			

**Subcatchment 218S: Subcatchment SC-218**

Runoff = 17.01 cfs @ 12.30 hrs, Volume= 1.815 af

$R_2 = 4.65 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 12.72 \text{ cfs}$

Area (ac)	CN	Description
9.260	70	Woods (Good,C)
0.200	98	Impervious Road
9.460	71	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.4	100	0.0500	0.1		<b>Sheet Flow, Segment A-B</b> Woods: Light underbrush n= 0.400 P2= 3.00"
4.8	500	0.1200	1.7		<b>Shallow Concentrated Flow, Segment B-C</b> Woodland Kv= 5.0 fps
3.7					<b>Direct Entry, Segment C-D (STWC,750,0.025)</b>
23.9	600	Total			

**Subcatchment 219S: Subcatchment SC-219**

Runoff = 111.19 cfs @ 12.23 hrs, Volume= 10.917 af

$R_2 = 38.67 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 86.91 \text{ cfs}$

Area (ac)	CN	Description
27.400	70	Woods (Good,C)
17.000	91	Urban Industrial Area (C)
0.400	98	Impervious Road
44.800	78	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.7	100	0.1000	0.1		Sheet Flow, Segment A-B Woods: Light underbrush n= 0.400 P2= 3.00"
5.0	450	0.0900	1.5		Shallow Concentrated Flow, Segment B-C Woodland Kv= 5.0 fps
0.6	225	0.1000	6.4		Shallow Concentrated Flow, Segment C-D Paved Kv= 20.3 fps
2.3					Direct Entry, Segment D-E (STWC,450,0.02)
19.6	775	Total			

**Subcatchment 2031S: Subcatchment SC-2031**

Runoff = 0.66 cfs @ 12.16 hrs, Volume= 0.060 af

$R_2 = 0.20 \text{ cfs}$

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Type III 24-hr Rainfall=5.50" (AMC=2)

$R_{10} = 0.51 \text{ cfs}$

Area (ac)	CN	Description
0.280	74	Open Space (Good, C)

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.5	120	0.0300	0.1		Sheet Flow, Segment A-B Grass: Dense n= 0.240 P2= 3.00"

**Reach 201R: Storm Drain Pipe P-201**

Inflow = 1.38 cfs @ 11.99 hrs, Volume= 0.102 af

Outflow = 1.35 cfs @ 12.00 hrs, Volume= 0.101 af, Atten= 3%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 3.5 fps, Min. Travel Time= 0.2 min  
Avg. Velocity = 1.2 fps, Avg. Travel Time= 0.7 min

$R_2 = 0.72 \text{ cfs}$

Peak Depth= 0.50'

Capacity at bank full= 2.73 cfs

12.0" Diameter Pipe n= 0.012 Length= 50.0' Slope= 0.0050 /'

$R_{10} = 1.17 \text{ cfs}$

### Reach 202R: Storm Drain Pipe P-202

Inflow = 2.95 cfs @ 11.99 hrs, Volume= 0.215 af  
Outflow = 2.86 cfs @ 12.00 hrs, Volume= 0.215 af, Atten= 3%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 4.3 fps, Min. Travel Time= 0.3 min  
Avg. Velocity = 1.6 fps, Avg. Travel Time= 0.7 min

Peak Depth= 0.80'  
Capacity at bank full= 2.99 cfs  
12.0" Diameter Pipe n= 0.012 Length= 70.0' Slope= 0.0060 '/

$$Q_2 = 1.47 \text{ cfs}$$
$$Q_{10} = 2.48 \text{ cfs}$$

### Reach 203R: Storm Drain Pipe P-203

Inflow = 4.15 cfs @ 12.00 hrs, Volume= 0.358 af  
Outflow = 3.95 cfs @ 12.01 hrs, Volume= 0.358 af, Atten= 5%, Lag= 0.8 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 5.2 fps, Min. Travel Time= 0.6 min  
Avg. Velocity = 1.8 fps, Avg. Travel Time= 1.6 min

Peak Depth= 0.77'  
Capacity at bank full= 5.86 cfs  
15.0" Diameter Pipe n= 0.012 Length= 180.0' Slope= 0.0070 '/

$$Q_2 = 2.04 \text{ cfs}$$
$$Q_{10} = 3.47 \text{ cfs}$$

### Reach 204R: Storm Drain P-204

Inflow = 0.76 cfs @ 11.99 hrs, Volume= 0.059 af  
Outflow = 0.75 cfs @ 12.00 hrs, Volume= 0.059 af, Atten= 1%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 3.5 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 1.2 fps, Avg. Travel Time= 0.3 min

Peak Depth= 0.32'  
Capacity at bank full= 3.45 cfs  
12.0" Diameter Pipe n= 0.012 Length= 25.0' Slope= 0.0080 '/

$$Q_2 = 0.41 \text{ cfs}$$
$$Q_{10} = 0.65 \text{ cfs}$$

### Reach 205R: Storm Drain Pipe P-205

Inflow = 1.40 cfs @ 11.99 hrs, Volume= 0.107 af  
Outflow = 1.38 cfs @ 12.00 hrs, Volume= 0.107 af, Atten= 1%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 3.5 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 1.2 fps, Avg. Travel Time= 0.3 min

Peak Depth= 0.50'  
Capacity at bank full= 2.78 cfs  
12.0" Diameter Pipe n= 0.012 Length= 25.0' Slope= 0.0052 '/

$$Q_2 = 0.74 \text{ cfs}$$
$$Q_{10} = 1.19 \text{ cfs}$$

### Reach 206R: Storm Drain Pipe P-206

Inflow = 0.59 cfs @ 11.98 hrs, Volume= 0.044 af  
Outflow = 0.58 cfs @ 11.98 hrs, Volume= 0.044 af, Atten= 1%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 3.8 fps, Min. Travel Time= 0.3 min  
Avg. Velocity = 1.3 fps, Avg. Travel Time= 0.8 min

Peak Depth= 0.25'  
Capacity at bank full= 4.23 cfs  
12.0" Diameter Pipe n= 0.012 Length= 60.0' Slope= 0.0120 1'

$$R_2 = 0.29 \text{ cfs}$$
$$R_{10} = 0.49 \text{ cfs}$$

### Reach 207R: Storm Drain Pipe P-207

Inflow = 2.47 cfs @ 11.99 hrs, Volume= 0.190 af  
Outflow = 2.42 cfs @ 11.99 hrs, Volume= 0.190 af, Atten= 2%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 4.0 fps, Min. Travel Time= 0.2 min  
Avg. Velocity = 1.4 fps, Avg. Travel Time= 0.6 min

Peak Depth= 0.73'  
Capacity at bank full= 2.75 cfs  
12.0" Diameter Pipe n= 0.012 Length= 55.0' Slope= 0.0051 1'

$$R_2 = 1.29 \text{ cfs}$$
$$R_{10} = 2.09 \text{ cfs}$$

### Reach 208R: Storm Drain Pipe P-208

Inflow = 0.49 cfs @ 11.98 hrs, Volume= 0.037 af  
Outflow = 0.49 cfs @ 11.98 hrs, Volume= 0.037 af, Atten= 1%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 3.6 fps, Min. Travel Time= 0.3 min  
Avg. Velocity = 1.2 fps, Avg. Travel Time= 0.8 min

Peak Depth= 0.23'  
Capacity at bank full= 4.23 cfs  
12.0" Diameter Pipe n= 0.012 Length= 60.0' Slope= 0.0120 1'

$$R_2 = 0.25 \text{ cfs}$$
$$R_{10} = 0.42 \text{ cfs}$$

### Reach 209R: Storm Drain Pipe P-209

Inflow = 3.46 cfs @ 11.99 hrs, Volume= 0.269 af  
Outflow = 3.45 cfs @ 11.99 hrs, Volume= 0.269 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 5.6 fps, Min. Travel Time= 0.0 min  
Avg. Velocity = 2.0 fps, Avg. Travel Time= 0.1 min

Peak Depth= 0.74'  
Capacity at bank full= 3.86 cfs  
12.0" Diameter Pipe n= 0.012 Length= 15.0' Slope= 0.0100 1'

$$R_2 = 1.79 \text{ cfs}$$
$$R_{10} = 2.93 \text{ cfs}$$

### Reach 210R: Storm Drain Pipe P-210

Inflow = 7.83 cfs @ 12.00 hrs, Volume= 0.662 af  
Outflow = 7.75 cfs @ 12.00 hrs, Volume= 0.662 af, Atten= 1%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 7.4 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 2.8 fps, Avg. Travel Time= 0.3 min

$$R_2 = 3.92 \text{ cfs}$$
$$R_{10} = 6.57 \text{ cfs}$$

Peak Depth= 1.00'  
Capacity at bank full= 8.01 cfs  
15.0" Diameter Pipe n= 0.012 Length= 55.0' Slope= 0.0131 1'

### Reach 211R: Storm Drain Pipe P-211

Inflow = 8.31 cfs @ 12.00 hrs, Volume= 0.704 af  
Outflow = 8.09 cfs @ 12.01 hrs, Volume= 0.703 af, Atten= 3%, Lag= 0.4 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 5.7 fps, Min. Travel Time= 0.3 min  
Avg. Velocity = 2.1 fps, Avg. Travel Time= 0.9 min

$$R_2 = 4.14 \text{ cfs}$$
$$R_{10} = 6.98 \text{ cfs}$$

Peak Depth= 1.15'  
Capacity at bank full= 8.81 cfs  
18.0" Diameter Pipe n= 0.012 Length= 110.0' Slope= 0.0060 1'

### Reach 212R: Storm Drain Pipe P-212

Inflow = 0.45 cfs @ 11.98 hrs, Volume= 0.035 af  
Outflow = 0.45 cfs @ 11.98 hrs, Volume= 0.035 af, Atten= 1%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 3.5 fps, Min. Travel Time= 0.3 min  
Avg. Velocity = 1.2 fps, Avg. Travel Time= 0.8 min

$$R_2 = 0.24 \text{ cfs}$$
$$R_{10} = 0.38 \text{ cfs}$$

Peak Depth= 0.22'  
Capacity at bank full= 4.23 cfs  
12.0" Diameter Pipe n= 0.012 Length= 55.0' Slope= 0.0120 1'

### Reach 213R: Storm Drain Pipe P-213

Inflow = 11.99 cfs @ 12.00 hrs, Volume= 0.991 af  
Outflow = 11.86 cfs @ 12.01 hrs, Volume= 0.990 af, Atten= 1%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 7.7 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 2.9 fps, Avg. Travel Time= 0.3 min

$$R_2 = 5.89 \text{ cfs}$$
$$R_{10} = 10.04 \text{ cfs}$$

Peak Depth= 1.22'  
Capacity at bank full= 11.98 cfs  
18.0" Diameter Pipe n= 0.012 Length= 55.0' Slope= 0.0111 1'



### Reach 214R: Storm Drain Pipe P-214

Inflow = 2.82 cfs @ 12.00 hrs, Volume= 0.203 af  
Outflow = 2.80 cfs @ 12.00 hrs, Volume= 0.203 af, Atten= 1%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 8.4 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 2.7 fps, Avg. Travel Time= 0.2 min

$$R_2 = 1.33 \text{ cfs}$$

$$R_{10} = 2.34 \text{ cfs}$$

Peak Depth= 0.44'  
Capacity at bank full= 7.01 cfs  
12.0" Diameter Pipe n= 0.012 Length= 30.0' Slope= 0.0330 '/'

### Reach 215R: Storm Drain Pipe P-215

Inflow = 0.73 cfs @ 11.98 hrs, Volume= 0.059 af  
Outflow = 0.73 cfs @ 11.98 hrs, Volume= 0.059 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 3.8 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 1.3 fps, Avg. Travel Time= 0.3 min

$$R_2 = 0.40 \text{ cfs}$$

$$R_{10} = 0.62 \text{ cfs}$$

Peak Depth= 0.30'  
Capacity at bank full= 3.86 cfs  
12.0" Diameter Pipe n= 0.012 Length= 20.0' Slope= 0.0100 '/'

### Reach 2031R: Reach from SC 2031 to CB-203

Inflow = 0.66 cfs @ 12.16 hrs, Volume= 0.060 af  
Outflow = 0.62 cfs @ 12.26 hrs, Volume= 0.060 af, Atten= 6%, Lag= 5.6 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 0.6 fps, Min. Travel Time= 2.7 min  
Avg. Velocity = 0.5 fps, Avg. Travel Time= 3.2 min

$$R_2 = 0.20 \text{ cfs}$$

$$R_{10} = 0.51 \text{ cfs}$$

Peak Depth= 0.01'  
Capacity at bank full= 1,038.64 cfs  
100.00' x 1.00' deep channel, n= 0.020 Length= 95.0' Slope= 0.0200 '/  
Side Slope Z-value= 0.1 '/'

### Reach 2170R: Reach From Route 9 to Presumpscot Street

Inflow = 15.53 cfs @ 12.30 hrs, Volume= 1.655 af  
Outflow = 14.95 cfs @ 12.44 hrs, Volume= 1.640 af, Atten= 4%, Lag= 8.7 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 5.4 fps, Min. Travel Time= 4.9 min  
Avg. Velocity = 2.1 fps, Avg. Travel Time= 12.6 min

$$R_2 = 4.42 \text{ cfs}$$

$$R_{10} = 11.69 \text{ cfs}$$

Peak Depth= 0.66'  
Capacity at bank full= 84.51 cfs  
4.00' x 2.00' deep channel, n= 0.035 Length= 1,600.0' Slope= 0.0400 '/  
Side Slope Z-value= 0.3 '/'

### Reach 2180R: Reach From Route 9 to Parking Lot

Inflow = 17.01 cfs @ 12.30 hrs, Volume= 1.815 af  
Outflow = 16.81 cfs @ 12.33 hrs, Volume= 1.812 af, Atten= 1%, Lag= 1.8 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 7.2 fps, Min. Travel Time= 1.0 min  
Avg. Velocity = 3.1 fps, Avg. Travel Time= 2.4 min

Peak Depth= 0.96'  
Capacity at bank full= 59.33 cfs  
2.00' x 2.00' deep channel, n= 0.035 Length= 450.0' Slope= 0.0600 '/  
Side Slope Z-value= 0.5 '/

$R_2 = 4.65 \text{ cfs}$   
 $R_{10} = 12.72 \text{ cfs}$

### Reach 2181R: Reach Parking Lot to CB

Inflow = 16.81 cfs @ 12.33 hrs, Volume= 1.812 af  
Outflow = 16.71 cfs @ 12.34 hrs, Volume= 1.810 af, Atten= 1%, Lag= 0.6 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 10.1 fps, Min. Travel Time= 0.4 min  
Avg. Velocity = 3.8 fps, Avg. Travel Time= 1.1 min

Peak Depth= 0.33'  
Capacity at bank full= 94.31 cfs  
5.00' x 1.00' deep channel, n= 0.013 Length= 250.0' Slope= 0.0400 '/  
Side Slope Z-value= 0.1 '/

$R_2 = 4.54 \text{ cfs}$   
 $R_{10} = 12.35 \text{ cfs}$

### Reach 2182R: Reach CB to Presump St. Culvert

Inflow = 16.71 cfs @ 12.34 hrs, Volume= 1.810 af  
Outflow = 16.37 cfs @ 12.38 hrs, Volume= 1.808 af, Atten= 2%, Lag= 2.4 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 11.5 fps, Min. Travel Time= 1.0 min  
Avg. Velocity = 5.7 fps, Avg. Travel Time= 2.0 min

Peak Depth= 1.13'  
Capacity at bank full= 17.99 cfs  
18.0" Diameter Pipe n= 0.012 Length= 700.0' Slope= 0.0250 '/

$R_2 = 4.51 \text{ cfs}$   
 $R_{10} = 12.34 \text{ cfs}$

### Reach 2183R: Culvert Accross Presumpscot Street

Inflow = 132.62 cfs @ 12.25 hrs, Volume= 14.364 af  
Outflow = 132.48 cfs @ 12.26 hrs, Volume= 14.363 af, Atten= 0%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
Max. Velocity= 19.7 fps, Min. Travel Time= 0.1 min  
Avg. Velocity = 8.9 fps, Avg. Travel Time= 0.2 min

Peak Depth= 2.30'  
Capacity at bank full= 172.33 cfs  
42.0" Diameter Pipe n= 0.012 Length= 100.0' Slope= 0.0250 '/

$R_2 = 42.50 \text{ cfs}$   
 $R_{10} = 102.10 \text{ cfs}$

**Reach 2184R: Stream Reach Pres. St. to AP-2**

Inflow = 132.48 cfs @ 12.26 hrs, Volume= 14.363 af  
 Outflow = 131.89 cfs @ 12.28 hrs, Volume= 14.353 af, Atten= 0%, Lag= 1.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs  
 Max. Velocity= 9.6 fps, Min. Travel Time= 0.5 min  
 Avg. Velocity = 4.0 fps, Avg. Travel Time= 1.1 min

$R_2 = 42.46 \text{ cfs}$   
 $R_{10} = 101.99 \text{ cfs}$

Peak Depth= 2.21'  
 Capacity at bank full= 415.56 cfs  
 4.00' x 4.00' deep channel, n= 0.035 Length= 265.0' Slope= 0.0350 '  
 Side Slope Z-value= 1.0 '

**Reach AP-2: (new node)**

Inflow = 139.35 cfs @ 12.27 hrs, Volume= 15.588 af  
 Outflow = 139.35 cfs @ 12.27 hrs, Volume= 15.588 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

$R_2 = 45.43 \text{ cfs}$   
 $R_{10} = 107.57 \text{ cfs}$

**Pond 201P: Inlet to CB-201**

Inflow = 1.39 cfs @ 11.99 hrs, Volume= 0.102 af  
 Outflow = 1.38 cfs @ 11.99 hrs, Volume= 0.102 af, Atten= 0%, Lag= 0.0 min  
 Primary = 1.38 cfs @ 11.99 hrs, Volume= 0.102 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

$R_2 = 0.72 \text{ cfs}$   
 $R_{10} = 1.17 \text{ cfs}$

Peak Elev= 0.06' Storage= 5 cf  
 Plug-Flow detention time= (not calculated)  
 Storage and wetted areas determined by Prismatic sections

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow** (Free Discharge)  
 ↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

14/21

**Pond 202P: Inlet for CB-202**

Inflow = 1.60 cfs @ 11.99 hrs, Volume= 0.113 af  
 Outflow = 1.60 cfs @ 11.99 hrs, Volume= 0.113 af, Atten= 0%, Lag= 0.0 min  
 Primary = 1.60 cfs @ 11.99 hrs, Volume= 0.113 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

*R<sub>2</sub> = 0.78 cfs*

Peak Elev= 0.07' Storage= 5 cf

Plug-Flow detention time= (not calculated)

Storage and wetted areas determined by Prismatic sections

*R<sub>10</sub> = 1.34 cfs*

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

**Pond 203P: Inlet for CB-203**

Inflow = 1.29 cfs @ 12.00 hrs, Volume= 0.144 af  
 Outflow = 1.29 cfs @ 12.00 hrs, Volume= 0.144 af, Atten= 0%, Lag= 0.0 min  
 Primary = 1.29 cfs @ 12.00 hrs, Volume= 0.144 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

*R<sub>2</sub> = 0.62 cfs*

Peak Elev= 0.06' Storage= 5 cf

Plug-Flow detention time= 0.1 min calculated for 0.143 af (99% of inflow)

Storage and wetted areas determined by Prismatic sections

*R<sub>10</sub> = 1.06 cfs*

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

*15/21*

**Pond 204P: Inlet to CB-204**

Inflow = 0.76 cfs @ 11.99 hrs, Volume= 0.059 af  
 Outflow = 0.76 cfs @ 11.99 hrs, Volume= 0.059 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.76 cfs @ 11.99 hrs, Volume= 0.059 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

Peak Elev= 0.04' Storage= 3 cf  
 Plug-Flow detention time= (not calculated)  
 Storage and wetted areas determined by Prismatic sections

$R_2 = 0.41 \text{ cfs}$   
 $R_{10} = 0.65 \text{ cfs}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow** (Free Discharge)  
 ↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

**Pond 205P: Inlet for CB-205**

Inflow = 0.65 cfs @ 11.99 hrs, Volume= 0.048 af  
 Outflow = 0.64 cfs @ 11.99 hrs, Volume= 0.048 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.64 cfs @ 11.99 hrs; Volume= 0.048 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

Peak Elev= 0.04' Storage= 3 cf  
 Plug-Flow detention time= (not calculated)  
 Storage and wetted areas determined by Prismatic sections

$R_2 = 0.34 \text{ cfs}$   
 $R_{10} = 0.55 \text{ cfs}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow** (Free Discharge)  
 ↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

16/21

**Pond 206P: Inlet for CB-206**

Inflow = 0.59 cfs @ 11.98 hrs, Volume= 0.044 af  
 Outflow = 0.59 cfs @ 11.98 hrs, Volume= 0.044 af, Atten= 0%, Lag= 0.1 min  
 Primary = 0.59 cfs @ 11.98 hrs, Volume= 0.044 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

Peak Elev= 0.04' Storage= 3 cf  
 Plug-Flow detention time= 0.1 min calculated for 0.044 af (100% of inflow)  
 Storage and wetted areas determined by Prismatic sections

$R_2 = 0.29 \text{ cf}$   
 $R_{10} = 0.49 \text{ cf}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow** (Free Discharge)  
 ↑1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

**Pond 207P: Inlet for CB-207**

Inflow = 0.52 cfs @ 11.98 hrs, Volume= 0.040 af  
 Outflow = 0.52 cfs @ 11.98 hrs, Volume= 0.040 af, Atten= 0%, Lag= 0.1 min  
 Primary = 0.52 cfs @ 11.98 hrs, Volume= 0.040 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

Peak Elev= 0.03' Storage= 2 cf  
 Plug-Flow detention time= 0.1 min calculated for 0.040 af (99% of inflow)  
 Storage and wetted areas determined by Prismatic sections

$R_2 = 0.27 \text{ cf}$   
 $R_{10} = 0.44 \text{ cf}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow** (Free Discharge)  
 ↑1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

17/21

**Pond 208P: Inlet for CB-208**

Inflow = 0.49 cfs @ 11.98 hrs, Volume= 0.037 af  
 Outflow = 0.49 cfs @ 11.98 hrs, Volume= 0.037 af, Atten= 0%, Lag= 0.1 min  
 Primary = 0.49 cfs @ 11.98 hrs, Volume= 0.037 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

$R_2 = 0.25 \text{ cfs}$

Peak Elev= 0.03' Storage= 2 cf  
 Plug-Flow detention time= 0.1 min calculated for 0.037 af (99% of inflow)  
 Storage and wetted areas determined by Prismatic sections

$R_{10} = 0.42 \text{ cfs}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

**Pond 209P: Inlet of CB-209**

Inflow = 0.56 cfs @ 11.98 hrs, Volume= 0.042 af  
 Outflow = 0.56 cfs @ 11.98 hrs, Volume= 0.042 af, Atten= 0%, Lag= 0.1 min  
 Primary = 0.56 cfs @ 11.98 hrs, Volume= 0.042 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

$R_2 = 0.29 \text{ cfs}$

Peak Elev= 0.03' Storage= 3 cf  
 Plug-Flow detention time= 0.1 min calculated for 0.042 af (100% of inflow)  
 Storage and wetted areas determined by Prismatic sections

$R_{10} = 0.47 \text{ cfs}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

18/21

**Pond 210P: Inlet of CB-210**

Inflow = 0.46 cfs @ 11.98 hrs, Volume= 0.035 af  
 Outflow = 0.46 cfs @ 11.98 hrs, Volume= 0.035 af, Atten= 0%, Lag= 0.1 min  
 Primary = 0.46 cfs @ 11.98 hrs, Volume= 0.035 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

Peak Elev= 0.03' Storage= 2 cf  
 Plug-Flow detention time= 0.1 min calculated for 0.035 af (99% of inflow)  
 Storage and wetted areas determined by Prismatic sections

$R_2 = 0.24 \text{ cf}$

$R_{10} = 0.39 \text{ cf}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

**Pond 211P: Inlet of CB-211**

Inflow = 0.57 cfs @ 11.98 hrs, Volume= 0.041 af  
 Outflow = 0.57 cfs @ 11.98 hrs, Volume= 0.041 af, Atten= 0%, Lag= 0.1 min  
 Primary = 0.57 cfs @ 11.98 hrs, Volume= 0.041 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

Peak Elev= 0.03' Storage= 3 cf  
 Plug-Flow detention time= 0.1 min calculated for 0.041 af (99% of inflow)  
 Storage and wetted areas determined by Prismatic sections

$R_2 = 0.27 \text{ cf}$

$R_{10} = 0.48 \text{ cf}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600



**Pond 212P: Inlet of CB-212**

Inflow = 0.45 cfs @ 11.97 hrs, Volume= 0.035 af  
 Outflow = 0.45 cfs @ 11.98 hrs, Volume= 0.035 af, Atten= 0%, Lag= 0.1 min  
 Primary = 0.45 cfs @ 11.98 hrs, Volume= 0.035 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

Peak Elev= 0.03' Storage= 2 cf  
 Plug-Flow detention time= 0.1 min calculated for 0.035 af (99% of inflow)  
 Storage and wetted areas determined by Prismatic sections

$R_2 = 0.24 \text{ cfs}$   
 $R_{10} = 0.38 \text{ cfs}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

**Pond 213P: Inlet of CB-213**

Inflow = 0.68 cfs @ 11.98 hrs, Volume= 0.050 af  
 Outflow = 0.68 cfs @ 11.98 hrs, Volume= 0.050 af, Atten= 0%, Lag= 0.1 min  
 Primary = 0.68 cfs @ 11.98 hrs, Volume= 0.050 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

Peak Elev= 0.04' Storage= 3 cf  
 Plug-Flow detention time= 0.1 min calculated for 0.049 af (99% of inflow)  
 Storage and wetted areas determined by Prismatic sections

$R_2 = 0.33 \text{ cfs}$   
 $R_{10} = 0.57 \text{ cfs}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↑ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

20/21

**Pond 214P: Inlet of CB-214**

Inflow = 2.10 cfs @ 12.00 hrs, Volume= 0.144 af  
 Outflow = 2.09 cfs @ 12.00 hrs, Volume= 0.144 af, Atten= 0%, Lag= 0.0 min  
 Primary = 2.09 cfs @ 12.00 hrs, Volume= 0.144 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

$R_2 = 0.95 \text{ cfs}$

Peak Elev= 0.08' Storage= 6 cf  
 Plug-Flow detention time= (not calculated)  
 Storage and wetted areas determined by Prismatic sections

$R_{10} = 1.73 \text{ cfs}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↳ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

**Pond 215P: Inlet of CB-215**

Inflow = 0.73 cfs @ 11.98 hrs, Volume= 0.059 af  
 Outflow = 0.73 cfs @ 11.98 hrs, Volume= 0.059 af, Atten= 0%, Lag= 0.1 min  
 Primary = 0.73 cfs @ 11.98 hrs, Volume= 0.059 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.10 hrs

$R_2 = 0.40 \text{ cfs}$

Peak Elev= 0.04' Storage= 3 cf  
 Plug-Flow detention time= 0.1 min calculated for 0.059 af (100% of inflow)  
 Storage and wetted areas determined by Prismatic sections

$R_{10} = 0.62 \text{ cfs}$

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	4	0	0
0.30	150	23	23
0.60	300	68	91

**Primary OutFlow (Free Discharge)**

↳ 1=Orifice/Grate

#	Routing	Invert	Outlet Devices
1	Primary	0.00'	0.50' x 0.15' Horiz. Orifice/Grate X 21.00 Limited to weir flow C= 0.600

2/21

**HYDROCAD WORKSHEET - PROPOSED CONDITIONS**

**TIME OF CONCENTRATION (T<sub>c</sub>) - DIRECT ENTRY**

**SUBCATCHMENT**                      SC-1

CHANNEL FLOW		SEGMENT ID			
		C - D			
1	SURFACE DESCRIPTION	GW			
2	FLOW LENGTH, L (ft)	80			
3	CHANNEL SLOPE, s (ft/ft)	0.075			
4	VELOCITY FROM NEH 4, V (ft/s)	4.0			
5	T <sub>t</sub> = L/60 V, (min)	0.3			

TOTAL T <sub>t</sub> , (min)	0.3
------------------------------	-----

**SUBCATCHMENT**                      SC-214

CHANNEL FLOW		SEGMENT ID			
		C-D			
1	SURFACE DESCRIPTION	PA			
2	FLOW LENGTH, L (ft)	170			
3	CHANNEL SLOPE, s (ft/ft)	0.02			
4	VELOCITY FROM NEH 4, V (ft/s)	2.7			
5	T <sub>t</sub> = L/60 V, (min)	1.0			

TOTAL T <sub>t</sub> , (min)	1.0
------------------------------	-----

**SUBCATCHMENT**                      SC-216

CHANNEL FLOW		SEGMENT ID			
		B-C	C-D		
1	SURFACE DESCRIPTION	GW	STWC		
2	FLOW LENGTH, L (ft)	220	75		
3	CHANNEL SLOPE, s (ft/ft)	0.005	0.24		
4	VELOCITY FROM NEH 4, V (ft/s)	1	9		
5	T <sub>t</sub> = L/60 V, (min)	3.7	0.1		

TOTAL T <sub>t</sub> , (min)	3.8
------------------------------	-----

**SUBCATCHMENT****SC-217****CHANNEL FLOW**

		SEGMENT ID			
		C - D			
1	SURFACE DESCRIPTION	STWC			
2	FLOW LENGTH, L (ft)	750			
3	CHANNEL SLOPE, s (ft/ft)	0.025			
4	VELOCITY FROM NEH 4, V (ft/s)	3.4			
5	$T_t = L/60 V$ , (min)	3.7			

TOTAL $T_t$ , (min)	3.7
---------------------	-----

**SUBCATCHMENT****SC-218****CHANNEL FLOW**

		SEGMENT ID			
		C-D			
1	SURFACE DESCRIPTION	STWC			
2	FLOW LENGTH, L (ft)	750			
3	CHANNEL SLOPE, s (ft/ft)	0.025			
4	VELOCITY FROM NEH 4, V (ft/s)	3.4			
5	$T_t = L/60 V$ , (min)	3.7			

TOTAL $T_t$ , (min)	3.7
---------------------	-----

**SUBCATCHMENT****SC-219****CHANNEL FLOW**

		SEGMENT ID			
		D - E			
1	SURFACE DESCRIPTION	STWC			
2	FLOW LENGTH, L (ft)	450			
3	CHANNEL SLOPE, s (ft/ft)	0.02			
4	VELOCITY FROM NEH 4, V (ft/s)	3.2			
5	$T_t = L/60 V$ , (min)	2.3			

TOTAL $T_t$ , (min)	2.3
---------------------	-----

APPENDIX C  
WATER QUALITY WORKSHEETS

# Worksheets for Evaluating Stormwater BMPs

## Worksheet 1. Identifying Subwatersheds

**Step 1. Identify and characterize significant subwatersheds within the development site.** Since no receiving water should receive stormwater that has not received the prescribed net level of treatment (% TSS Removal), areas which drain to different rivers, streams or brooks; lakes or ponds; or coastal waters should be delineated and evaluated discreetly. This means that if the entire developed site drained directly to a single stream it could all be treated as one watershed, but if half of it drained to stream "x" and the other half to stream "y", two separate watersheds must be delineated and two separate analyses performed. Delineate each subwatershed in the development site and complete the following table. Indicate whether the development is a residential subdivision or nonsubdivision.

Sub-wshd ID	Receiving Waterbody	Type of Development subd, nonsub	Total Area (Acres)	Wetland Area (Acres)	Develop-able Area total-well
A	UNNAMED STREAM	New Sub	4.1	(Browns) .05 A-	4.05

For subwatersheds which drain directly or indirectly to sensitive lakes or ponds see Phosphorus Control In Lake Watersheds: a Technical Guide for Evaluating New Development (DEP, 1992).

For subwatersheds which do not drain directly or indirectly to sensitive lakes or ponds go to Worksheet 2

## Worksheets for Evaluating Stormwater BMPs

### Worksheet 2. Determining the Required Level of Treatment

Note: This worksheet is meant to be used on subwatersheds which *do not* drain directly or indirectly to sensitive lakes or ponds.

**Step 2. Determine the required level of stormwater treatment for each sub watershed.**

**a. Residential subdivisions:**

- (1). For subdivisions with an existing impervious surface road or with new or upgraded roads with less than 4,000 sq. ft. of additional impervious surface the required level of stormwater treatment is **15% TSS removal**.
- (2). For subdivisions with new or upgraded roads greater than 4,000 sq. ft. new impervious surface the required level of stormwater treatment is **40% TSS removal**.

**b. Non subdivision development: Complete the following table by:**

- (1). Calculating the % imperviousness for each subwatershed by dividing the area within the subwatershed which will be **impervious** (definition in Sect 5.2.2) after development by the total developable area within the subwatershed and multiplying by 100.

$$\% \text{ Impervious} = (\text{Impervious Area} / \text{Developable Area}) \times (100)$$

- (2). Using the curve in figure ? to determine the required % TSS removal.

Sub-wtshd ID	Type of Development subd, nonsub	Imperv. Area (Acres)	Develop. Area (Acres)	% Imper-vious	% TSS Removal (fig. ?) <i>51</i>
<i>A</i>	<i>Non Sub</i>	<i>1.57</i>	<i>4.05</i>	<i>38.7</i>	<i>50%</i>

**Next Step:** Complete Worksheet 3a + 3b (residential subdivision) or 3c (non-subdivision) for each subwatershed.

## Worksheets for Evaluating Stormwater BMPs

### Worksheet 3c. Determining Net % TSS Removal for Non-Subdivisions

Step 3a. Determine the Net Weighted % TSS Removal in each Subwatershed. Complete the following table for each subwatershed by:

- dividing the impervious area within the subwatershed into subareas to which the same BMPs are being applied
  - calculating the % of Total Impervious Area for each subarea by dividing the subarea's impervious area by the total impervious area in the subwatershed (from Worksheet 2) and multiplying by 100
  - multiplying the % of Total Impervious Area by the Net BMP % TSS Removal Efficiency (see note) for the BMP(s) being applied to the subarea
  - adding the products to get the Net weighted % TSS Removal for the subwatershed.
- Compare this to the prescribed % TSS removal for the subwatershed in Worksheet 2.

If only one BMP is applied to a subarea the Net BMP % TSS Removal Efficiency is equal to the % TSS removal efficiency for the BMP. If more than one BMP are applied in series, the Net BMP % TSS Removal Efficiency for the suite of BMPs is calculated as follows:

$$\text{Net BMP \% Removal Eff.} = 100[1 - \{(1-r_1) \times (1-r_2) \times \dots \times (1-r_n)\}]$$

where  $r_n$  is the removal efficiency of each BMP expressed as a fraction.

Subwatershed \_\_\_\_\_.

Subarea ID	% Total Imperv. Area	X	Net BMP % TSS Removal	X 0.01 =	BMP Notes
A	100%	X	50	= 50	
		X		X 0.01 =	
		X		X 0.01 =	
		X		X 0.01 =	
		X		X 0.01 =	
		X		X 0.01 =	
		X		X 0.01 =	
		X		X 0.01 =	
		X		X 0.01 =	
		X		X 0.01 =	
<b>Totals</b>	<b>100%</b>		<b>Net Weighted % TSS Removal for Subwatershed</b>	<b>=</b>	



### Stormwater Quality Standard




Figure 5.1.

38.7%


For the purposes of this manual, **impervious surface** is fully defined as a hard surface area which either prevents or retards the entry of water into the soil mantle as under natural conditions prior to development, and/or a hard surface area which causes water to run off the surface in greater quantities or at an increased rate of flow from the flow present under natural conditions prior to development. Common impervious areas include, but are not limited to, rooftops, walkways, patios, driveways, parking lots or storage areas, concrete or asphalt paving, gravel roads, packed earthen materials, and oiled, macadam, or other surfaces which similarly impede the natural infiltration of stormwater.

This BMP manual is not regulatory. However, the practices described in this manual are designed to ensure that stormwater runoff from a development site not adversely affect the physical, biological, and chemical properties of the receiving water or of associated aquatic habitats. As such, use of this manual may assist compliance with applicable statutes, regulations, and ordinances. Other equivalent techniques of stormwater treatment, of course, will also assist with compliance.

**Alternatively**, the criterion of reducing post development TSS loadings to predevelopment levels may be applied. This criterion is not intended to be used as an alternative to achieving adequate control where existing high sediment loadings are the result of poor management of "developed" sites such as farmlands where appropriate erosion control components of a USDA conservation management plan are not being used, or sites where land disturbed by previous development (e.g., gravel pits or log yards) was not permanently stabilized (EPA, 1993.)

APPENDIX D  
RIPRAP APRONS

Figure 32.1 MINIMUM TAILWATER CONDITION (USDA Soil Conservation Service)



APPENDIX E  
PROJECT DRAWINGS

<u>Dwg. #</u>	<u>Title</u>
D-100	Stormwater Management Plan Pre-Development
D-101	Stormwater Management Plan Post-Development

Stormwater runoff from subcatchment SC-1 is conveyed to a 42-inch diameter culvert, the inlet of which is Analysis Point 1. Flows from SC-1 eventually flow westward below the St. Lawrence and Atlantic Railroad Tracks and below Interstate 95 prior to discharge to Casco Bay. Subcatchment SC-1 is approximately 1.7 acres in pre-development and approximately 1.1 acres in post-development. Subcatchment SC-1 consists of open space, woods, gravel railroad right of way, and impervious roof and pavement in both pre and post development. Subcatchment SC-1 loses approximately 0.6 acres to SC-2 in post-development due to the construction of the intermodel facility parking lot.

Storm water runoff from SC-2 is conveyed to a 30-inch by 30-inch stone arch located in the southeast corner of the site, the inlet of which is Analysis Point 2. In pre-development subcatchment SC-2 consists of a 62.6 acre upgradient watershed to the west (Subcatchments SC-217, 218, and 219) and a 3.2 acre site watershed between Presumpscot Street and the St. Lawrence and Atlantic Railroad (SC-2). Both the intermodel facility watershed and the upgradient watershed convey runoff to an unnamed stream along the south side of the property. In pre-development the upgradient watershed consists mainly of woods, open space and urban industrial areas. In pre-development the intermodel facility watershed consists of open space with some woods, gravel railroad right of way, and impervious roof and pavement. In post-development conditions the upgradient watershed will be unchanged in area and land use from its pre-development conditions. In its post-development conditions the intermodel facility watershed will have approximately 3.8 acres and will consist of impervious pavement with some open area, woods, and gravel railroad right of way.

To determine the peak surface water runoff rates for each watershed, a weighted curve number ( $C_N$ ) and time of concentration ( $T_c$ ) were calculated for each subcatchment in pre- and post-development conditions based on area, hydrologic soil group, cover type, and drainage patterns. These calculations are in Appendix A and B respectively. Pre- and post-development conditions for the SC-1 and SC-2 watershed are summarized in Table 1. The catchment boundaries and  $T_c$  routing for pre-development and post-development conditions for the upgradient watershed are shown in Figure 2. The catchment boundaries and  $T_c$  routing for pre-development site conditions



*Sevee & Maher Engineers, Inc.*  
Waste Management and Hydrogeologic Consultants

August 14, 2001

00013.07  
010813la.doc

City of Portland  
Attn: Mr. Larry Ash  
Traffic Engineering Division  
65 Hanover Street  
Portland, ME 04101

Portland, Maine

Subject: October Corp.  
Intermodal Transfer Facility  
Traffic Study

Dear Mr. Ash:

In response to our telephone conversation of June 28, 2001 concerning October Corporation's proposed intermodal transfer facility on Presumpscot Street, we offer the following information for your review:

I. Sight distance at the project entrances:

Sevee & Maher Engineers, Inc. (SME) has measured the available sight distance at each proposed entrance. Sight distance was measured at a point 10 feet from the edge of travelway to the centerline of the opposing lane(s), assuming a height of eye of 3.5 feet and a height of object of 4.25 feet. The available sight distance from each entrance is as follows:

	Available Site Distance	
	<u>Left</u>	<u>Right</u>
North Entrance/Exit	>750'	>950'
South Entrance/Exit	530'	>1200'

The measured sight distance exceeds the City's sight distance standard of 513 feet for a posted speed limit of 35 mph, as specified in Section III, paragraph 4, Traffic Design Standards and Guidelines of the "City of Portland, Maine Technical and Design Standards and Guidelines," March 2000.

2. Impact on Intersection Capacity of Washington Avenue and Presumpscot Street:

SME conducted turning movement counts at Washington Avenue and Presumpscot Street from 6:00 AM to 9:00 AM, and from 3:00 PM to 6:00 PM on Tuesday, July 10, 2001. Because of late afternoon thunderstorms which caused numerous accidents and traffic delays, the afternoon count was repeated from 4:00 PM to 6:00 PM on Wednesday, July 18, 2001. Traffic generation from the project site was based on rates outlined in the 6<sup>th</sup> Edition of "ITE Trip Generation", Land Use 090; Park and Ride Lot with Bus Shuttle. It is expected that this facility (171 parking spaces) will generate 113 PM peak hour trips, and 109 AM peak hour trips. Based on the traffic distributions at Washington Avenue and studies conducted for the Pineland Center in New Gloucester, it was assumed that 15 new trips would be generated from/to Washington Avenue, 17 new trips would result on Presumpscot Street from Falmouth, with the remainder of the trips diverted from existing traffic on Washington Avenue.

Peak hour volumes were increased by 2 percent to account for traffic growth from 2001 to 2002. The morning and afternoon peak hour performance for 2002 was calculated for both the "Build" and "No-build" 2002 conditions. It was found that no significant degradation in the intersection's level of service will result from this project. The intersection will continue to operate at a Level of Service (LOS) B (AM) and C (PM). Performance charts, assumptions, and analyses are attached.

The traffic analysis was prepared through the combined efforts of Sevee & Maher Engineers, Inc. and HNTB of Westbrook, Maine. SME conducted turning movement counts, compiled intersection configuration data and performed the traffic generation and distribution analysis. HNTB reviewed the information compiled by SME and provided the peak hour performance analysis.

3. Presumpscot Street Truck Traffic:

Based on the turning movement counts, existing truck traffic on Presumpscot Street is as follows:


	<u>No. Trucks</u>	<u>% of Total Traffic</u>
AM (6-9)	101	9.4
PM (4-6)	43	6.1

Enclosed is a copy of site plans for Phase I of the project.

If you have any questions or require additional information, please contact me.

Sincerely,

SEVEE & MAHER ENGINEERS, INC.

A handwritten signature in black ink, appearing to read "John R. Kennedy". The signature is stylized with a large, looping flourish at the end.

John R. Kennedy, P.E.

Enclosures



**TRAFFIC STUDY  
FOR  
INTERMODAL TRANSFER  
FACILITY  
PRESUMPCOT STREET  
PORTLAND, MAINE**

**BY  
OCTOBER CORPORATION  
PORTLAND, MAINE**


**AUGUST 2001**

*SME*

*Sevee & Maher Engineers, Inc.*  
*Waste Management and Hydrogeologic Consultants*  
*Cumberland Center, Maine*

## Washington Ave. @ Presumpscot St.

### AM Peak Hour Performance, 2002 -- No-Build vs. Build

Configuration	Movement	2002 - No-Build			2002 - Build		
		Volume	Delay	LOS	Volume	Delay	LOS
	NB - L	3			3		
	NB - T	162	9.1	A	162	8.5	A
	NB - R	128			143		
	SB - L	9			64		
	SB - T	1,054	22.8	C	999	23.3	C
	SB - R	44			44		
	EB - L	15			15		
	EB - T	7	39.6	D	8	41.7	D
	EB - R	8			7		
	WB - L	328			331		
	WB - T	16	45.3	D	16	49.7	D
	WB - R	37			51		
Intersection		1,811	25.6	C	1,843	26.8	C
NOTES: - Washington Ave. is considered the north-south route, with I-295 laying to the south. - All volumes are unadjusted, but MDOIT group mean factors indicate that 3rd week in July represents close to 30th high hour.							

## Washington Ave. @ Presumpscot St.

### PM Peak Hour Performance, 2002 -- No-Build vs. Build

Configuration	Movement	2002 - No-Build			2002 - Build		
		Volume	Delay	LOS	Volume	Delay	LOS
	NB - L	6			6		
	NB - T	921	14.1	B	865	15.8	B
	NB - R	179			183		
	SB - L	5			21		
	SB - T	855	12.5	B	855	15.9	B
	SB - R	20			20		
	EB - L	6			6		
	EB - T	5	26.6	C	5	27.7	C
	EB - R	18			18		
	WB - L	165			180		
	WB - T	5	28.0	C	6	30.9	C
WB - R	25			81			
Intersection		2,210	14.9	B	2,246	17.8	B

**NOTES:**

- Washington Ave. is considered the north-south route, with I-295 laying to the south.
- All volumes are unadjusted, but MDOT group mean factors indicate that 3rd week in July represents close to 30th high hour.

PROJECT  
 OCTOBER CORP  
 PRESUMPT CUT STREET

COMP. BY  
 JPK  
 CHK. BY



JOB NO.  
 00013.07  
 DATE  
 7/01

Trip Generation:

REFERENCE: ITE Trip Generation, 6th Edition  
 LAND USE (090): PARK AND RIDE  
 LOT w/ BUS SERVICE

# TRIPS P.M. PEAK HOUR  
 $T = 0.602(x) + 9.5$   
 $= 0.6(171) + 9.5 = 113 \text{ TRIPS}$   
 22% ENTER, 78% EXIT

# TRIP A.M. PEAK HOUR  
 $T = 0.84(171) - 34.7 = 109 \text{ TRIPS}$   
 80% ENTER  
 20% EXIT



PROJECT OCTOBER CORP PRESUMPSOFT ST	COMP. BY JK	JOB NO. D0013.07
	CHK. BY	DATE July 01

## TRIP DISTRIBUTION:

### ASSUMPTION:

USE TRAFFIC DISTRIBUTION AT WASHINGTON AVE/PRESUMPSOFT STREET AS BASIS FOR ASSIGN TRIPS

ALL TRIPS ARE EXIST EXCEPT  
 (1) OUTBOUND WASHINGTON AVE AM  
 (2) INBOUND WASHINGTON AVE PM

WHICH ARE CONSIDERED NEW TRIPS ON WASHINGTON AVE/PRESUMPSOFT ST WITH DEST/ONLY BEING PINELAND CENTER, New Gloucester (EXIST TRAFFIC STUDY ESTIMATES THIS TO BE 15 TRIPS)

(2) PRESUMPSOFT ST EAST of PARKING CONSIDER AS NEW TRIPS DIVERTED FROM I 295

(3) REMAINDER of TRIPS EXIST ON WASHINGTON AVE AND ARE DIVERTED TO PARKING FACILITY VIA PRESUMPSOFT STREET

PROJECT  
 OCTOBER Comp  
 PRESUMPSCOT ST PKG

COMP. BY  
 JALC  
 CHK. BY

JOB NO.  
 100013.07  
 DATE  
 July 01

USE AM INBOUND VOLUME TO ESTABLISH  
 DIVERTED TRIP to PKG


PKG AM 88 entering TRIPS

ASSUMES 15 NEW TRIPS FROM  
 PORTLAND, SO. PKG, C.E. w/ dest  
 New Gloucester

Remaining 73 Remaining trips

INBOUND PRESUMPSCOT ST 23% (Assume New)  
 WASHINGTON 76% (DIVERTED)  
 PRESUMP (E) 1% (DIVERTED)

TRIPS to LT



PROJECT

OCTOBER Corporation

COMP. BY

JRK


CHK. BY

JOB NO.


00073.07

DATE

7/01



\* Growth @ 2% / yr



## Park-and-Ride Lot with Bus Service (090)


Average Vehicle Trip Ends vs: Parking Spaces  
On a: Weekday,  
Peak Hour of Adjacent Street Traffic,  
One Hour Between 7 and 9 a.m.

Number of Studies: 9  
Average Number of Parking Spaces: 394  
Directional Distribution: 80% entering, 20% exiting

### Trip Generation per Parking Space

Average Rate	Range of Rates	Standard Deviation
0.75	0.29 - 0.87	0.87

### Data Plot and Equation





# Park-and-Ride Lot with Bus Service (090)


Average Vehicle Trip Ends vs: Parking Spaces  
On a: Weekday,  
Peak Hour of Adjacent Street Traffic,  
One Hour Between 4 and 6 p.m.

Number of Studies: 9  
Average Number of Parking Spaces: 394  
Directional Distribution: 22% entering, 78% exiting

## Trip Generation per Parking Space

Average Rate	Range of Rates	Standard Deviation
0.63	0.23 - 0.93	0.81

## Data Plot and Equation




PROJECT  
OCTUBER Corp  
PREEMPSLOT ST

COMP. BY  
JRM  
CHK. BY

JOB NO.  
00013.07  
DATE  
7/07



AM BUILD 2002



PROJECT  
 OCTOBER CORP  
 P. ESUMPSUT ST

COMP. BY  
 JRLC  
 CHK. BY

JOB NO.  
 00013.07  
 DATE  
 7/01




7727410

PROJECT  
PineLand Presumpscot ST  
TRAFFIC STUDY @ Washington Ave

COMP. BY  
*[Signature]*  
CHK. BY

JOB NO.  
0013.07  
DATE  
7/10/01




SIGN  
No RTOR  
8AM - 9AM  
11:30AM - 12:30PM  
3PM - 3:30PM  
08-6/86 School Days only



PROJECT  
 PINA AND PRESUMPT ST  
 TRAFFIC STUDY @ WASHINGTON AVE

COMP. BY  
 CHK. BY

JOB NO.  
 DATE



PED ACT CROSSING = 21 SEC



**SME**

*Sevee & Maher Engineers, Inc.*  
Waste Management and Hydrogeologic Consultants  
Cumberland Center, Maine

## TELEPHONE MEMORANDUM

Job No. 00013.07

DATE: June 28, 2001

BETWEEN: Larry Ash, city of Portland Traffic Engineer

AND: John Kennedy, SME

SUBJECT: PRESUMPSCOT STREET - TRAFFIC IMPACTS

---

Explained to Larry that October Corporation had submitted a site plan application for an intramodal transfer facility on Presumpscot Street. Use to be for car/bus transfer of October Corporation/Boulos Properties employees to work in downtown Portland. Also, use for rail transportation for commuters from Portland, South Portland, and Cape Elizabeth to work in Pineland, New Gloucester. At this time, majority of usage would be bussing of commuter traffic to downtown.

### Larry's Concerns.

1. Sight distance of project entrance (SME believes OK on this).
2. Ability of Presumpscot Street/Washington Avenue to handle additional traffic and/or change in turning movement. May be a simple matter of striping and modification of signal timing. Current Washington Avenue traffic is 20,000 vehicles per day. Recommends that a local traffic engineer review the intersection impact.
3. Also, elementary school is located on Presumpscot Street. However, there are crossing guides on Washington and Presumpscot Street.
4. Large number of trucks on Presumpscot Street.
5. Neighborhood is well organized.

Document2

Finance Department



Duane G. Kline  
Director

**CITY OF PORTLAND**

October 23, 2002

Jennifer Baldwin  
Maine Bank & Trust  
P.O. Box 17510  
Portland, ME 04112-8510

Re: October Corporation, Intermodal Transfer Facility @ 373 Presumpscot St.  
Escrow Account #6270 dated October 15, 2001

Dear Ms. Baldwin:

This is to inform you that I am authorizing the release and return of the above-named escrow account to October Corporation, in the amount of \$335,213.55 plus accrued interest.

If you have any questions or require further information, please call my assistant, Jennifer Babcock, at 874-8645.

Sincerely,

Kevin Markee  
Treasury Director

KRM,jlb

pc: Jay Reynolds, Development Review Coordinator

**CB**  **Richard Ellis**  
Boulos Property Management

One Canal Plaza  
Portland, ME 04101  
207.871.1290 Tel  
207.772.2647 Fax  
www.boulos.com

June 7, 2002

Ms. Sarah Hopkins  
Planning Department  
City of Portland  
389 Congress Street, 4<sup>th</sup> Floor  
Portland, ME 04101

RE: Intermodal Transfer Facility  
373 Presumpscot Street  
October Corporation

Dear Sarah:

Please consider this letter as a request for the release of the performance guarantee posted by October Corporation regarding the above referenced property. The escrow guarantee is in the amount of \$335,213.55, and was executed on 10/16/01. I have enclosed a copy for your reference.

Regarding the requirement for a 10% Defect Guarantee, if one is required, will it be possible to reduce the amount of the existing guarantee by 90% and leave the balance 10% in place for that purpose?

Please let me know if you need any further information in order to process this request.

Sincerely,



KIM A. FARRAR  
Development Coordinator

cc: Rick Donald



SITE PLAN/SUBDIVISION  
PERFORMANCE GUARANTEE  
ESCROW ACCOUNT  
#6270

October 15, 2001

Alex Jaegerman  
Director of Planning and Urban Development  
City of Portland  
389 Congress Street  
Portland, Maine 04101

Re: Application of October Corporation for Intermodal Transfer Facility at 373 Presumpscot Street, Portland, Maine.

Maine Bank & Trust hereby certifies to the City of Portland that Maine Bank & Trust will hold the sum of Three Hundred Thirty Five Thousand Two Hundred and Thirteen Dollars and Fifty-five cents (\$335,213.55) in an interest bearing account established with the Bank. This account shall be in the name of the City of Portland and shall represent the estimated cost of installing site improvements as depicted on the site plan approved on September 25, 2001 as required under Portland Code of Ordinances Chapter 14 §§499, 499.5, 525 and Chapter 25 §§46 through 65. It is intended to satisfy the Developer's obligation, under Portland Code of Ordinances Chapter 14 §§501, 502 and 525, to post a performance guarantee for the above referenced development.

Maine Bank & Trust will hold these funds as escrow agent for the benefit of the City subject to the following:

The City, through its Director of Planning and Urban Development and in his sole discretion, may draw against this Escrow Account by presentation of a draft in the event that:

1. the Developer has failed to satisfactorily complete by September 25, 2003 the work on the improvements contained within the site improvements approval dated September 25, 2001; or
2. the Developer has failed to deliver to the City a deed containing the metes and bounds description of any streets, easements or other improvements required to be deeded to the City; or
3. the Developer has failed to post the ten percent (10%) Defect Guarantee required by Portland Code of Ordinances Chapter 14 §§501 and 525; or
4. the Developer has failed to notify the City for inspections in conjunction with the installation of improvements noted in paragraph one.

It is a condition of this Escrow Agreement that it is deemed to be automatically extended without amendment for a period(s) of one year from the current expiration date hereof, or any future expiration date, unless within sixty (60) days prior to any expiration, Maine Bank & Trust notifies the City by certified mail (restricted delivery to Duane Kline, Director of Finance, City of Portland, 389 Congress Street, Portland, Maine 04101), that Maine Bank & Trust elects not to consider this Escrow Agreement renewed for any such additional period.

After all underground work has been completed and inspected to the satisfaction of the Department of Public Works and Planning, including but not limited to sanitary sewers, storm drains, catch basins, manholes, electrical conduits, and other required improvements constructed chiefly below grade, the City of Portland Director of Planning and Urban Development or its Director of Finance as provided in Chapter 14 §501 of the Portland Code of Ordinances, may authorize Maine Bank & Trust by written certification, to reduce the available amount of the escrowed money by a specified amount.

All costs associated with establishing, maintaining, and disbursing funds from the Escrow Account shall be borne by October Corporation.

This Escrow Account expires on:

1. September 25, 2003 or ninety days following Maine Bank & Trust's written notice of its expiration as detailed above; or
2. Maine Bank & Trust's receipt of written notification from the City of Portland that said work contained within the site improvements approval as required by the Portland Code of Ordinances Chapter 14 §§499, 499.5, 525 and Chapter 25 §46 through 65 has been completed in accordance with the City of Portland's specifications and Maine Bank & Trust's Escrow Agreement No. 6270 may be cancelled.

Very truly yours,

Date: 10/16/01

Maine Bank & Trust

By: [Signature]  
Its Duly Authorized Agent

Seen and Agreed to: October Corp.

By: [Signature]  
Owen W. Wells, President

Reviewed pursuant to Portland Code of Ordinances, Chapter 14 §§501, 525:

By: [Signature]  
Director of Planning and Urban Development

Date: \_\_\_\_\_

By: [Signature]  
Director of Finance

Date: 11-5-01

By: [Signature]  
Corporation Counsel

Date: \_\_\_\_\_

**From:** "Farrar, Kim" <KFarrar@Boulos.com>  
**To:** 'Jay Reynolds' <JAYJR@ci.portland.me.us>  
**Date:** Tue, Jul 23, 2002 4:10 PM  
**Subject:** RE: intermodal facility/383presumpscot

Jay, thank you for getting back to me. I have a call in to White Brothers, who were the general contractors on this project for us, to go over the situation, and will get back to you shortly. Kim

-----Original Message-----

From: Jay Reynolds [mailto:JAYJR@ci.portland.me.us]  
Sent: Tuesday, July 23, 2002 9:41 AM  
To: KFarrar@Boulos.com  
Cc: SH@ci.portland.me.us  
Subject: intermodal facility/383presumpscot

I've spoken with Gary stockton, from bay electric, on the light fixture issue.

He stated that what was installed, is what was spec'd for the project. However, this conflicts with the drawing/detail of the fixture on the approved lighting plan.

We didn't really come to any resolve. He felt it wasn't any wrongdoing of his.

So, back to Boulos. I'll have to request, in writing that the applicant either replace the fixtures, or modify/tilt the existing fixtures so that they will be in compliance.

Thank you for your help.

Hi Kim,

The site looks great. White Bros., and whomever the landscaper was did a great job!

The one item is the lighting fixtures. This might be hard to explain, easy to see.....

the fixtures need to be 'cutoff' fixtures (which they are) and installed so that the lens is parallel to the ground. They are sort of angled up a bit, allowing the light to glare out. This is a common issue in site development, although a small issue, is a concern. Hence, our lighting standards!

To ensure lighting requirements (glare and spillover), the fixtures need to be tilted down.

Thanks for your attention on this matter, and feel free to contact me if you have any questions or comments.

Once this is corrected, the defect guarantee can be submitted, and I can release the original letter of credit.

Thanks again.  
Jay

Jay Reynolds  
Development Review Coordinator  
Department of Planning and Urban Development  
City of Portland  
207-874-8632  
jayjr@ci.portland.me.us

**CC:** "Ureneck, Paul" <PUreneck@Bouios.com>

# White Bros. Inc.

95 Warren Avenue  
Westbrook, Maine 04092  
Telephone: (207) 854-9173  
FAX: (207) 854-3809  
wbil@earthlink.net

## FAX TRANSMITTAL

DATE: 7/30/02  
TO: CITY of Portland  
ATTN: Mr. Jay Reynolds  
FROM: Mike White  
PAGES (To include this cover sheet): 2

Jay, Please review the attached memo from Bennett Engineering to C.W.S., based on my review it confirms what we discussed the other day. I will assume this puts the issue to bed, if not please give Tom Dunross or myself a call.

*Mike White*

**IMPORTANT MESSAGE:** Any message on this fax cover sheet, and any accompanying materials, may contain confidential, secret or privileged information, the disclosure, copying, or further dissemination of which is strictly prohibited under applicable law. Therefore, if this fax cover sheet is not addressed to you or if this fax cover sheet is addressed to you, but the accompanying materials do not appear to be intended for you, please do not read, copy or disseminate either any message on the fax cover sheet or the accompanying materials. Instead, please call us collect at 207-854-9173, and we will make arrangements for return of these materials at our expense. If you are having difficulties in receiving this, please call us at 207-854-9173. Thank you.



---

**CONSULTING ENGINEERS**

Bennett Road, P.O. Box 297, Freeport, Maine 04032  
Tel - (207) 865-9475  
Fax - (207) 865-1800  
Email - office@bennettengineering.net

---

**Memorandum**

---

To: Curtis Walter Stewart Architects

Date: 07/29/02

CC:

From: Will Bennett

Project: Portland Intermodal Transfer Facility

---

The Site lighting fixture specified and installed for the project mentioned above is Kim Model AR fixture with curved arm. The photometric isocurves indicated on the Site Plan E100 are accurate and based on this fixture. The design complies with the local site lighting ordinances in Portland. The fixture shown on the Pole Base Detail showing the side elevation of the lighting fixture with a straight mounting arm does not represent the specified fixture. The detail is shown primarily for information on the pole base construction and wiring.

Department of Planning & Development  
Lee D. Urban, Director



**CITY OF PORTLAND**

Division Directors  
Mark B. Adelson  
Housing & Neighborhood Services

Alexander Q. Jaegerman, AICP  
Planning

John N. Lufkin  
Economic Development

October 10, 2002

Kim Farrar  
Development Coordinator  
CB Richard Ellis/Boulos Property Management  
One Canal Plaza  
Portland, ME 04101

RE: 383 Presumpscot Street Intermodal Facility

CBL: 420 A 001001

Dear: Ms. Farrar:

This letter is to confirm the revision to the approved plan of the project located at 383 Presumpscot Street. The approved revision includes use of the site as a snow storage facility. The revised plan has been reviewed and approved by the project review staff including representatives of the Planning, Public Works, Building Inspections, Fire and Parks Departments, with the following conditions:

If you have any questions regarding the revision please contact Sarah Hopkins at 874-8720.

Sincerely,

Alexander Jaegerman  
Planning Division Director

cc: Lee D. Urban, Planning and Development Department Director  
Sarah Hopkins, Development Review Program Manager  
✓ Jay Reynolds, Development Review Coordinator  
Marge Schmuckal, Zoning Administrator  
Jodine Adams, Inspections  
Larry Ash, Traffic Engineer  
Tony Lombardo, Project Engineer  
Eric Labelle, City Engineer  
Jeff Tarling, City Arborist  
Penny Littell, Associate Corporation Counsel  
Lt. Gaylen McDougall, Fire Prevention  
Don Hall, Appraiser, Assessor's Office  
Approval Letter File  
Correspondence File

O:\PLANDEV\REV\WPRESUMP383\REVISIONLETTER.DOC

# MAINE BANK & TRUST

P.O. Box 17510, 467 Congress St.  
Portland, Maine 04112  
207-828-3000

For the Account of: OCTOBER CORP/CITY OF PORTLAND ESCROW CUSTODY

Account Number: 60 00 6267 31 \$

Date: SEPTEMBER 30, 2002

CITY OF PORTLAND  
ATTN: ALEX JAEGERMAN  
389 CONGRESS STREET  
PORTLAND ME 04101

16270



**MAINE BANK & TRUST**  
P.O. Box 17510, 467 Congress St.  
Portland, Maine 04112  
207-828-3000

For the Account of: **OCTOBER CORP/CITY OF PORTLAND ESCROW CUSTODY**

Account Number: **60 00 6267 31 8**

Date: **SEPTEMBER 30, 2002**

---

## *Statement Of Account*

### **Contents**

*Summary of Assets / 1*

*Review of Assets / 2*

*Receipts & Disbursements / 3*

*Summary Statement of Transactions / 4*

**MAINE BANK & TRUST**  
 F.O. Box 17510, 467 Congress St.  
 Portland, Maine 04112  
 207-828-3000

For the Account of: **OCTOBER CORP/CITY OF PORTLAND ESCROW CUSTODY**

Account Number: **60 00 6267 31 B**

Date: **SEPTEMBER 30, 2002**

*Summary of Assets*

	Investment Cost Basis	Market Value	Total Market Value	Est. Annual Income	Current Yield
<b>CASH</b>					
INCOME CASH	0.00	0.00	0.00		
PRINCIPAL CASH	0.00	0.00	0.00		
<b>TOTAL CASH</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>		
<b>CASH EQUIVALENTS</b>					
MISC CASH EQUIV - TXBL	33,521.35	33,521.35	33,521.35	577	1.72
<b>TOTAL CASH EQUIVALENTS</b>	<b>33,521.35</b>	<b>33,521.35</b>	<b>33,521.35</b>	<b>577</b>	<b>1.72</b>
<b>GRAND TOTAL</b>	<b>33,521.35</b>	<b>33,521.35</b>	<b>33,521.35</b>	<b>577</b>	<b>1.72</b>



For the Account of: OCTOBER CORP/CITY OF PORTLAND ESCROW CUSTODY

Account Number: 60 00 6267 31 8

Date: From SEPTEMBER 1, 2002 through SEPTEMBER 30, 2002

# MAINE BANK & TRUST

P.O. Box 17510, 467 Congress St.  
Portland, Maine 04112  
207-828-3000

## Receipts & Disbursements

Date	Income Cash	Principal Cash	Investment Cost Basis
	0.00	0.00	0.00
09/30/02		33,521.35	
09/30/02		-33,521.35	33,521.35
	0.00	0.00	33,521.35

**MAINE BANK & TRUST**

P.O. Box 17510, 467 Congress St.  
 Portland, Maine 04112  
 207-828-3000

For the Account of: **OCTOBER CORP/CITY OF PORTLAND ESCROW CUSTODY**

Account Number: **60 00 6267 31 8**

Date: *From SEPTEMBER 1, 2002 through SEPTEMBER 30, 2002*

*Summary Statement of Transactions*

	Income Cash	Principal Cash	Investment Cost Basis
<b>BEGINNING BALANCES</b>	0.00	0.00	0.00
<b>RECEIPTS</b>			
CONTRIBUTIONS		33,521.35	
<b>TOTAL RECEIPTS</b>	0.00	33,521.35	0.00
<b>DISBURSEMENTS</b>			
PURCHASES OF ASSETS		-33,521.35	33,521.35
<b>TOTAL DISBURSEMENTS</b>	0.00	-33,521.35	33,521.35
<b>ENDING BALANCES</b>	0.00	0.00	33,521.35

Department of Planning & Development  
Lee D. Urban, Director



**CITY OF PORTLAND**

Division Directors  
Mark B. Adelson  
Housing & Neighborhood Services

Alexander Q. Jaegerman, AICP  
Planning

John N. Lufkin  
Economic Development

**TO:** Duane Kline, Finance Department  
**FROM:** Alexander Jaegerman, Planning Division Director  
**DATE:** October 7, 2002  
**SUBJECT:** Request for Release of Performance Guarantee  
Intermodal Transfer Facility 383 Presumpscot St.  
(October Corporation)  
ID# 2001-0160 Lead CBL#420-A-002

Please release the Escrow Account # 6270 in the amount of \$335,213.55 for the Intermodal Facility at 383 Presumpscot Street.

Approved:

A handwritten signature in cursive script that reads "Alexander Jaegerman".  
Alexander Jaegerman  
Planning Division Director

cc: Sarah Hopkins, Development Review Services Manager  
✓ Jay Reynolds, Development Review Coordinator  
Todd Merkle, Public Works  
Code Enforcement  
file

O:\PLAN\CORRESP\DRC\PERFORM\383PRESUMPCOT1.DOC

DEVELOPMENT REVIEW COORDINATOR  
POST APPROVAL PROJECT CHECKLIST

Date: 4/14/10

Project Name: 383 Presumpscot Str.

Project Address: Subdivision - After the fact

Site Plan ID Number: 10-98900001

Planning Board/Authority Approval Date: 3/23/10

Site Plan Approval Date: 3/23/10

Performance Guarantee Accepted: 7/21/10

Inspection Fee Paid: 6/17/10

Infrastructure Contributions Paid: N/A

Amount of Disturbed Area in SF or Acres: < 1 Acre

MCGP/Chapter 500 Stormwater PBR: < 1 Acre

Plans/CADD Drawings Submitted: ?

Pre-Construction Meeting: 8/20/10

Conditions of Approval Met: 8/27/10

As-Builts Submitted: \_\_\_\_\_

Public Services Sign Off: 9/21/10

Certificate of Occupancy Memo Processed:  
(Temporary or Permanent) 10/27/10

Performance Guarantee to Defect Guarantee: 10/27/10

Defect Guarantee Released: 9/26/11

Memorandum  
Department of Planning and Urban Development  
Planning Division



---

**TO:** Ellen Sanborn, Finance Director  
**FROM:** Alexander Jaegerman, Planning Division Director  
**DATE:** 11-26-11  
**RE:** Request for Release of Defect Guarantee

---

<b>Project Name:</b>	<b>AFTER THE FACT SUBDIVISION</b>	<b>PROJECT ID:</b>	<b>10-98900001</b>
<b>Project Address:</b>	<b>383 PRESUMPCOT STREET</b>	<b>CBL:</b>	<b>420 A 001001</b>
<b>Applicant:</b>	<b>TIMOTHY SANDERS</b>		

Please release the Defect Guarantee #710-0000-233.91-33 for the **AFTER THE FACT SUBDIVISION**, at **383 PRESUMPCOT STREET**.

Remaining Balance **\$1,611.00**

**Approved:**   
Alexander Jaegerman  
Planning Division Director

**cc:** Barbara Barhydt, Development Review Services Manager  
Philip DiPierro, Development Review Coordinator



Memorandum  
Department of Planning and Urban Development  
Planning Division



---

**TO:** Ellen Sanborn, Finance Director  
**FROM:** Alexander Jaegerman, Planning Division Director  
**DATE:** 10-27-10  
**RE:** Request for Reduction of Performance Guarantee to Defect Guarantee

---

**Project Name:** AFTER THE FACT SUBDIVISION      **PROJECT ID:** 10-98900001  
**Project Address:** 383 PRESUMPCOT STREET      **CBL:** 420 A 001001  
**Applicant:** TIMOTHY SANDERS

Please reduce the Performance Guarantee #710-0000-233.91-33 for the AFTER THE FACT SUBDIVISION, at 383 PRESUMPCOT STREET to the Defect Guarantee.

Original Amount      \$16,110.00

This Reduction      \$14,499.00

Remaining Balance \$1,611.00

This is the reduction to a one year defect guarantee for this project.

Approved: \_\_\_\_\_

Alexander Jaegerman  
Planning Division Director

cc: Barbara Barhydt, Development Review Services Manager  
Philip DiPierro, Development Review Coordinator

Memorandum  
Department of Planning and Urban Development  
Planning Division



---

**TO:** Inspections Division  
**FROM:** Philip DiPierro  
**DATE:** 10-27-10  
**RE:** Permanent Certificate of Occupancy

---

**Project Name:** Presumpscot Street - 383; After The Fact Review 3 Lot Subdivision;  
Timothy Sanders  
**Project ID:** 10-98900001  
**Project Address:** 383 Presumpscot St CBL: 420 - A-001-001  
**Applicant:** Timothy Sanders

After visiting the site, I have the following comments:

Site work complete

**At this time, I recommend issuing a permanent Certificate of Occupancy.**

cc: Barbara Barhydt, Development Review Services Manager  
Tammy Munson, Inspections Division Director



Strengthening a Remarkable City. Building a Community for Life

www.portlandmaine.gov

Planning & Urban Development Department  
Penny St. Louis Littell, Director

MARCH 29, 2010

Planning Division  
Alexander Jaegerman, Director

**APPLICANT:**

Timothy Sanders  
383 Presumpscot Street  
Portland ME 04103

**CONSULTANT:**

Chris Michaud, SGC Engineering  
501 County Road  
Westbrook, ME 04092

**Project Name:** 383 Presumpscot Street, After The Fact Review  
**Subdivision**  
**Project ID:** 10-98900001  
**CBL:** 420 - A-001-001  
**Project Address:** 383 PRESUMPSCOT ST  
**Planner** Erick Giles, AICP, LEED AP

Dear Mr. Sanders:

On March 23, 2010, the Portland Planning Board considered the After The Fact Review for the three lot subdivision at 383 Presumpscot Street. The Planning Board reviewed the proposal for conformance with the standards of the Subdivision Ordinance. The Planning Board voted 7-0 to approve the application with the following conditions as presented below.

- i. On September 25, 2001 the Planning Board approved the development of an intermodal storage facility. Any reuse of the site requires the applicant to submit a change of use review application to be reviewed by the Zoning Administrator.
- ii. The applicant must use the City's standard sidewalk details for a Collector when installing the bituminous sidewalk and granite curbing on Presumpscot Street. The proposed sidewalk shall drain from the back of the walk to the street.
- iii. The applicant must locate the survey lot pin on the road right of way next to the driveway so the location of the sidewalk can be established.
- iv. The applicant shall saw cut the driveway and remove the corrugated metal culvert. If the culvert continues beyond the driveway, the pipe shall be saw cut at the edge of the driveway at the existing sidewalk and sealed water tight. Replace the driveway gravels and pave to the current driveway pavement thickness.

*done  
initials*

*done  
initials*

*done  
initials*

- done*  
*12/2/10*
- v. The applicant shall arrange with CMP to reset the utility pole guy wire with a support arm to allow construction of the proposed sidewalk.
  - vi. Prior to the release of the recording plat the applicant shall submit to the Planning Authority evidence of compliance with Sec. 24-36 of Ch. 24 Sewers of the Portland Code of Ordinances.

The approval is based on the submitted plans and the findings related to site plan and subdivision review standards as contained in Planning Report #3-10 for application **Subdivision #10-98900001** which is attached.

#### **STANDARD CONDITIONS OF APPROVAL**

Please note the following standard conditions of approval and requirements for all approved subdivision plans:


1. A revised recording plat listing all conditions of subdivision approval must be submitted for review and signature prior to the issuance of a performance guarantee.
2. Pursuant to 30-A MRSA section 4406(B)(1), any waiver must be specified on the subdivision plan or outlined in a notice and the plan or notice must be recorded in the Cumberland County Registry of Deeds within 90 days of the final subdivision approval).
3. The above approvals do not constitute approval of building plans, which must be reviewed and approved by the City of Portland's Inspection Division.
4. A performance guarantee covering the site improvements as well as an inspection fee payment of 2.0% of the guarantee amount and seven (7) final sets of plans must be submitted to and approved by the Planning Division and Public Services Dept. prior to the release of the subdivision plat for recording at the Registry of Deeds and prior to the release of a building permit or street opening permit. If you need to make any modifications to the approved plans, you must submit a revised subdivision application for staff review and approval.
5. Final sets of plans shall be submitted digitally to the Planning Division, on a CD or DVD, in AutoCAD format (\*.dwg), release AutoCAD 2005 or greater.
6. Mylar copies of the as-built drawings for the public streets and other public infrastructure in the subdivision must be submitted to the Public Services Dept. prior to the issuance of a certificate of occupancy.
7. The subdivision approval is valid for three (3) years.
8. A defect guarantee, consisting of 10% of the performance guarantee, must be posted before the performance guarantee will be released.

9. Prior to construction, a pre-construction meeting shall be held at the project site with the contractor, development review coordinator, Public Service's representative and owner to review the construction schedule and critical aspects of the site work. At that time, the site/building contractor shall provide three (3) copies of a detailed construction schedule to the attending City representatives. It shall be the contractor's responsibility to arrange a mutually agreeable time for the pre-construction meeting.
10. If work will occur within the public right-of-way such as utilities, curb, sidewalk and driveway construction, a street opening permit(s) is required for your site. Please contact Carol Merritt at 874-8300, ext. 8828. (Only excavators licensed by the City of Portland are eligible.)

Philip DiPierro, Development Review Coordinator, must be notified five (5) working days prior to date required for final site inspection. The Development Review Coordinator can be reached at 874-8632. Please make allowances for completion of site plan requirements determined to be incomplete or defective during the inspection. This is essential as all site plan requirements must be completed and approved by the Development Review Coordinator prior to issuance of a Certificate of Occupancy. Please schedule any property closing with these requirements in mind.

If you have any questions, please contact **Erick Giles** at 207-874-8723 or [egiles@planning.gov](mailto:egiles@planning.gov)

Sincerely,



Bill Hall, Chair  
Portland Planning Board

**Attachments:**

1. PB Report #3-10
2. Performance Guarantee Packet

**Electronic Distribution:**

Penny St. Louis Littell, Director of Planning and Urban Development  
Alexander Jaegerman, Planning Division Director  
Barbara Barhydt, Development Review Services Manager  
Eric Giles, AICP Planner  
Philip DiPierro, Development Review Coordinator  
Marge Schmuckal, Zoning Administrator  
Tammy Munson, Inspections Division Director  
Gayle Guertin, Inspections Division  
**Hard Copy:** Project File



SHAW BROTHERS CONSTRUCTION, INC.  
 511 MAIN ST., P.O. BOX 69 GORHAM, ME 04038  
 (207) 839-2552 Fax (207) 839-6239

# PROPOSAL

PROPOSAL SUBMITTED TO: Tim Sanders	CC: File	DATE: 11/16/2009
ADDRESS:	JOB NAME: 383 Presumpscot Street	FAX:
CITY, STATE, AND ZIP Portland, Maine 04101	JOB LOCATION: Portland	PHONE: (207) 798-2766
ATTN: Tim Sanders	DATE OF PLANS STAMP: N/A	<a href="mailto:tsanders@maine.rr.com">tsanders@maine.rr.com</a>

Shaw Brothers Construction, Inc. will furnish all necessary labor, equipment and materials to install approximately 125 lineal feet of granite curb and bituminous sidewalk to match the curb and sidewalk of the adjacent lots. All work to be in accordance with City of Portland standards.

**Scope of Work:**

- Dig Safe Notifications
- Traffic Control as required
- Sawcut pavement as required
- Install 124+/- lineal feet of granite curb lf of 15" pipe
- Install 5' wide x 124 lf of sidewalk ( 2" pavement, 12" Type A gravel)
- Install 7' wide grass esplanade
- Abandon 8" storm drain pipe
- Restore all disturbed areas
- Cleanup/Demobilize

Street Opening Fees	\$2,050.00
Granite Curb & Sidewalk	\$13,110.00
Restore (Loam & Seed)	\$950.00
<b>Total</b>	<b>\$16,110.00</b>

**Exclusions:**

- Performance and Payment Bond
- Federal, State and Local permit fees (street opening fees included)
- Relocation of Utility Pole Guy Wires
- Trees (if required)

**We Propose** hereby to furnish material, labor and equipment to complete the work described above for the sum of: \$ 16,110.00  
 ----- **Sixteen thousand one hundred ten dollars** -----

Payment to be made as follows: Net 30 days

Interest at 1.5 percent per month on accounts over 30 days. Collection costs and reasonable attorney's fees will be added to account.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. All alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents, or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Workers Compensation Insurance.

Authorized Signature

*Mark Barnes*

NOTE: This proposal may be withdrawn by us if not accepted within 30 days.

**Acceptance of Proposal-** The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to the work as specified. Payment will be made as outlined above.

Signature \_\_\_\_\_

Date of Acceptance: \_\_\_\_\_

Signature . \_\_\_\_\_

# CITY OF PORTLAND, MAINE

---

## PLANNING BOARD

Jaimy Caron, Chair  
Deborah Krichels, Vice Chair  
Kenneth M. Cole III  
Cyrus Y. Hagge  
Erin Rodriguez  
Mark Malone  
Orlando E. Delogu

October 8, 2001

Robert Arsenaault  
Sevee & Maher Engineers, Inc.  
4 Blanchard Road  
Cumberland, ME 04021

re: 383 Presumpscot Street Intermodal Facility CBL: 420 A001001

Dear Mr. Arsenaault:

On September 25, 2001 the Portland Planning Board voted unanimously (7-0) to approve your application to for an intermodal facility to be constructed in three phases at 383 Presumpscot Street. The Board found that the application met the standards of the Site Plan Ordinance of the Land Use Code and Chapters 500 and 502 of the Maine DEP Regulations.

The approval was granted for the project with the following conditions:

That an executed drainage maintenance agreement for the Vortechincs unit be provided by the applicant and approved by Corporation Counsel, prior to commencement of site work.

The approval is based on the submitted site plan and the findings related to site plan review standards as contained in Planning Report # 41-01, which is attached.

Given the approved phasing of this project, a separate performance guarantee and inspection fee will be issued for each separate phase. No work may commence on a subsequent phase until all work has been completed on the previous phase.

Please note the following provisions and requirements for all site plan approvals:


1. A performance guarantee covering the site improvements as well as an inspection fee payment of 2.0% of the guarantee amount and 7 final sets of plans must be submitted to and approved by the Planning Division and Public Works prior to the release of the building permit. If you need to make any modifications to the approved site plan, you must submit a revised site plan for staff review and approval.
2. The site plan approval will be deemed to have expired unless work in the development has commenced within one (1) year of the approval or within a time period agreed upon in writing by the City and the applicant. Requests to extend approvals must be received before the expiration date.

3. A defect guarantee, consisting of 10% of the performance guarantee, must be posted before the performance guarantee will be released.
4. Prior to construction, a preconstruction meeting shall be held at the project site with the contractor, development review coordinator, Public Works representative and owner to review the construction schedule and critical aspects of the site work. At that time, the site/building contractor shall provide three (3) copies of a detailed construction schedule to the attending City representatives. It shall be the contractor's responsibility to arrange a mutually agreeable time for the preconstruction meeting.
5. If work will occur within the public right-of-way such as utilities, curb, sidewalk and driveway construction, a street opening permit(s) is required for your site. Please contact Carol Merritt at 874-8300, ext. 8828. (Only excavators licensed by the City of Portland are eligible.)

The Development Review Coordinator 874-8632 must be notified five (5) working days prior to date required for final site inspection. Please make allowances for completion of site plan requirements determined to be incomplete or defective during the inspection. This is essential as all site plan requirements must be completed and approved by the Development Review Coordinator prior to issuance of a Certificate of Occupancy. Please schedule any property closing with these requirements in mind.

If there are any questions, please contact the Planning Staff.

Sincerely,



Jaimey Caron, Chair  
Portland Planning Board

cc: Alexander Jaegerman, Chief Planner  
Sarah Hopkins, Development Review Services Manager  
P. Samuel Hoffses, Building Inspector  
Marge Schmuckal, Zoning Administrator  
Tony Lombardo, Project Engineer  
Jay Reynolds, Development Review Coordinator  
William Bray, Director of Public Works  
Jeff Tarling, City Arborist  
Penny Littell, Associate Corporation Counsel  
Lt. Gaylen McDougall, Fire Prevention  
Inspection Department  
Lee Urban, Director of Economic Development  
Don Hall, Appraiser, Assessor's Office  
Susan Doughty, Assessor's Office  
Approval Letter File



For the Account of: OCTOBER COPACITY OF PORTLAND ESCROW

Account Number: 60 00 6270 31 2

Date: DECEMBER 31, 2001

**MAINE BANK & TRUST**

P.O. Box 17510, 467 Congress St.  
Portland, Maine 04112  
207-828-3000

CITY OF PORTLAND  
ATTN: ALEX JAEGERMAN  
389 CONGRESS STREET  
PORTLAND ME 04101

For the Account of: OCTOBER COPRICITY OF PORTLAND ESCROW

Account Number: 60 00 6270 31 2

Date: DECEMBER 31, 2001

**MAINE BANK & TRUST**  
P.O. Box 17510, 467 Congress St.  
Portland, Maine 04112  
207-828-3000

## Statement Of Account

---

### Contents

*Summary of Assets / 1*

*Review of Assets / 2*

*Receipts & Disbursements / 3*

*Summary Statement of Transactions / 4*

For the Account of: OCTOBER CORP/CITY OF PORTLAND ESCROW

Account Number: 60 00 6270 31 2

Date: DECEMBER 31, 2001

**MAINE BANK & TRUST**  
P.O. Box 17510, 467 Congress St.  
Portland, Maine 04112  
207-828-3000

# Summary of Assets

	Investment Cost Basis	Total Market Value	Est. Annual Income	Current Yield
<b>CASH</b>				
INCOME CASH	84.87	84.87		
PRINCIPAL CASH	-84.87	-84.87		
<b>TOTAL CASH</b>	<b>0.00</b>	<b>0.00</b>		
<b>CASH EQUIVALENTS</b>				
MISC CASH EQUIV-TXB1	335,298.42	335,298.42	7,175	2.14
<b>TOTAL CASH EQUIVALENTS</b>	<b>335,298.42</b>	<b>335,298.42</b>	<b>7,175</b>	<b>2.14</b>
<b>GRAND TOTAL</b>	<b>335,298.42</b>	<b>335,298.42</b>	<b>7,175</b>	<b>2.14</b>

For the Account of: **OCTOBER COPRICITY OF PORTLAND ESCROW**  
 Account Number: **60 00 6270 31 2**

Date: **From NOVEMBER 1, 2001 through DECEMBER 31, 2001**

**MAINE BANK & TRUST**  
 P.O. Box 17510, 467 Congress St.  
 Portland, Maine 04112  
 207-828-3000

# Receipts & Disbursements

Date		Income Cash	Principal Cash	Investment Cost Basis
	<b>BEGINNING BALANCES</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
11/27/01	CASH RECEIPT - INITIAL FUNDING TRANSFER FROM ACCT 5249 LIBRA FOUNDATION		335,213.55	
11/27/01	PURCHASED \$ 335,213.55 FEDERATED PRIME OBLIGATIONS FUND		-335,213.55	335,213.55
12/04/01	DIVIDEND RECEIVED FEDERATED PRIME OBLIGATIONS FUND	84.87		
12/05/01	PURCHASED \$ 84.87 FEDERATED PRIME OBLIGATIONS FUND		-84.87	84.87
	<b>ENDING BALANCES</b>	<b>84.87</b>	<b>-84.87</b>	<b>335,298.42</b>

For the Account of: OCTOBER COMPACTY OF PORTLAND ESCROW


Account Number: 60 00 6270 31 2

Date: From NOVEMBER 1, 2001 through DECEMBER 31, 2001

**MAINE BANK & TRUST**  
P.O. Box 17510, 467 Congress St.  
Portland, Maine 04112  
207-828-3000

## Summary Statement of Transactions


	Income Cash	Principal Cash	Investment Cost Basis
<b>BEGINNING BALANCES</b>	0.00	0.00	0.00
<b>RECEIPTS</b>			
CONTRIBUTIONS		335,213.55	
ORDINARY DIVIDENDS	84.87		
<b>TOTAL RECEIPTS</b>	84.87	335,213.55	0.00
<b>DISBURSEMENTS</b>			
PURCHASES OF ASSETS		-335,298.42	335,298.42
<b>TOTAL DISBURSEMENTS</b>	0.00	-335,298.42	335,298.42
<b>ENDING BALANCES</b>	84.87	-84.87	335,298.42

DESIGN BY: JIK		 <b>SME</b> <i>Seves &amp; Maher Engineers, Inc.</i> <i>Consulting Engineers</i> <i>Commercial Center, Maine</i>	JOB NO. 00013.07 DWG FILE FINAL SITE PLAN
DRAWN BY: GSK			
DATE: 5/04/01			
L.A.M.: EXCON			
P.C.P.: EXCON			
C-100			

OCTOBER CORPORATION  
 INTERMODAL TRANSFER FACILITY  
 PRESUMPSCOT STREET  
 PORTLAND, MAINE  
 EXISTING CONDITIONS PLAN



REV.	BY	DATE	STATUS
		8/17/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP FOR SITE PLAN APPROVAL
		6/26/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP



ZONING: I-Ma > MODERATE IMPACT INDUSTRIAL (OFF PENINSULA)

MINIMUM LOT SIZE: NONE

MAXIMUM IMPERVIOUS SURFACE RATIO: SEVENTY-FIVE (75) PERCENT

MAXIMUM BUILDING HEIGHT: FORTY-FIVE (45) FEET.

MINIMUM SIDE YARDS: TWENTY-FIVE (25) FEET.

MINIMUM REAR YARDS: EACH STRUCTURE SHALL BE SET BACK ONE (1) FOOT FROM THE REAR PROPERTY LINE FOR EACH ONE (1) FOOT OF BUILDING HEIGHT, UP TO TWENTY-FIVE (25) FEET.


MINIMUM FRONT YARDS: EACH STRUCTURE SHALL BE SET BACK ONE (1) FOOT FROM THE FRONT PROPERTY LINE FOR EACH ONE (1) FOOT OF BUILDING HEIGHT.

MINIMUM STREET FRONTAGE: SIXTY (60) FEET.

PAVEMENT SETBACK FROM LOT BOUNDARIES: TEN (10) FEET.

N/F Patrick E. Victoria & Marie

OCTOBER CORPORATION DB 18137  
 D.58 ACRES ±  
 25,455 SQ. FT. ±  
 TM 420 BL A TL P/O 2



ALWAY COMPANY

APPROXIMATE LOCATION OF BURIED OUTFALL PIPE

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93


DEED: 107.66

DEED: 105.93

DEED: 107.66

DEED: 105.93



DEED: 107.66

DESIGN BY: JRK	DATE: 5/04/01	 <b>Serve &amp; Maher Engineers, Inc.</b> Consulting Engineers Cumberland Center, Maine	JOB NO. 00013.07 DWG FILE FINAL SITE PLAN
DRAWN BY: SISK	DATE: 5/04/01		
POP: PH1-RNGRADE	DATE: 5/04/01		
UIN: PH1-RNGRADE			
C-101			

OCTOBER CORPORATION  
 INTERMODAL TRANSFER FACILITY  
 PRESUMPSCOT STREET  
 PORTLAND, MAINE  
 PHASE I  
 FINAL GRADING PLAN






REV.	BY	DATE	STATUS
		8/17/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP FOR SITE PLAN APPROVAL
		6/28/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP





LEGEND

- INDEX CONTOUR (EXISTING) - 95
- INTERMEDIATE CONTOUR (EXISTING) - 95
- FINAL GRADE CONTOUR - 95
- PROPERTY LINE - 95
- EDGE OF TRAVELED WAY - 95
- TEST PIT - TP-108
- EXISTING TREE LINE - 95
- EXISTING BUILDING - 95
- STREAM WITH DIRECTION OF FLOW - 95



JOB NO. 00013.07 DWG. FILE FINAL SITE PLAN			
PCP: PH2-FINGRADE	DATE: 5/04/01		
LMM: PH2-FINGRADE	DRAWN BY: BSK		
DESIGN BY: JRX			
<b>PHASE II</b> <b>FINAL GRADING PLAN</b>			
<b>OCTOBER CORPORATION</b> <b>INTERMODAL TRANSFER FACILITY</b> <b>PRESUMPSCOT STREET</b> <b>PORTLAND, MAINE</b>			
			
REV.	BY	DATE	STATUS
		8/17/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP FOR SITE PLAN APPROVAL
		8/26/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP

- LEGEND
- INDEX CONTOUR (EXISTING)
  - INTERMEDIATE CONTOUR (EXISTING)
  - FINAL GRADE CONTOUR
  - PROPERTY LINE
  - EDGE OF TRAVELED WAY
  - TP-108 TEST PIT
  - EXISTING TREE LINE
  - EXISTING BUILDING
  - STREAM WITH DIRECTION OF FLOW



- NOTES:
1. SEE DRAWING A-100 FOR BUILDING SECTION AND ELEVATION.
  2. SEE DRAWING E-100 FOR SITE LIGHTING.
  3. SEE DRAWING L-100 AND L-101 FOR LANDSCAPE PLAN AND DETAILS.




DESIGN BY: JAK		DRAWN BY: BSK		DATE: 5/04/01	LIN: PH3-FINGRADE	PCP: PH3-FINGRADE
<p style="text-align: center;"><b>SME</b>  <i>Sevon &amp; Maher Engineers, Inc.</i>  <i>Consulting Engineers</i>  <i>Portland Office, Maine</i></p>						
<p style="text-align: center;">OCTOBER CORPORATION          INTERMODAL TRANSFER FACILITY          PRESUMPSOOT STREET          PORTLAND, MAINE          PHASE III          FINAL GRADING PLAN</p>						
JOB NO. 00013.07 DWG FILE FINALSTEP.LAN						
REV.	BY	DATE	STATUS			
		8/17/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP FOR SITE PLAN APPROVAL			
		6/28/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP			




- LEGEND
- INDEX CONTOUR (EXISTING)
  - INTERMEDIATE CONTOUR (EXISTING)
  - FINAL GRADE CONTOUR
  - PROPERTY LINE
  - EDGE OF TRAVELED WAY
  - TP-10B
  - TEST PIT
  - EXISTING TREE LINE
  - EXISTING BUILDING
  - STREAM WITH DIRECTION OF FLOW



- NOTES:
1. SEE DRAWING E-100 FOR SITE LIGHTING.
  2. SEE DRAWING L-100 AND L-101 FOR LANDSCAPE PLAN AND DETAILS.
  3. ALL CURB RUNS SHALL BEGIN AND END WITH A 6" GRANITE TIP DOWN. SEE DETAIL DRAWING C-300.
  4. ADJUST CATCH BASINS TO GRADE AS FOLLOWS:
- |     |      |      |
|-----|------|------|
| 203 | 97.0 | 97.9 |
| 201 | 95.0 | 96.0 |
| 202 | 95.0 | 96.9 |
- EXIST RIM EL. PROPOSED RIM EL.

JOB NO. 00013.07 DWG FILE SITEPLAN	
 <b>SME</b> Serve & Maher Engineers, Inc. Consulting Engineers Cumberland Center, Maine	
DATE: 5/04/01	DESIGN BY: JMK
LMN: PH1-LAYOUT	DRAMA BY: BSK
PCP: PH1-LAYOUT	
<b>PHASE I</b> <b>GEOMETRIC LAYOUT &amp; UTILITY PLAN</b>	
<b>OCTOBER CORPORATION</b> <b>INTERMODAL TRANSFER FACILITY</b> <b>PRESUMPSCOT STREET</b> <b>PORTLAND, MAINE</b>	
REV. BY DATE STATUS	
8/17/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP FOR SITE PLAN APPROVAL
8/28/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP

CB NO.	TYPE	RM ELEV.	INV. IN	INV. OUT
201	B	95.0	95.0	91.50
202	B	95.9	91.25	91.15
203	B	97.0	90.70	90.45
204	B	95.9	91.50	91.50
205	B	95.9	91.50	91.50
206	B	94.7	90.50	90.50
207	B	95.7	90.40	90.30
208	B	98.5	99.80	99.30
210	B	98.5	99.10	98.85
211	B	96.5	98.10	98.00
212	B	94.0	99.10	98.00
213	B	94.0	97.20	97.10
214	B	93.5	97.30	97.10
215	B	93.5	98.80	98.70



**NOTE:**  
 SIDEWALK ESPALANDE  
 STA 4+88-STA 5+72  
 ESPALANDE WIDTH=5'  
 STA 6+00-6+50'  
 ESPALANDE WIDTH=5'  
 EXCEPT FOR TRANSITION AREAS TO CHANGE WIDTH.  
 THE ESPALANDE WILL BE 8' WIDE  
 (ESPALANDE WIDTHS INCLUDE CURBING)

**ZONING**  
 I-MB > MODERATE IMPACT INDUSTRIAL (OFF PENNSYLV.)

**MINIMUM LOT SIZE:** NONE

**MAXIMUM IMPERVIOUS SURFACE RATIO:** SEVENTY-FIVE (75) PERCENT

**MAXIMUM BUILDING HEIGHT:** FORTY-FIVE (45) FEET.

**MINIMUM SIDE YARDS:** TWENTY-FIVE (25) FEET.

**MINIMUM REAR YARDS:** EACH STRUCTURE SHALL BE SET BACK ONE (1) BUILDING HEIGHT, UP TO TWENTY-FIVE (25) FEET.

**MINIMUM FRONT YARDS:** EACH STRUCTURE SHALL BE SET BACK ONE (1) FOOT FROM THE FRONT PROPERTY LINE FOR EACH ONE (1) FOOT OF BUILDING HEIGHT.

**MINIMUM STREET FRONTAGE:** SIXTY (60) FEET.

**PAVEMENT SETBACK FROM LOT BOUNDARIES:** TEN (10) FEET.



JOB NO. 00013.07 DWG FILE SITEPLAN		DATE: 5/04/01	
SME Seves & Maher Engineers, Inc. Consulting Engineers Portland, Maine		DRAWN BY: BSK	
PP: PH2-LAYOUT		DESIGN BY: JRK	
LME: PH2-LAYOUT			
DATE: 5/04/01			
DRAWN BY: BSK			
DESIGN BY: JRK			
OCTOBER CORPORATION INTERMODAL TRANSFER FACILITY PRESUMPSCOT STREET PORTLAND, MAINE			
PHASE II GEOMETRIC LAYOUT & UTILITY PLAN			
REV.	BY	DATE	STATUS
		8/17/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP FOR SITE PLAN APPROVAL
		6/26/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP



ZONING: I-M2 > MODERATE IMPACT INDUSTRIAL (OFF PENINSULA)

MINIMUM LOT SIZE: NONE

MAXIMUM IMPERVIOUS SURFACE RATIO: SEVENTY-FIVE (75) PERCENT

MAXIMUM BUILDING HEIGHT: FORTY-FIVE (45) FEET



MINIMUM SIDE YARDS: TWENTY-FIVE (25) FEET



MINIMUM REAR YARDS: EACH STRUCTURE SHALL BE SET BACK ONE (1) FOOT FROM THE REAR PROPERTY LINE FOR EACH ONE (1) FOOT OF BUILDING HEIGHT, UP TO TWENTY-FIVE (25) FEET.


MINIMUM FRONT YARDS: EACH STRUCTURE SHALL BE SET BACK ONE (1) FOOT FROM THE FRONT PROPERTY LINE FOR EACH ONE (1) FOOT OF BUILDING HEIGHT.

MINIMUM STREET FRONTAGE: SIXTY (60) FEET.

PAVEMENT SETBACK FROM LOT BOUNDARIES: TEN (10) FEET.



JOB NO. 00013.07 DWG FILE STEPLAN		 <b>Serve &amp; Maher Engineers, Inc.</b> Consulting Engineers 100 Portland Center, Maine	
PP: PH3-LAYOUT	LAN: PH3-LAYOUT		
DATE: 5/04/01	DRAWN BY: BISK		
DESIGN BY: JPK			
OCTOBER CORPORATION INTERMODAL TRANSFER FACILITY PORTLAND, MAINE PHASE III GEOMETRIC LAYOUT & UTILITY PLAN			
REV.	BY		DATE
		8/17/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP FOR SITE PLAN APPROVAL
		6/26/01	SUBMITTED TO PORTLAND PLANNING BOARD WORKSHOP



NOTE:  
ADJUST CATCH BASINS TO GRADE AS FOLLOWS:

CB#	EAST RIM EL.	PROPOSED RIM EL.
203	97.0	97.9
202	95.0	96.8
201	95.0	98.0

ZONING  
I-IND > MODERATE IMPACT INDUSTRIAL (OFF PENINSULA)

MINIMUM LOT SIZE: NONE

MAXIMUM IMPERVIOUS SURFACE RATIO: SEVENTY-FIVE (75) PERCENT

MAXIMUM BUILDING HEIGHT: FORTY-FIVE (45) FEET.

MINIMUM SIDE YARDS: TWENTY-FIVE (25) FEET.

MINIMUM REAR YARDS: EACH STRUCTURE SHALL BE SET BACK ONE (1) FOOT FROM THE REAR PROPERTY LINE FOR EACH ONE (1) FOOT OF BUILDING HEIGHT, UP TO TWENTY-FIVE (25) FEET.

MINIMUM FRONT YARDS: EACH STRUCTURE SHALL BE SET BACK ONE (1) FOOT FROM THE FRONT PROPERTY LINE FOR EACH ONE (1) FOOT OF BUILDING HEIGHT.

MINIMUM STREET FRONTAGE: SIXTY (60) FEET.

PAVEMENT SETBACK FROM LOT BOUNDARIES: TEN (10) FEET.

E100

Drawing Number:

Scale: 1" = 30'-0"  
Date: August 16, 2001  
Revision Dates:

**LIGHTING PLAN**

Drawing Title:

Project No. 01414 IFF


Presumpscot Street  
Portland, ME

**INTERMODAL  
TRANSFER  
FACILITY**

OCTOBER  
CORPORATION  
PORTLAND, MAINE

424 Cumberland Avenue  
Portland, ME 04101  
Phone: (207)774-4441  
Fax: (207)774-4016  
PO Box 6566  
Laconia, NH 03247  
Phone: (603)524-3000  
Fax: (603)521-0700

Chris Walter Stewart  
Architects



L101

Drawing Number

Scale AS NOTED  
 Date August 16, 2001  
 Revision JCB

**SITE DETAILS**

Project No. 0144-11  
 Drawing Title

Presumpscot Street  
 Portland, ME

**INTERMODAL  
 TRANSFER  
 FACILITY**




OCTOBER  
 CORPORATION  
 PORTLAND, MAINE


424 Cumberland Avenue  
 Portland, ME 04101  
 Phone: (207) 774-4441  
 Fax: (207) 774-4016  
 PO Box 8885  
 Lakewood, NH 03247  
 Phone: (603) 924-3000  
 Fax: (603) 927-0700

Chris Walker Stewart  
 Architects



**DECIDUOUS TREES**  
 NOT TO SCALE  
 2" TO 4" CALIPER





**S** SOUTH ELEVATION  
SCALE: 1/8"=1'-0"








FIGURE 2  
OCTOBER CORPORATION  
INTERMODAL TRANSFER FACILITY  
PRESUMPSCOT STREET  
PORTLAND, MAINE  
UPGRADIENT WATERSHED



REFERENCE:  
USGS 7.5 MINUTE TOPOGRAPHIC MAP  
PORTLAND WEST DATED 1956,  
PHOTOREVISED 1978.

LEGEND:  
SUBCATCHMENT BOUNDARY  
SC-217 SUBCATCHMENT DESIGNATION  
REACH DESIGNATION  
TIME OF CONCENTRATION  
DESIGNATION





L100

Drawing Number:

Revision Dates  
Date: August 16, 2001  
Scale: 1" = 30'-0"

LANDSCAPE PLAN

Drawing Title:

Project No. 0144-01

Presumpscot Street  
Portland, ME

**INTERMODAL  
TRANSFER  
FACILITY**

OCTOBER  
CORPORATION  
PORTLAND, MAINE

434 Cumberland Avenue  
Portland, ME 04103  
Phone: (207) 744-4444  
Fax: (207) 744-4016  
PO Box 6696  
Laconia, NH 06247  
Phone: (603) 524-5000  
Fax: (603) 524-5000

Charles Walter Simpson  
Architects

