

WALL TYPES:

GRAPHIC DEPICTION		DESCRIPTION			
		DEMISING WALL 1 HOUR FIRE RATED WITH DEFLECTION HEAD SLIP TRACK - 5/8" TYPE "X" GWB - 6" MTL STUDS AT 16" O.C. - 6" ROXUL MINERAL BATT INSULATION - RESILIENT CHANNEL - 5/8" TYPE "X" GWB			
		TYPE	FIRE RATING	UL NUMBER	STC RATING
1A		1 HR	U465	N/A	N/A

GRAPHIC DEPICTION		DESCRIPTION			
		- 5/8" TYPE "X" GWB - 6" MTL STUDS AT 16" O.C. - 6" ROXUL MINERAL BATT INSULATION - RESILIENT CHANNEL - 5/8" TYPE "X" GWB			
		TYPE	FIRE RATING	UL NUMBER	STC RATING
1B		1 HR	U465	N/A	N/A

GRAPHIC DEPICTION		DESCRIPTION			
		- 5/8" GWB - 3/8" MTL STUDS AT 16" O.C. - 3/2" ROXUL MINERAL BATT INSULATION - 5/8" GWB			
		TYPE	FIRE RATING	UL NUMBER	STC RATING
NA		N/A	N/A	N/A	N/A

GRAPHIC DEPICTION		DESCRIPTION			
		- 5/8" GWB - 3/8" MTL STUDS AT 16" O.C. - 3/2" ROXUL MINERAL BATT INSULATION - 1/2" SOUNDBOARD - 5/8" GWB			
		TYPE	FIRE RATING	UL NUMBER	STC RATING
NB		N/A	N/A	N/A	N/A

GRAPHIC DEPICTION		DESCRIPTION			
		- 5/8" GWB - 3/8" MTL STUDS AT 16" O.C. - 5/8" GWB			
		TYPE	FIRE RATING	UL NUMBER	STC RATING
NC		N/A	N/A	N/A	N/A

GRAPHIC DEPICTION		DESCRIPTION			
		DOUBLE SOUND WALL AND PERIMETER BEARING WALL (SEE STRUCTURAL DRAWINGS FOR STUD SIZES) 1" AIR SPACE BETWEEN WALLS - MTL STUDS AT 16" O.C. - 3/2" ROXUL MINERAL BATT INSULATION - 5/8" GWB			
		TYPE	FIRE RATING	UL NUMBER	STC RATING
ND		N/A	N/A	N/A	N/A



© 2017 RYAN SENATORE ARCHITECTURE

GRIME STUDIOS  
PORTLAND, MAINE



RYAN SENATORE  
**ARCHITECTURE**  
565 CONGRESS STREET, SUITE 304  
PORTLAND, MAINE 04101  
207-650-8414  
senatorearchitecture.com

CONSULTANTS:

REVISIONS:

DATE: OCTOBER 16, 2017

PROJECT No. 1428

DRAWN BY: RJS / RRT

CHECKED BY: RJS

SCALE: AS NOTED

SHEET TITLE:  
WALL AND FLOOR TYPES

A0-1