

GENERAL DEMOLITION NOTES:

 SEE GI001 FOR GENERAL PROJECT NOTES, SYMBOL LEGEND, PARTITION LEGEND, AND ABBREVIATIONS.
 CONTRACTOR TO PROTECT ALL EXISTING

SURFACES AND MATERIALS DURING
DEMOLITION. ANY DAMAGE WILL BE
CORRECTED OR REPLACED WITH NEW
MATERIAL AND FINISH TO MATCH ADJACENT
FINISH.

3. IN AREAS WHERE EXISTING EQUIPMENT, FURNITURE, OR CEILINGS ARE IMPACTED BY DEMOLITION OR NEW WORK, CONTRACTOR SHALL REMOVE AND PROTECT DURING CONSTRUCTION AND REINSTALL/RETURN TO ORIGINAL LOCATION.

DEMOLITION KEY NOTES:

- 1 DEMOLISH EXISTING WALL COMPLETE
- 2 DEMOLISH EXISTING OH DOOR
- DEMOLISH FLOOR AREA SHOWN HATCHED.
 COORDINATE WITH NEW CONSTRUCTION TO
 ENSURE THAT THE AREAS THAT ARE TO
 REMAIN CONTINUE TO BE APPROPRIATELY
 STRUCTURALLY SUPPORTED.
- 4 DEMOLISH EXISTING STEEL STAIRS
- DEMOLISH FULL HEIGHT WALL COMPLETE,
 BUT DO NOT DISTURB OR REMOVE EITHER
 OF THE STEEL STRUCTURAL COLUMNS
 AND CONCRETE COLUMN BASES
 EMBEDDED IN THE WALL.
- REMOVE EXISTING METAL AS REQUIRED TO PATCH AND MATCH FOR NEW INFILL
- 7 DEMOLISH EXISTING CANOPY.
- 8 DEMOLISH BOLLARDS AND PATCH PAVEMENT WHERE DISTURBED
- 9 CUT EXISTING SLAB AS REQUIRED FOR ELEVATOR PIT. EXCAVATE AND DISPOSE OF FILL MATERIAL.
- DEMOLISH WALL TO EXTENT REQUIRED FOR INSTALLATION OF NEW WINDOW. SEE AE101.
- DEMOLISH EXISTING DOOR IN PREPERATION FOR A NEW DOOR TO BE INSTALLED IN THE SAME LOCATION
- 12 NOT USED
- 13 DEMOLISH EXISTING DOOR
- DEMOLISH EXISTING WINDOW FOR INFILL WITH NEW METAL SIDING WALL ASSEMBLY TO MATCH

144 Fore Street/P.O. Box 618
Portland, Maine 04104

144 For

PLANNING
INTERIORS
ENERGY

35

JANET OF WANTE

O" 1"

SCALE: As indicated PROJECT MANAGER: JLH

JC/DRAWN BY: SHK

A/E OF RECORD: JLH

PROJECT NO: 15105

SMRT FILE: AD101-15105

DATE: 7-29-15

SHEET TITLE:
FIRST FLOOR
DEMO PLAN

SHEET No. AD101