

RRUS 11 – Dual PA RRU.

Technical Data

- › Multi standard
- › RF: 2x30 Watts
- › Carrier BW: 1.4 – 20 MHz
- › Alarms: 2
- › Dimensions (with sunshield):
 - Width: 17.0 in
 - Height: 17.8 in
 - Depth: 7.2 in
 - Weight: 55 lbs (Band 12)
 - Weight: 50 lbs (Band 4)
- › Temperature: -40 to +131 F
- › Cooling: Self convection
- › Power: -48 VDC
- › Rec. fuse size 20 Amp
 - Rec. DC cable:
 - › 6 mm² up to 60 meters
 - › 10 mm² over 60 meters
 - › Shielded
- › Power Cons: 200 Watts typ.



RRUS-11 I/F

RBS6000

