CITY OF PORTLAND, MAINE
RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/13/14

5/12 Roof

2x10 Ledger

2x8 Roof Rafters 16" O.C.

R-49

5/8 OSB

Full Grace Ice +

2x8 Roof Rafter
Appx 9' Span

2x6 Collar Ties

Simpson H2.5 on Each Rafter

Roof will be 8/12 +/-
9'x9'

Boral Trim 1x8 w/ 1x4 Shadow Painted.

* Painted Alum Drip Edge
* CT ARC Roof Shingles

Ext House

(Window Headers)

Built up 2x8 w/ ½CDX Ply