Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/13/14

Project Description - Bathroom Remodel/Addition

37 Summer Place, Portland ME 04103

We wish to build a second story 8' by 8' addition off our bedroom for a master bathroom. This addition will be supported by 8" by 8" posts. The bathroom will contain a shower, tub, toilet, and two sinks. The work is being done by Envy construction and a proposal with building materials list is attached to the application. Ingress and egress from the bathroom will be from the bedroom through a 30" door. Windows will be Pella 350 series and walls will be 2x6 construction with R19 insulation. The floors and ceiling will be R 30 insulation. Floor joists will be 2x10.

Scott Stevenson