Envy Construction
Falmouth, Maine 04105
(207)232-0351

CITY OF PORTLAND, MAINE · RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/13/14

Scott Stevenson
37 Summer Place
Portland, Maine

207-632-2205

ESTIMATE

Estimate # 179

Estimate Date 03/11/2014

Item	Description	Unit Price	Quantity	Amount
Product	8'X8' Master Bath Addition: -Framing -6"X6" Support Post 2"X6" Walls 2"X10" Floor Joists Shed Style Roof -3/4" T&G Glued Advantech Flooring -1/2" Green Board Zip Wall -5/8" Brown Board zip Roof -Metal Roof -All Trim will be white Azek PVC Board -6" Novelty siding -R19 wall insulation -R30 Floor/Ceiling -Mildew Resistant Sheetrock	9994.00	1.00	9,994.00
Expense	Window Allowance	400.00	2.00	800.00
Expense	Azek PVC Board T&G Allowance (For the underside of the addition)	700.00	1.00	700.00

Subtotal	11,494.00
Total	11,494.00
Amount Paid	0.00