Covering Schedule

Id	Qty	Type	Start Length	Gage	OP	Fin.	Color	Direction
#3	10	PR	24'-1 1/2"	26	F	K	GG	Left to Right
#7	21	PR	13'-11"	26	1	K	GG	Left to Right

Oper. Code:F=CR,SQ
Oper. Code:1=SQ,SQ
Finish:K=KXL (Kynar)
Color:GG=Cool Granite Gray

Trim Schedule

Id	Parts	Color	Details
T1	DFT10,JT10,TRMX01	Cool Granite Gray	
T2	DFT10,HTS10,TRMX01	Cool Granite Gray	
T3	(10)HSEP1,(10)RFR10,(4)RKF20,RKF16	Cool Imperial Blue	RC34H4,RC35N1
T4	(0.9)BA125	Match Wall Color	EN52A1,RC00A1,WC01

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/10/13

Insulation Schedule (Install in same direction as Covering)

Id	Qty	Type	Start Run	Last Run	Thick.	Facing	Increment
BLK1	16	IB	25'-0"	25'-0"	6.00	PS	

Starter Width= 6'-0", Interm. Width= 6'-0", End Width= 6'-0"
Location =Outside Secondary Structural
Direction =Across Secondary Structural
Type:IB=Fiberglass Blanket
Facing:PS=Polypropylene Scrim Kraft, Standard Duty
Shape Name = Pack Edge, Wall = 4

COVERING ELEVATION AT D

1 2'-0"
Dimension Key

Fastener Schedule

Part	Discription
0097597-112	(T-2) #17/#12-14 x 1 7/8" Stand-Off, 5/16" Hex Hd, SS Cap w/Washer
0097585-112	(T-2) #12-14 x 1 1/2", 5/16" Hex Hd, SS Cap w/Washer
0097581-112	(T-1) 1/4-14 x 7/8", 5/16" Hex Hd, SS Cap w/Washer

Shape Name = Pack Edge, Wall = 4

1. PRE-DRILLING 1/8 DIAMETER HOLES FOR STRUCTURAL FASTENERS MAY BE REQUIRED FOR HEAVY GAGE NESTED ZEE's AND/OR FASTENERS TO STRUCTURAL BEAMS
2. STEEL PANELS ARE AN INTEGRAL PART OF THE STRUCTURAL SYSTEM. REMOVAL OR ALTERATION WITHOUT PRIOR AUTHORIZATION IS PROHIBITED.
3. PANELS SHOWN WITH A LENGTH LESS THAN 5 FT MAY HAVE TO BE FIELD CUT.
4. SEE JOB DETAILS FOR COVERING AND TRIM FASTENER SPECIFICATION.

THE VP ENGINEER'S SEAL APPLIES ONLY TO THE WORK PRODUCT OF VP AND DESIGN AND PERFORMANCE REQUIREMENTS SPECIFIED BY VP. THE VP ENGINEER'S SEAL DOES NOT APPLY TO THE PERFORMANCE OR DESIGN OF ANY OTHER PRODUCT OR COMPONENT FURNISHED BY VP EXCEPT TO ANY DESIGN OR PERFORMANCE REQUIREMENTS SPECIFIED BY VP.

THIS DRAWING, INCLUDING THE INFORMATION HEREON, REMAINS THE PROPERTY OF VP BUILDINGS. IT IS PROVIDED SOLELY FOR ERECTING THE BUILDING DESCRIBED IN THE APPLICABLE PURCHASE ORDER AND SHALL NOT BE MODIFIED, REPRODUCED OR USED FOR ANY OTHER PURPOSE WITHOUT PRIOR WRITTEN APPROVAL OF VP BUILDINGS.

THE GENERAL CONTRACTOR AND/OR ERECTOR IS SOLELY RESPONSIBLE FOR ACCURATE GOOD QUALITY WORKMANSHIP IN ERECTING THIS BUILDING IN ACCORDANCE WITH THIS DRAWING, DETAILS REFERENCED IN THIS DRAWING, ALL APPLICABLE VP BUILDINGS ERECTION GUIDES, AND INDUSTRY STANDARDS PERTAINING TO PROPER ERECTION, INCLUDING THE CORRECT USE OF TEMPORARY BRACING.

VP Buildings
3200 Players Club Circle Memphis TN 38125

REV	DATE	BY	DESCRIPTION

NTS

COVERING ELEVATION AT D

BUILDER: Patco
CUSTOMER:
LOCATION: Portland, Maine
PROJECT: Pack Edge
BUILDERS PO#:

VP BUILDINGS
VARCO PRUDEN
A BlueScope Steel Company
VPC VERSION: 2012.3d

JOB # 12-4084
DATE 3/14/2013
DRAWN/CHECK COOP DC
PAGE 18

3/14/2013 7:37:38
FILENAME: Pack Edge addition BO
a division of BlueScope Buildings North America, Inc.