COM*check* Software Version 3.9.1

Envelope Compliance Certifica

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/10/13

2009 IECC

Section 1: Project Information

Project Type: **New Construction**
Project Title : Pack Edge Addition

Construction Site:
352 Presumpscot Street
Portland, ME 04103

Owner/Agent:
Jim Freeman
Pack Edge
352 Presumpscot Street
Portland , ME 04103

Designer/Contractor:
Dennis Waters
Patco Construction Inc
1293 Main Street
Sanford, ME 04073
207-324-5574 x101
dwaters@patco.com

Section 2: General Information

Building Location (for weather data):	**Portland, Maine**
Climate Zone:	**6a**
Building Type for Envelope Requirements:	**Non-Residential**

Activity Type(s)	Floor Area
loading/storage (Warehouse)	4056

Section 3: Requirements Checklist

Envelope PASSES: Design 2% better than code.

Climate-Specific Requirements:

Component Name/Description	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U-Factor(a)
Roof 1: Metal Building, Standing Seam	4059	19.0	0.0	0.065	0.049
Exterior Wall 1: Metal Building Wall	5096	19.0	0.0	0.070	0.069
Door 1: Insulated Metal, Non-Swinging	504	---	---	0.060	0.500
Door 2: Insulated Metal, Swinging	42	---	---	0.140	0.700

(a) Budget U-factors are used for software baseline calculations ONLY, and are not code requirements.

Air Leakage, Component Certification, and Vapor Retarder Requirements:

- ☐ 1. All joints and penetrations are caulked, gasketed or covered with a moisture vapor-permeable wrapping material installed in accordance with the manufacturer's installation instructions.
- ☐ 2. Windows, doors, and skylights certified as meeting leakage requirements.
- ☐ 3. Component R-values & U-factors labeled as certified.
- ☐ 4. No roof insulation is installed on a suspended ceiling with removable ceiling panels.
- ☐ 5. 'Other' components have supporting documentation for proposed U-Factors.
- ☐ 6. Insulation installed according to manufacturer's instructions, in substantial contact with the surface being insulated, and in a manner that achieves the rated R-value without compressing the insulation.
- ☐ 7. Stair, elevator shaft vents, and other outdoor air intake and exhaust openings in the building envelope are equipped with motorized dampers.
- ☐ 8. Cargo doors and loading dock doors are weather sealed.
- ☐ 9. Recessed lighting fixtures installed in the building envelope are Type IC rated as meeting ASTM E283, are sealed with gasket or caulk.
- ☐ 10. Building entrance doors have a vestibule equipped with self-closing devices.

Exceptions:

- ☐ Building entrances with revolving doors.
- ☐ Doors not intended to be used as a building entrance.
- ☐ Doors that open directly from a space less than 3000 sq. ft. in area.
- ☐ Doors used primarily to facilitate vehicular movement or materials handling and adjacent personnel doors.
- ☐ Doors opening directly from a sleeping/dwelling unit.

RESURGAM CITY OF PORTLAND, MAINE

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/10/13

Section 4: Compliance Statement

Compliance Statement: The proposed envelope design represented in this document is consistent with the building plans, specifications and other calculations submitted with this permit application. The proposed envelope system has been designed to meet the 2009 IECC requirements in COM*check* Version 3.9.1 and to comply with the mandatory requirements in the Requirements Checklist.

Name - Title	Signature	Date
JOHN EINSIEDLER, R.A. ARCHITECT		APRIL 29, 2013