de La Fontaine

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/10/13

Honeycomb core

Compression ratio:1857 pounds per sq./ft, 1"(25.4mm) cell with phenoloc
Continuous bonding of core to steel faces.

Option A0

Inoperable panel STC38, with appropriate sound gasketings operational door calculated STC of 33.
Added stiffener, full height, in middle of door when over 3'0" wide.

Polystyrene core

"R" factor: 7.03(hr °F-sq/ft)/BTU....."U" factor: 0.14 BTU/(hr °F-sq/ft)
Continuous bonding of core to steel faces.

Option A1

Added stiffener, full height, in middle of door when over 3'0" wide.