GENERAL NOTES

GENERAL CONTRACTOR SHALL PROVIDE ANY MECHANICAL WORK REQUIRED ON A DESIGN BUILD BASIS. REBALANCE SYSTEM WHEN COMPLETE.

GENERAL CONTRACTOR SHALL PROVIDE ALL ELECTRICAL AND PLUMBING WORK ON A DESIGN BUILD BASIS.

GENERAL CONTRACTOR SHALL PROVIDE ALL FIRE PROTECTION WORK ON A DESIGN BUILD BASIS.

MEP DESIGN BUILD SCOPE OF WORK SHALL MEET ALL APPLICABLE STATE AND CITY CODE REQUIREMENTS.

ALL WORK SHALL CONFORM TO FEDERAL, STATE AND MUNICIPAL CODES AND ORDINANCES. THESE SHALL SUPERSEDE DRAWINGS, NOTES AND DIMENSIONS IN ALL CASES. THE ARCHITECT SHALL BE NOTIFIED OF SUCH CHANGES BEFORE WORK IS STARTED. OBTAIN PERMITS BEFORE STARTING WORK AND OBTAIN APPROVALS OF ALL REGULATORY AGENCIES UPON COMPLETION AND AS REQUIRED.

THE CONTRACT DOCUMENTS CONSIST OF THE DRAWINGS & SPECIFICATIONS: GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCION-AIA DOCUMENT A201 (1987 EDITION), OWNER-CONTRACTOR AGREEMENTS AND ALL ADDENDA ISSUED PRIOR TO AND ALL PLAN CHANGES ISSUED AFTER EXECUTION OF THE CONTRACT.

UNLESS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS AS BEING NOT IN CONTRACT (N.I.C.) OR EXISTING: ALL ITEMS, MATERIALS AND INSTALLATION OF SAME ARE A PART OF THE CONTRACT DEFINED BY THE CONSTRUCTION DOCUMENTS. THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL ACCESSORIES, COMPONENTS AND ASSEMBLIES REQUIRED FOR THE WORK SHOWN.

CONTRACTOR SHALL SUBMIT A DETAILED PROJECT SCHEDULE. CONTRACTOR IS SOLELY RESPONSIBLE FOR CONSTRUCTION SEQUENCING, METHODS AND TECHNIQUES.

THE GENERAL CONTRACTOR IS RESPONSIBLE FOR PAYING AND OBTAINING ALL PERMITS, INSPECTIONS, REQUIRED TESTS AND UTILITY CONNECTIONS UNLESS OTHERWISE NOTED.

CONTRACTOR SHALL PROVIDE AND IS SOLEY RESPONSIBLE FOR PUBLIC AND EMPLOYEE PROTECTION AS NECESSARY AND AS REQUIRED BY THE CODES, ORDINANCES AND REGULATIONS OF GOVERNMENTAL AGENCIES HAVING JURISDICTION AT THE PROJECT PLACE.

CONTRACTOR TO INSPECT THE AREA OF WORK PRIOR TO STARTING AND NOTIFY THE ARCHITECT OF ANY DISCREPENCIES BETWEEN THESE DRAWINGS AND THE ACTUAL CONDITIONS. DO NOT SCALE THESE DRAWINGS.

PRIOR TO CLOSING ANY WALLS OR CEILINGS, ALL SYSTEMS (HVAC, PLUMBING, ELECTRICAL) SHALL BE INSPECTED, AND WHERE REQUIRED, TESTING BY CONTRACTOR'S ENGINEERS AND BY PROPER AUTHORITIES HAVING JURISDICTION TO INSURE THEIR PROPER INSTALLATION AND FUNCTION.

13. THE ARCHITECT RESERVES THE RIGHT TO MOVE ANY FIXTURE, RECEPTACLE OR BUILT-IN OBJECT UP UNTIL THE TIME HE/SHE SHALL APPROVE THE WALLS OR CEILINGS TO BE CLOSED. THIS APPROVAL SHALL TAKE PLACE PRIOR TO THE INSPECTORS APPROVAL SO AS NOT TO CONFLIGT WITH ANY BUILDING OFFICIALS DECISIONS.

14. AT NEW CONSTRUCTION PROVIDE ONE PRIMER COAT AND TWO TOP COATS OF PAINT WITH COLOR .

15. SUBMIT SAMPLES, SHOP DRAWINGS & SCHEDULES FOR ARCHITECT REVIEW & APPROVAL FOR THE FOLLOWING:
    a. PAINT, BASE MOULDING SAMPLES
    b. DOORS, FRAMES, HARDWARE SCHEDULES & PRODUCT DATA SHEETS
    c. MILLWORK SHOP DRAWINGS & SAMPLES
    d. CEILING SYSTEM
    e. LIGHT FIXTURES

16. IN THE EVENT OF DISCREPANCIES BETWEEN ANY DRAWINGS AND/OR SPECIFICATIONS, THE COSTLIER OR MORE RESTRICTIVE CONDITIONS SHALL BE DEEMED THE CONTRACT REQUIREMENT, UNLESS OTHERWISE STATED IN WRITING, FROM THE OWNER.

17. GENERAL CONTRACTOR SHALL WARRANT WORK PERFORMED FOR A PERIOD OF ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE.

18. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO KEEP THE PREMISE CLEAN OF DEBRIS, RUBBISH, EXCESS MATERIALS, ETC.

19. CHARGES FOR EXTRA WORK DONE BY THE CONTRACTOR WILL NOT BE HONORED UNLESS THE WORK AND THE AMOUNT ARE AGREED TO BY THE OWNER IN WRITING BEFORE THE WORK IS DONE, BASED UPON UNIT PRICING.

20. AS REQUIRED BY CODE, EACH CONTRACTOR AND EACH SUBCONTRACTOR SHALL OBTAIN REQUIRED INSPECTION OF THAT PORTION OF WORK.

21. ALL DIMENSIONS ARE TO THE FACE OF DRYWALL OR MASONRY U.O.N.

22. QUALITY CONTROL:
A. SITE MEETINGS: CONTRACTOR TO CONDUCT SITE MEETINGS AND WRITE MEETING MINUTES AT FREQUENCY AS DIRECTED BY OWNER. CONTRACTOR AND ALL SUB-CONTRACTORS MUST BE PRESENT, UNLESS WAIVED BY OWNER.
B. INSTALLATION: EXCEPT AS MORE STRINGENT REQUIREMENTS ARE INDICATED ON THESE DRAWINGS AND IN THESE NOTES, COMPLY WITH GENERALLY ACCEPTED INDUSTRY STANDARDS AND INSTALL PRODUCTS IN STRICT COMPLIANCE WITH MANUFACTURER'S PRINTED INSTRUCTIONS.
C. WHEN EVALUATING APPEARANCE OR CONFORMANCE WITH DESIGN INTENT, THE WORDS 'ACCEPTABLE', 'VISIBLE', 'INVISIBLE', 'MATCHING', 'ALIGNED' AND SIMILAR TERMS OF JUDGEMENT SHALL MEAN 'ACCEPTABLE, ETC., IN THE OPINION OF THE ARCHITECT OR OWNER'.

CODE SUMMARY

PROJECT IS DESIGNED TO: INTERNATIONAL BUILDING CODE, 2003 EDITION.

USE GROUP: BUSINESS

PROJECT SIZE: 10,0000 SF, 1 STORIES.

TYPE OF CONSTRUCTION: TYPE 5

FIRE SUPPRESSION: N/A
BELOW SQ. FT. REQUIREMENT W/ FRONTAGE EXCEPTION

LIST OF DRAWINGS

T001	TITLE SHEET
A101	FLOOR PLANS
A102	ROOF PLAN
A201	EXTERIOR ELEVATIONS
A601	BUILDING SECTIONS
A701	WALL SECTIONS
S1	FOUNDATION PLAN
S2	ROOF FRAMING PLANS
S3	PLANS SECTIONS AND DETAILS

ISSUE/REVISION DATE

1	08/15/05

ROUNDHOUSE 125 PRESUMPSCOT STREET

NO | DATE | REVISIONS
1 | 08/18/05 | PERMITING
2 |

PROJECT NORTH

OWNER: ROUNDHOUSE
BUILDING 1
PORTLAND, MAINE

JERRY ADE

TITLE: COVER

SCALE: AS NOTED

Cubellis Associates Inc.
Architecture Interiors Engineering
Boston Philadelphia Chicago Portland, ME
428 Fore Street, 3rd Flr.
Portland, ME 04101
Tel: 207-874-2777
Fax: 207-874-2775
www.cubellis.com

DRAWN BY: DVS
CHECKED BY: GDN
DATE:

T001

05072PT

E:\Jerry-Ade\05072PTRoundhouseofficebldg\Dwg\Arch\05072PTT001.dwg Aug 19, 2005 - 7:44am

COPYRIGHT (C) BY CUBELLIS ASSOCIATES INC. ALL RIGHTS RESERVED
NO PART OF THIS DOCUMENT MAY BE REPRODUCED, STORED IN A RETRIEVAL SYSTEM OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC, MECHANICAL, PHOTOCOPYING, RECORDING OR OTHERWISE WITHOUT THE PRIOR WRITTEN PERMISSION OF CUBELLIS ASSOCIATES INC. ANY MODIFICATIONS MADE TO THIS DOCUMENT WITHOUT THE WRITTEN PERMISSION OF CUBELLIS ASSOCIATES INC. SHALL RENDER IT INVALID AND UNUSABLE.