LEGEND

PARTION WALL

NEW MILLWORK

HARDWARE: LOCKSET

ALIGN SURFACES

FOR INFORMATIONAL PURPOSES ONLY. THE CONTRACTOR ASSUMES ALL RESPONSIBILITY NCE.

ICHES ETC. ARE PROVIDED TO OUR MATION PROVIDED BY THE CLIENT E WITH COMMON SWILDING PRACTICES IF THE EMPLOYEES OF PMC CADD DRAFTING INED ARCHITECTS, ENGINEERS OR LAND IS AND SPECIFICATIONS SHOULD BE VENIFIED ICTOR BEFORE ACTUAL CONSTRUCTION SPECIFICATIONS ARE NOT VERIFIED
ICTOR SEPORE ACTUAL CONSTRUCTION
IS SERVICES, NO. WILL SE HELD HAVELESS
ICES, INC. ASSUMES NO LIABILITY FOR CHANGES D PLANS BY CLIENT AND/OR CONTRACTOR

KEYED NOTES

- I. KITCHEN-STYLE CABINETS ABOVE & BELOW IN KITCHEN WITH COUNTER, SPLASH BOARD AND SINK
- 2. KITCHEN-STYLE CABINETS ABOVE & BELOW IN WOR/COPY AREA, WITH COUNTER TOP 25" DEEP.
 3. REFRIGATOR, GE OR EQUAL, FULL SIZE, W/ ICE-MAKER, WHITE.
- 4. COFFE MAKER, BUNN-O-MATIC OR EQUAL BY MLI.
- 5. MICROWAVE, GE OR EQUAL, CABINET HUNG, WHITE BY MLI.
- REFRIGATOR, GE OR EQUAL, SMALL SIZE, WHITE. WALL MOUNTED COUNTERTOP AT 30" AFF. PL. LAM. FINISH.
- PROVIDE ADEQUATE BLOCKING AND GABLES AS REQID. 8. RAYNOR SHUTTER WINDOW LOCATION, G.C. TO PROVIDE FINISH
- OPENING THAT SHALL 64'WX42'H AT 42' AFF. PROVIDE SOLID BLOCKING 12' WIDE BOTH SIDES, NO BLOCKING REQUIRED AT HEADER.
- 9. WALL MOUNTED COUNTER TOP AT 42' AFF. PL. LAM. FINISH. 18' DEEP. PROVIDE ADEQUATE BLOCKING AS REQ'D.
- IO. TIME CLOCK, PROVIDED AND INSTALLED BY MLI. II. LOCKERS, PROVIDED AND INSTALLED BY MLI.
- 12. PROVIDE NEW CLOSET DOORS, BI-PASS SLIDERS, AND SHELF AND ROD
- 13. 3/4" F.R. PLY SHEET (4'x8') PAINT TO MATCH WALLS FOR PHONE EQUIPMENT, FULL WIDTH OF ROOM.

GENERAL CONSTRUCTION NOTES

- 1. ROOM 101 -LOUVER IN DOOR & THERMOSTATICALLY CONTROLLED EXHAUST FAN IN CEILING, FAN SHALL BE PENN ZEPHYR, 2000 CFM OR EQUAL.
- 2. FURR-OUT AS CLOSE AS POSSIBLE TO EXISTING COLUMNS IN NON-WAREHOUSE SPACE.
- 3. REFER TO SHEET TI-Ø FOR OTHER INFORMATION.

