Boiler Replacement

SECTION 01 1000 SUMMARY

PART 1 GENERAL

1.01 PROJECT

- A. Project Name: Boiler Replacement at Washington Gardens in Portland, Maine.
- B. Owner's Name (Local Housing Authority): Portland Housing Authority.
- C. Designer's Name: Facility Strategies Group, LLC

1.02 CONTRACT DESCRIPTION

A. Contract Type: A single prime contract based on the base bid as described in Document 00 5200 - Agreement Form.

1.03 DESCRIPTION OF ALTERATIONS WORK

The scope of work includes the removal and replacement of existing boiler and domestic hot water systems at Washington Gardens (Buildings 1, 3, 4, 7, 9, 10, & Community Building). Work will include installation of new equipment pads as needed, new condensing tankless water heaters, new condensing boilers, new combustion air and flue vent piping, new boiler primary and secondary pumps, and associated valves and piping accessories. Testing and balancing will be required for all systems.

Bids must include all materials, labor, and disposal fees for equipment, pumps, piping, and peripheries that are to be installed as part of this scope of work. Piping will be required to be insulated only after inspection and acceptance of the work by Owner or Engineer. All materials and packaging shall be recycled or disposed of per the required construction waste management plan.

1.04 OWNER OCCUPANCY

- A. Portland Housing Authority intends to continue to occupy adjacent portions of the existing building during the entire construction period.
- B. Portland Housing Authority intends to occupy the Project upon Substantial Completion.
- C. Cooperate with Portland Housing Authority to minimize conflict and to facilitate Portland Housing Authority's operations.
- D. Schedule the Work to accommodate Portland Housing Authority, occupancy of the units will be through the complete job.

1.05 CONTRACTOR USE OF SITE AND PREMISES

- A. Construction Operations: Limited to Washington Gardens, Portland, ME.
- B. Arrange use of site and premises to allow:
 - 1. Portland Housing Authority occupancy.
 - 2. Use of site and premises by the public.
- C. Provide access to and from site as required by law and by Portland Housing Authority:
- Emergency Building Exits During Construction: Keep all exits required by code open during construction period; provide temporary exit signs if exit routes are temporarily altered.
- E. Existing building spaces may not be used for storage.
- F. Time Restrictions:
 - Limit conduct of especially noisy interior work to the hours of 8:00am to 5:00pm.
- G. Limit shutdown of utility services to hours at a time, arranged at least 24 hours in advance with Portland Housing Authority.
 - 1. Prevent accidental disruption of utility services to other facilities.

PROJECT SCOPE SUMMARY

N

THE PROJECT INCLUDES THE DEMOLITION OF EXISTING BOILER AND INDIRECT DHW SYSTEMS FOR 6 RESIDENTIAL BUILDINGS (1,3,4,7,9,10) AND THE COMMUNITY BUILDING AT WASHINGTON (A,600MS).

THE PROJECT INCLUDES THE INSTALLATION OF A SINGLE CONDENSING LOCKHINVAR BOILER, BOILER PRIMARY AND SECONDARY ROOM, ALSO INCLUDED IS THE INSTALLATION OF A SETBACK-CAPABLE THERMOSTAT IN THE COMMUNITY BUILDING. THE COMMUNITY BUILDING, ASSOCIATED PIPMS, EXPANSION TANK, AND CONDENSING RINGH WATER HEATER IN EACH BOILER ROOM THE COMMUNITY BUILDING, ASSOCIATED PIPMS, EXPANSION TANK, AND CONDENSING RINGH WATER HEATER IN EACH BOILER ROOM THE PROJECT INCLUDES THE REPLACEMENT OF ALT HEATING HOT WATER, AND CONDENSATE NEUTRALIZATION KIT AND DRAIN. THE THE PROJECT INCLUDES THE REPLACEMENT OF ALL HEATING HOT WATER, DOMESTIC HOT WATER, AND NATURAL GAS PIPING IN HITS PRAYING SET, INCLUDES DEMOLISHING AND REBUILDING AS NECESSARY CONDENSATE PIPMS IN BUILDINGS ALREADY RETROFITED IN THIS DRAWING SET, INCLUDING ADDING HEAT TRACE CABLE AND INSULATION WHERE NOT ALREADY PRESENT AND REROUTING DRAIN THE BIDEWALL OF THE BOILER ROOM.

DEMOLITION NOTES:

ALL EXISTING ITEMS SHOWN ON DRAWINGS ARE AS EXACT AS COULD BE SECURED. THE CONTRACTOR SHALL OBTAIN EXACT LOCATIONS, SIZES, ELEVATIONS, ETC. AT THE SITE AND SHALL SATISFACTORILY ADAPT THE NEW WORK TO THE ACTUAL CONDITIONS AS RECUIRED, THE INSTALLING CONTRACTOR SHALL DEMOLISH THE EXISTING BOILERS, WATER HEATERS, AS WELL AS ALL ASSOCIATED PIPING, FITTINGS, VALVES, HANGERS, SUPPORTS, ETC. IN A CODE APPROVED MANNER WHETHER SHOWN, OR NOT. PRIOR TO COMMENCEMENT OF WORK — THE CONTRACTOR SHALL COORDINATE THE FOLLOWING WITH THE OWNER: 0.SCHEDULE OF ALL ITEMS TO BE SALVAGED, SORTED, AND/OR REUSED.

b.SCHEDULE OF WORK TO BE DONE SO PROVISIONS CAN BE MADE TO ACCOMMODATE ANY TEMPORARY RELOCATIONS.

©. ANY AND ALL INTERRUPTIONS OF UTILITIES SHALL BE SCHEDULED AT THE OWNER'S CONVENIENCE AND WELL IN ADVANCE.

'n

4 W N -

NO CHANGES ARE TO BE MADE IN LAYOUT WITHOUT WRITTEN PERMISSION BY THE ENGINEER.
PIPE, AND FITTINGS SHALL CONFORM TO THE LATEST ANSI, ASTM, ASME, AND COMMERCIAL STANDARDS.
INDOOR DOMESTIC WATER SUPPLY PIPING SHALL BE TYPE "L" COPPER, UNLESS OTHERWISE NOTED.
GAS PIPING (AS REQUIRED) SHALL BE SCHEDULE 40 BLACK STEEL WITH CLASS 150 MALLEABLE IRON FITTINGS, UNLESS OTHERWISE

MECHANICAL NOTES

3. THE CONTRACTOR SHALL USE EXTREME CAUTION TO PROTECT EXISTING FACILITIES FROM DAMAGE. SEAL OFF AND PROTECT LINEAFFECTED AREAS OF THE EXISTING BUILDING FROM DUST. AS REQUIRED AND COORDINATE IN ADVANCE WITH THE OWNER. DO NOT ALLOW CONSTRUCTION DUST TO BE DRAWN INTO EQUIPMENT, DUCTWORK, PIPING AND OTHER SYSTEMS.

4. ANY EXISTING CONSTRUCTION OR UTILITIES THAT ARE DAMAGED BY THE CONTRACTOR OR SUBJECT.

5. WHERE EXISTING CONSTRUCTION OR UTILITIES THAT ARE DAMAGED BY THE CONTRACTOR OR SUBJECT.

6. REPLACED BY THE CONTRACTOR TO THE SATISFACTION OF THE OWNER AT NO ADDITIONAL COST. UNLESS OTHERWISE INDICATED, INSTALL NEW SUFFLOW SATE AND HYDRONIC LINES SCHEDULED TO BE DEMOLISHED. INSTALL NEW SUFFLOW SATE AND HYDRONIC PIPING IS NOT REQUIRED, REMOVE PIPING UP TO WITHIN 12" OF ACTIVE LINES.

7. DEMOLISH ALL SUPPORTS, HAVEERS, BOILERS, HYAG EQUIPMENT, PUMPS AND ASSOCIATED PIPING AND APPURTENANCES DEMOLISHED ALL SUPPORTS, HAVEERS, BOILERS, HYAG EQUIPMENT, PUMPS AND SOCIATED NITO THE NEW WORK, IN A CODE CONTRACTOR TO CORDINATE ALL DEMOLITION AND REQUIRED SHOTOWN THAT OF THE MECHANICAL AND PLUMBING SYSTEMS.

7. DEMOLISH ALL SUPPORTS, HAVEERS, MISSELLANEOUS PIPING AND EQUIPMENT NOT INCORPORATED INTO THE NEW WORK, IN A CODE CONTRACTOR TO CORDINATE ALL DEMOLITION AND NEW WORK WITH ALL OTHER DISCIPLINES AND WITH PHASING PLANS, INSTALL EFFORTS WHILE EARLIER WORK IS UNDER CONSTRUCTION.

8. DEMOLISH ALL PIPING, CONTROLS, VALVES, ETC. AS NECESSARY TO PROVIDE SERVICE TO SPACES TO BE COMPLETED UNDER LATER BEAULTHON. WHETHER SHOWN, OR NOT. LIGHT PIXTURES, OUTLIT RECEPTACLES, CONDUIT, AND OTHER ADDITIONAL COST TO THE NEW WORK AT NO THERE SHOWS, NOW METHER SHOWN, OR NOT. LIGHT PIXTURES, OUTLIT RECEPTACLES, CONDUIT, AND OTHER ADDITIONAL COST TO THE OWNER, FIELD VERIFY EXISTING DEVICE LOCATIONS.

NEW CONSTRUCTION NOTES:

GENERAL NOTES

DRAWINGS ARE SCHEMATIC IN NATURE SHOWING GENERAL ROUTING OF PIPING, IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COMPLETELY COORDINATE MECHANICAL/PLUMBING WORK WITH ALL TRADES, OFFSET REQUIRED SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE PROVIDED AT NOTATIONAL COST TO THE PROVIDED AT THE PROVIDED AT NOTATIONAL COST TO THE PROVIDED AT THE

CONTRACTOR TO PROVIDED AT NO AUDITIONAL COST TO THE OWNER.

CONTRACTOR TO PROVIDE OR MODIFY MECHANICAL CONDENSATE DRAINS) AS REQUIRED IN ALL BUILDINGS AT ASSENDED TO A CONDENSATE DRAINS TO CONTRACTOR MILL BUILDINGS PREVIOUSLY RETROPTIED. CONTRACTOR MILL BUILDINGS PREVIOUSLY RETROPTIED.

ROOM THRU SIDEWALL AS HIGH AS POSSIBLE WILL INSTALL SIDEWALL AS HIGH AS POSSIBLE WILL BUILDING OF THESE CONDENSATE DRAINS. TO CUTISDE BOILER AND THE MILL INSTALL BUILDING OF THE STALL BOILER AND THE MILL STABLISH SLOPES ON THE FIELD. ESTABLISH SLOPES AND INSTALLED IN STALLED IN SUBJUATION ON ALL CONDENSATE DRAINS.

BIEFORE INSTALLATION AND FREE FORM SCALE AND INSTALLED IN STALLED IN STALLED

Çi 4.

NOTED OTHERWISE.
CONTRACTOR STALL REVIEW ALL EXISTING CONDITIONS PRIOR
TO COMMENCING WORK. VERIEY SIZE AND LOCATION OF ALL
EXISTING PIPMO IN THE FIELD.
REFER TO ALL NOTES AND SPECIFICATIONS FOR DETAILS AND
REQUIREMENTS.

≓. ö

Ď

Ċ

AND INSTALL*

14. CONTRACTOR MUST COMPLETE WORK BEFORE SEPTEMBER

15. 2015, OR CONTRACTOR TO PROVIDE TEMPORARY
SERVICE UNTIL WORK IS COMPLETE ANY TEMPORARY
SERVICE UNITE WORK IS COMPLETE ANY TEMPORARY
SERVICE UNITE WORK IS COMPLETE. BAY TEMPORARY
SERVICE WILST RECEIVE PROOR PHA PERMISSION.

15. PROVIDE OWNER WITH ONE SET OF AS-BUILT DRAWNICS,
AND EQUIPMENT MODELS AND SERIAL NUMBERS;

UNITESS NOTED OFFICENCY.

MANUFACTURER'S OPERATION MANUFACTURER'S OPERATION MANUFACTURER'S OPERATION MANUFALS AND PARTS LISTS; EQUIPMENT WARRANTY DAITES; EQUIPMENT WARRANTY CERVIFICATES; AND SUGGESTED SERVICE PROCEDURES AND INTERVALS. INCLUDE WARRANTY SERVICE CONTACT INFORMATION, IN ADDITION TO ABOVE, PROVIDE A CD WITH ALL REQUIRED DOCUMENTS PROVIDED IN ELECTRONIC FORMAT.

ထ

CONTRACTOR TO OBTAIN ALL REQUIRED PERMITS AND LOCAL APPROVALS REQUIRED TO PERFORM WORK AND PAY ANY RELATED FEES.

ALL DOMESTIC WATER PIPING LOCATED IN EXTERIOR WALLS SHALL BE RUN ON THE ROOM SIDE OF WALL OR CELLING MISSING TO THE ROOM SIDE OF WALL OR CELLING

INSULATION,
CONTRACTOR SHALL PROVIDE NEW PIPE TO EXISTING MITHIN 5'-0" OF LOCATIONS SHOWN AT NO ADDITIONAL

COST TO OWNER.
PROVIDE ALL NECESSARY TEMPORARY OR PERMANENT CAPS OR PLUGS FOR PIPING. DO NOT LEAVE PIPING OPEN

WHERE USED, THE TERM "PROVIDE" SHALL MEAN "FURNISH AND INSTALL".

16. TRAINING OF MAINTENANCE STAFF TO BE PROVIDED BY MANUFACTURER'S REPRESENTATIVE AS PER SPECIFICATIONS.
17. START-UP TESTING TO BE BY MANUFACTURER OR QUALIFIED MANUFACTURER'S REPRESENTATIVE.
18. ALL WORK SHALL COMPLY WITH CURRENT ADOPTED STATE AND LOCAL CODES AS WELL AS LOCAL UTILITY COMPANY REQUIREMENTS AND SHALL BE ACCEPTED BY THE AUTHORITY HAVING JURISDICTION.

. OFFSETS AL COST TO

WITHEW M.

This plan and all associated notes, schedules, and specifications are the property of Fadiliy Strategies Group, LC Use of these plans other than for this specific project and location is prohibited. Unauthorized use will be subject to legal action.

FACILITY
STRATEGIES
GROUP,
1012 Market St., Suite 307
Fort Market St., Suit

ELECTRICAL NOTES

in in

1. FURNISH ALL LABOR, MATERIALS, TRANSPORTATION, AND PERFORM ALL REQUIRED OPERATIONS TO PROVIDE COMPLETE AND OPERATIONS TO PROVIDE COMPLETE AND SPECIFICATIONS.

2. ALL REQUIPMENT SHALL BE INSTALLED WITH SUFFICIENT ACCESS TO CONTROLS, FILTERS, ELECTRIC MOTORS, ETC. ACCESS CLEARANCE SHALL REQUIRED THE EQUIPMENT THANUFLYER IS GREATER.

3. THE EXISTING LECTRICAL PARIL FOR THE BOILER ROOM IS TO BE USED FOR NEW CONNECTIONS. VERIFY EXISTING CAPACITY.

4. THE EXISTING HOT WARLL PREVOVALS AND PERMITS. AND EXCESSARY TO SERVICE THE NEW BOILER(S) AND WATER HEADING. THE PERSTING HOT WATER HEADING TO BE USED FOR NEW CONNECTIONS PER CODE AND LOCAL REQUIREMENTS.

4. CECORDANCE WITH THE MANUFACTURERY REQUIRED LAW CONNECTIONS PER CODE AND LOCAL REQUIREMENTS. VERIFY OPERATION OF EXISTING GAS METER RESSURE REGULATOR. AND OTHER APPURTANCESSARY TO SERVICE THE NEW BOILER(S) AND WATER HEADING AND ATTER HEADING PRING AND ALL DOWNERS TO THE BUILDING'S GAS SERVICE.

5. INSULATE ALL EXPOSED BOILER ROOM HOT WATER PERS AND DOMESTIC HOT WATER HEATING PIPING PIPING HOR AND COMMISSIONING.)

6. INSULATE ALL EXPOSED BOILER ROOM HOT WATER AND DOMESTIC HOT WATER HEATING PIPING PIPIN ខាក់ខាខា

4.

PROVIDE ALL WORK AND MATERIALS FOR THE INSTALLATION OF COMPLETE WRING SYSTEM PER CURRENT NATIONAL ELECTRICAL CODE AND ALL LOCAL REQUIREMENTS.

CONTRACTOR TO PROVIDE ALL INCIDENTAL LITEMS REQUIRED FOR WORK (INCLUDING, BUT NOT LIMITED TO; J-BOXES, WIRE NUTS, GROUNDING SCREWS, FASTENERS, ELECTRICAL TAPE, AND CLIPS.

IN STRAIGHT LINES PARALLEL OR PERPENDICULAR TO BUILDING WALLS.

IN STRAIGHT LINES PARALLEL OR PERPENDICULAR TO BUILDING WALLS.

IN STRAIGHT LINES PARALLEL OR PERPENDICULAR TO BUILDING WALLS.

CONTROL WIRING SYDERED WIRING SHALL BE USED WHENEVER POSSIBLE. IF EXISTING WIRE WAYS/CONDUIT CANNOT BE USED, INSTALL CONDUIT.

LONTROL WIRING AND POWER WIRING SHALL BE USED WHENEVER POSSIBLE. IF EXISTING WIRE WAYS/CONDUIT CANNOT BE USED, INSTALL CONDUIT.

LUNCTION AND PULL BOXES SHALL BE CODE GALVES GALVANIZED STEEL.

ALL LINE WOLFAGE AND LOW VOLTAGE WIRE SHALL BE NISTALLED IN METAL CONDUIT.

CONNECT PURING SOILERS AND ALL PLUPS TO EXISTING CIRCUITS. ANY JUNCTION BOXES REQUIRED FOR BOILERS ARE TO BE MANUFACTURER'S RECOMMENDATIONS AND PROVIDE AS NEEDED AND PLANS MAY REQUIRE PURING FOR BOILERS. FOLLOW B. CONNECT PURING POLITIES OF EXISTING CIRCUITS ON EXISTING POWER PANEL.

IN RE-USE EXISTING BOILER EMERGENCY STOP SWITCH (VERIFY IN GOOD WORKING CONDITION OR REPLACE WITH LIKE.)

MAINTENANCE PROCEDURES.

24.42

MAINTENANCE PROCEDURES.
CONTRACTOR TO PROVIDE ACCURATE PANEL SCHEDULES AT COMPLETION OF WORK.
PROVIDE DISCONNECTING MEANS WITHIN SITE OF ALL DEVICES.

M-0. `

Project

Name: Boiler/DHW Renovation, Washington Gardens

Portland, Maine

Revisions
Rev. Deta Description
0 04/09/15 Etd set

NOTED.

NOTED.

NOTED.

NISULATE ALL DOMESTIC WATER PIPING IN UNCONDITIONE AREAS WITH FIBERGLASS INSULATION AND NON-COMBUSTIBLE UL RATED

NAPOR BARRIER OR CLOSED CELL FLEXBLE INSULATION EQUAL TO AP/ARMAFLEX PIPE. INSULATION LEVELS 1° OR PER CODE.

NISULATE ALL HEATING HOT WATER PIPING IN UNCONDITIONED AREAS WITH FIBERGLASS INSULATION AUDINON-COMBUSTIBLE UL

NAFOR BARRIER OR CELLULAR GLASS INSULATION EQUAL TO 1.5°

NISULATION THICKNESS SHALL BE:

NISULATION THICKNESS SHALL B

Sheet Name Checked by: MMP MECHANICAL & RIECTRICAL NOTES

Drawn by: PJM

Sheet Number

그 약

BOILER SCHEDULE LOCATIONS NATURAL GAS INPUT MBH TAG MANUFACTURER & MODEL NO. BOILER TYPE BOILER GPM @ 20°F/DT EFF (%) AFUE HEAD LOSS (FT.) LWT--*F Ø 0*F OAT WATER INLET (IN.) GAS INLET (IN.) VENT OUTLET VENT AMPS VOLTS/ PHASE BLDG 1,3,4,7,9, 10 & COMMUNITY B-1 CONDENSING 139 95 14.0 160 1/2 3" 3" 1.5 120/1

NOTES:

ALL DATA IS MINIMUM REQUIRED MECHANICAL LOAD PERFORMANCE
SCHEDULES BASED ON LOCHINVAR (SUPPLIED WITH 50 PSI RELIEF VALVES), SUBSTITUTIONS NOT PERMITTED
INTAKE FLUE, EXHAUST STACK, TO BE FACTORY APPROVED SCHEDULE 40 PVC COMBINED INTO SIDEWALL TERMINATION PER MANUFACTURER'S AND AHJ REQUIREMENTS. MAINTAIN
MANUFACTURER'S REQUIRED CLEARANCES OPENINGS, WALLS, GROUND AND TO ADDITIONAL FLUE TERMINATIONS.
BURNER: FORCED DRAFT WITH COMBUSTION CONTROL; SEALED COMBUSTION SYSTEM. INLET GAS PRESSURE 4.0" WC TO 14.0" WC.
GAS CONTROL SHALL BE FULL MODULATION FIRING CONDITIONS, WITH MINIMUM 5:1 TURNDOWN.

GAS CONTROL SHALL BE FULL MODULATION FIRING CONDITIONS, WITH MINIMUM 3:1 IURINDOWN.

PROVIDE GAS TRAIN AND CONTROLS TO MEET FM AND UL (PLUS XL GAP FOR BOILERS OVER 400,000 MBH) REQUIREMENTS.

PROVIDE EACH BOILER WITH CONTROLS TO MODULATE FIRING RATES.

PROVIDE CONDENSATE NEUTRALIZATION KIT BY MANUFACTURER. ROUTE CONDENSATE DRAIN AS HIGH AS POSSIBLE WHILE MAINTAINING PROPER SLOPE THRU THE SIDEWALL TO OUTSIDE THE

HEAT EXCHANGER AND INTERNAL BOILER EXHAUST PIPES SHALL BE 316L STAINLESS STEEL FOR CONDENSING APPLICATION. BOILER SYSTEM CONTROLS AND CONTROL WIRING BY CONTRACTOR.

INSTANTANEOUS GAS WATER HEATER SCHEDULE

LOCATIONS	TAG	MANUFACTURER MODEL NUMBER	TANK CAPACITY	TEMP. RISE	POWER SUPPLY	GAS		WATER C	ONNECTION			
			0/11/10/11		SUPPLI	LINE	BTUH DEMAND	CW	HW	VENT DIA.—IN.		
BLDG 1,3,4,7,9, 10& COMMUNITY	WH-1	rinnai Ru98i	TANKLESS	4.8 GPM @ 77°F RISE	120VAC/2A	3/4"	199,000	3/4"	3/4"	5		

NOTES:

IES.

ALL DATA IS MINIMUM REQUIRED PERFORMANCE.
SCHEDULES BASED ON RINNAI, SUBSTITUTIONS NOT PERMITTED.
DOE ENERGY FACTOR TO BE 0.95 OR BETTER.
INTAKE FLUE, EXHAUST STACK, TO BE FACTORY APPROVED SCHEDULE 40 PVC CONCENTRIC PER MANUFACTURER'S AND AHJ REQUIREMENTS. MAINTAIN MANUFACTURER'S REQUIRED CLEARANCES OPENINGS, WALLS, GROUND AND TO ADDITIONAL FLUE TERMINATIONS.
PROVIDE WITH MANUFACTURER'S RECOMMENDED CONDENSATE NEUTRALIZATION KIT. ROUTE CONDENSATE DRAIN LINE AS HIGH AS POSSIBLE WHILE MAINTAINING PROPER SLOPE THRU THE SIDEWALL TO OUTSIDE THE BOILER ROOM.
HEAT EXCHANGER AND INTERNAL EXHAUST PIPES SHALL BE COPPER OR STAINLESS STEEL FOR CONDENSING APPLICATION.

5.

6.

EXPANSION TANK SCHEDULE

LOCATIONS	TAG	TYPE	SERVIVCE	LOCATION	TANK VOLUME	ACCEPT. VOLUME	SIZE (II	NCHES)	MANUFACTURER/
					GALLONS	GALLONS	DIA.	LENGTH	MODEL NUMBEŘ
BLDG 1,3,4,7,9, 10 & COMMUNITY	X-1	PRESSURIZED	HEAT. HW	MECHANICAL ROOM	7.6	2.5	11	23	AMTROL/EX-60

NOTES:

ALL DATA IS MINIMUM REQUIRED PERFORMANCE.

VERIFY BOILER RELIEF PRESSURE SETTING IN CONJUNCTION WITH MANUFACTURER'S RECOMMENDATIONS FOR PRECHARGE PRESSURE REQUIREMENT.

VERIFY DOMESTIC COLD WATER LINE PRESSURE AND PRECHARGE DOMESTIC HOT WATER EXPANSION TANK TO THIS PRESSURE. SUBMIT EXPANSION TANK TO ENGINEER FOR APPROVAL. SCHEDULES BASED ON AMTROL, SUBSTITUTIONS NOT PERMITTED.

HEATING HOT WATER PLIMP SCHEDULE

THEATING HOT WATER PUMP SCHEDULE															
LOCATIONS	TAG	SERVICE TYPE			HEAD	B.H.P.	H.P.	VOLT	PH	RPM	SUCT.	DISCH.	IMP.	PUMP	MANUFACTURER/MODEL
					(F1)						(IN)	DISCH.	(in)	(%)	,
BLDG 1,3,4,7,9,	P-1	HOT WATER HEATING	IN-LINE	33	29	_	1/6	115	1	3380	1-1/2	1-1/2	_	_	GRUNDFOS UPS 26-99FC
TO & COMMUNITY	P2	HOT WATER HEATING	IN-LINE	31	31	-	1/8	115	1	3250	1-1/2	1-1/2	_	-	TACO 0011-F4

NOTES:

ALL DATA IS MINIMUM REQUIRED PERFORMANCE.
SCHEDULES BASED ON TACO AND GRUNDFOS, SUBSTITUTIONS NOT PERMITTED.
STARTERS TO BE PROVIDED WITH EQUIPMENT, DISCONNECTS BY E.C..
CONNECT TO HW HEATER CONTROLS AS DETAILED
PUMP P-1 TO BE CONTROLLED BY STARTER RELAY INTEGRAL TO BOILER.

CONTROLS POINTS LIST

LOCIVINOL	5 1 011115 E131					
LOCATIONS	RESET S	CHEDULE				
	OSA	SETPOINT				
BLDG 1,3,4,7,9,	65°F	120°F				
10 oc COMMONIT	O*F	160°F				
1107770						

NOTES

ES:

REFER TO DIVISION 23 SPECIFICATIONS FOR DETAILS.
P-1 PUMPS OPERATE INTERMITTENTLY PER BOILER FIRING, P-2 PUMPS OPERATE 24
HOURS PER DAY 7 DAYS PER WEEK.
BOILERS CYCLE TO MAINTAIN SECONDARY LOOP TEMPERATURE DURING HEATING SEASON.
BOILER TEMPERATURE SET-POINT VARIES PER BOILER RESET SCHEDULE. 1. 2.

Reyisions Descriptions or GA/09/10 Bit est or GA/	L	4. 0	UILLIN	IEM	PER	KA IL	JKE.	5E	1-1	OIL	41	VAI	(IES	PI	:K	RO	ILER I	4
		M-0.	Sheet Number	MECHANICAL SCHED	Sheet Name	-	1							0 04/09/15 Eld set	Nev. Data Description	Daticion	Pr Bo W	

CHANGCAL SCHEDULES

Boiler/DHW Renovation, Washington Gardens Portland, Maine



