



NEW ROOF BUILD-UP
 2X10 RAFTERS @ 16" O.C.
 3/4" ADVANTECH SHEATHING
 1/2" INSULATION BOARD
 E.P.D.M. ROOFING MEMBRANE

6" CCSPF IN ROOF - R42

EXISTING ROOFLINE

(2) 1-3/4" X 11-7/8" CONTINUOUS LVL HEADER

NEW EXTERIOR WALLS:
 2X6 @ 16" O.C.
 1/2" CDX PLYWOOD SHEATHING
 4" RIGID INSULATION - R20
 3/4" STRAPPING
 SIDING

NEW EXTERIOR WALLS IN SAME LOCATION AS EXISTING:

NEW FLOOR SYSTEM:
 2X10 JOISTS @ 16" O.C.
 3/4" ADVANTECH SUBFLOOR
 FINISHED FLOORING
 6" CCSPF INSULATION IN JOIST BAYS - R42

(3) 2X10 PRESSURE TREATED BEAM

6X6 PRESSURE TREATED POST
 ON GALVANIZED POST BASE

EXISTING GRADE

12" DIAMETER FOOTING

7'-8 1/2"
 MATCHES EXISTING PORCH WIDTH

1.5
 12

NEW 3/0 6/8 ENTRY DOOR
 ANDERSEN 400 SERIES

107 anderson street
 portland | maine | 04101
 t.207.775.2267
 www.portlandrenovations.com

pr
 portland
 renovations

kendall street residence
 portland, maine

TITLE
 SIDE
 ELEVATION

by RVW
 date 03.25.13
 scale 1/4"=1'-0"
 number

A3