



2014NEC

- INSULATED STAPLES REQUIRED TO SUPPORT ALL WIRING
 1275 SQ. FT. SMOKE DETECTORS REQUIRED EVERY 1200 SQ. FT.
 SMOKE DETECTORS ARE FACTORY WIRED AND FINAL LOCATION IS DETERMINED BY LOCAL FIRE MARSHALL.
- * THIS PLAN MAY HAVE ADDITIONAL APPLIANCES/FIXTURES ADDED TO THE ELECTRICAL SCHEMATIC AND/OR PANEL BOX PROVIDING THE LOADING DOESN'T EXCEED THE MAXIMUM ALLOWED BY STATE & LOCAL CODES.
 - * E-CUTOFF SWITCH ON-SITE BY OTHERS PER ALL STATE & LOCAL CODES.
 - * ALL BRANCH CIRCUITS SUPPLYING 15 & 20 AMPERE OUTLETS IN LIVING SPACES ARE PROTECTED BY AN ARC-FAULT CIRCUIT INTERRUPTER IN ACCORDANCE WITH SECTION 210.12 2014 NEC.
 - * PER 406.12 OF 2014 NEC ALL 125 -VOLT, 15 AND 20 AMP RECEPPTS INSTALLED IN AREAS SPECIFIED BY 210.52, SHALL BE LISTED TAMPER RESISTANT TYPE.
 - * 50# LIGHT BOXES REQUIRED

PFS Corporation
Northeast Region
APPROVED
H Raup - 3
2/27/15
Approval limited to
Factory Built Portion

PTL#: Kim 4355 <input checked="" type="checkbox"/> PD <input type="checkbox"/> QN <input type="checkbox"/> SN <input type="checkbox"/> SD	STATE: ME BUILDER: MTR DEV., LLC CUSTOMER/PROJECT: COPE
 Keiser Home Brand Built By Excel Homes of Maine.	
THIS DRAWING AND DESIGN IS THE PROPERTY OF EXCEL HOMES GROUP, LLC. ANY REPRODUCTION OF THE DRAWING OR DESIGN IS PROHIBITED WITHOUT THE EXPRESS WRITTEN CONSENT OF EXCEL HOMES GROUP, LLC.	
ADJUSTMENTS MADE FOR CODE COMPLIANCE AND PRODUCTION CAPABILITY DRAWING MAY BE REVERSED	
DRAWN: _____ SLP SLP	CHECKED: VMC
NO: _____ DATE: 1-22-15 PD1 1-29-15 PD2	DESCRIPTION:
FIRST FLOOR ELECTRICAL PLAN	
SCALE: NTS	SHEET: 4