



More saving.  
More doing.

Your Store:  
**South Portland #2406** [\(Change\)](#)

[Tool & Truck Rental](#) | [Installation Services and Repair](#) | [Gift Cards](#) | [Help](#)

Feather River Doors | Model # GK3190 | Internet #204487446 | Store SKU # 1000021886  
**6 Lite Craftsman Primed Smooth Fiberglass Entry Door**

★★★★☆ (4) | [Write a Review](#)

**\$229.00** / each

IN STOCK AT YOUR SELECTED STORE

**South Portland #2406**  
 South Portland, ME 04106  
[Change Pick Up Store](#)

**6 In Stock**  
 Aisle 29, Bay 003



**PRODUCT OVERVIEW** Model # GK3190 | Store SKU # 1000021886 | Store SO SKU# 806449

Feather River Doors 6 Lite External Grille Clear Glass Craftsman is a Smooth Fiberglass Door Ready to Paint any color to match your homes decor. This classic design will provide instant curb appeal to any opening and has the true Craftsman look. The rich 2-Panel design with square profile is patterned off a true wood door design to give the door the warmth and feel of wood with the long lasting benefits of fiberglass. This door is true elegance. This door has all the long lasting benefits associated with fiberglass doors, a great look, along with a load of features and benefits usually viewed as upgrades with other doors plus energy efficient and energy star qualified. Door specification: 36 in. x 80 in. prehung door, 4-9/16 in. primed jamb, left-hand inswing, fits rough opening of 38-1/4 in. x 82-1/8 in.

California residents: see [Proposition 65 information](#)

- Fiberglass construction resists denting, rusting and rotting for durability in the elements
- Polyurethane foam core provides energy-efficient insulation
- Composite adjustable threshold and compression weather strip help to prevent air and water infiltration
- Sill-to-jamb kit and bottom door rail provide resistance to exterior jamb and door rot
- Matching sill and hinge finish add a stylish accent
- 6 Lite external grille is double-pane glass is insulated and tempered for energy efficiency and security
- 2-Panel embossment with traditional-Panel design for that wood door look
- Ball-bearing hinges offer smooth operation and help to prevent door sagging and hinge wear
- Requires a 38-1/4 in. x 82-1/8 in. rough opening for a secure fit
- Energy star qualified to meet or exceed federal guidelines for energy efficiency for year-round energy and money savings
- From outside, opens toward the inside of the home with the hinges on the left
- Limited Lifetime Warranty
- Includes brick mold
- MFG Brand Name: Feather River Doors

**SPECIFICATIONS**

Assembled Depth (in.)	6.563 in	Assembled Height (in.)	82.875 in
Assembled Width (in.)	40 in	Color Family	White
Color/Finish	Smooth White: Ready to Paint	Commercial	No
Door Configuration	Single Door	Door Handing	Left-Hand/Inswing

Door Size (WxH) in.	36 x 80	Door Style	Beach Style, Carriage, Classic, Craftsman, Farmhouse, Modern
Door Thickness (in.)	1.75 in	Door Type	Exterior Prehung
Energy Star Qualified	North-Central, Northern, South-Central, Southern	Features	Brickmould, Lockset Bore, Weatherstripping
Finish Type	Unfinished	Fire rating	None
Glass Caming Finish	Patina	Glass Style	Decorative
Glass Type	Fan Lite	Hinge Finish	Patina
Included	No additional items or accessories included	Jamb Size (in.)	4-9/16"
Manufacturer Warranty	Limited Lifetime Warranty	Material	Fiberglass
Number of Hinges	3	Panel Type	2 Panel
Product Weight (lb.)	87	Rough Opening Height	82.125 in
Rough Opening Width	38.25 in		

## SHIPPING OPTIONS