1. 8' HIGH, 3/4" AC PLYWOOD BACKBOARD ALL AROUND ON 3 1/2" STANDOFFS ~ PAINT BOTH SIDES WITH (2) COATS OF BLACK FIRE RETARDANT PAINT
2. EXISTING TEMPORARY POWER AND LIGHTING SHALL REMAIN. WIRE AND CONNECT TO NEW PANELS.
3. PROVIDE CONDUIT, BOXES AND WIRING TO PANEL INDICATED FOR FUTURE LIGHTING AND DEVICES INDICATED. DEVICES AND LIGHTING SHALL BE INSTALLED AS PART OF THE FUTURE TENANT FIT-UP PROJECT.
4. (4) 4" SLEEVES FOR FUTURE TEL/DATA CABLING. MOUNT HORIZONTALLY AS HIGH TO STRUCTURE AS POSSIBLE.
5. PROVIDE JUNCTION BOX AND CIRCUIT FOR MECHANICAL CONTROLS

G9	KEY NOTES

PLAN NORTH

A1	LIGHTING PLAN ~ FIRST FLOOR
1/8" = 1'-0"	

A6	POWER AND SYSTEMS PLAN ~ FIRST FLOOR
1/8" = 1'-0"	

Reviewed for Code Compliance
Inspection Division
Date: 03/20/18

PDT ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

Allied Engineering
Structural Mechanical Electrical Commissioning
160 Veranda Street
Portland, Maine 04103
T: 207.221.2260
F: 207.221.2266
Web: www.allied-eng.com

allied Project No: 11-022
CAD File: 11022E

MARTIN'S POINT - BUILDING 4
SHELL AND CORE RETROFIT
PORTLAND, MAINE

STATE OF MAINE CATHERINE A. FAUCHER No. 7171 LICENSED PROFESSIONAL ENGINEER

PDT JOB NO.
-

DRWN. CHK.
DLL/CAF

SCALE
AS NOTED

ISSUE
MAY 1 2011
FOR CONSTRUCTION

TITLE
ELECTRICAL
FIRST FLOOR
PLANS

SHEET
E-101

C:\Users\slambert\AppData\Local\Temp\Temp2_Permit Set Dwgs.zip\11022E.dwg Sep 19, 2011 - 8:40am