ABBREVIATIONS

AB	ANCHOR BOLT
AB	AIR BARRIER
AC	AIR CONDITIONING
ADDL	ADDITIONAL
ADJ	ADJUSTABLE
ADO	AUTOMATIC DOOR OPERATOR
AFF	ABOVE FINISHED FLOOR
AH	AIR HANDLER
AIB	AIR INFILTRATION BARRIER
ALT	ALTERNATE
ALUM	ALUMINUM
AOR	AREA OF REFUGE
APPROX	APPROXIMATE
ARCH	ARCHITECT(URAL)
ARND	AROUND
AVB	AIR/VAPOR BARRIER
AWP	ACOUSTICAL WALL PANEL
BD	BOARD
BF	BARRIER FREE
BIT	BITUMINOUS
BLDG	BUILDING
BLKG	BLOCKING
BM	BENCHMARK
BOT	BOTTOM
BO	BOTTOM OF
BRK	BRICK
BRG	BEARING
B/S	BRICK SHELF
BSMT	BASEMENT
C, CRS	COURSE
CAB	CABINET
CB	CATCH BASIN
CC	CENTER TO CENTER
CF	CUBIC FOOT
CFMF	COLD FORMED METAL FRAMING
CJ	CONTROL JOINT
CL	CENTERLINE
CLG	CEILING
CLR	CLEAR
CMT	CERAMIC MOSAIC TILE
CMU	CONCRETE MASONRY UNIT
CO	CLEANOUT
COL	COLUMN
CONC	CONCRETE
CONC/C	COLORED CONCRETE
CONT	CONTINUOUS OR CONTINUE
CONTR	CONTRACTOR
CPT	CARPET
CS	COUNTERSINK
CSMT	CASEMENT
CT	CERAMIC TILE
CWT	CERAMIC WALL TILE
CUH	CABINET UNIT HEATER
CY	CUBIC YARD
DBL	DOUBLE
DC	DISPLAY CASE
DEMO	DEMOLISH, DEMOLITION
DF	DRINKING FOUNTAIN
DIA, DIAM	DIAMETER
DIM	DIMENSION
DIV	DIVISION
DMP	DEMOUNTABLE PARTITION
DN	DOWN
DR	DOOR
DTL	DETAIL
DWG	DRAWING
DWR	DRAWER
E	EAST
EA	EACH
EF	EXHAUST FAN
EMHO	ELECTRO MAGNETIC HOLD OPEN
EIFS	EXTERIOR INSULATION FINISH SYSTEM
EJ	EXPANSION JOINT
EL	ELEVATION
EP	EPOXY PAINT
ELEC	ELECTRICAL
ELEV	ELEVATOR
EMER	EMERGENCY
ENCL	ENCLOSED/ENCLOSURE
EQ	EQUAL
EQUIP	EQUIPMENT
EXH	EXHAUST
EXIST	EXISTING
EXT	EXTERIOR
EW	EYEWASH
EWC	ELECTRIC WATER COOLER
FB	FIRE BLANKET
FBO	FURNISHED BY OWNER
FCS	FLOOR COATING SYSTEM
FD	FLOOR DRAIN
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER AND CABINET
FFE	FINISHED FLOOR ELEVATION
FG	FIBERGLASS
FHVC	FIRE HOSE AND VALVE CABINET
FIN	FINISH(ED)
FIN GR	FINISH GRADE
FLR	FLOOR(ING)
FMB	FIBERGLASS MAT BOARD
FNDN	FOUNDATION
FP	FIREPROOFING
FO	FACE OF
FRMG	FRAME(ING)
FRP	FIBER REINFORCED PLASTIC
FRT	FIRE RETARDANT TREATED
FSR	FLEXIBLE SHEET ROOFING
FT	FOOT(FEET)
FTG	FOOTING
FTR	FIN TUBE RADIATION
FUR	FURRED(ING)
FV	FIELD VERIFY
FWC	FABRIC WALL COVERING
GA	GAUGE
GALV	GALVINIZED
GB	GRAB BAR
GFB	GROUND FACE CMU
GL	GLASS, GLAZING
GWB	GYPSUM WALLBOARD
HARD	HARDENER
HB	HOSE BIBB
HC	HOLLOW CORE
HD	HEAD
HDO	HIGH DENSITY OVERLAY
HDWD	HARDWOOD
HDWR	HARDWARE
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HR	HAND RAIL
HS	HIGH SCHOOL
HT	HEIGHT
HTG	HEATING
HVAC	HEATING/VENTILATION/AIR CONDITIONING
IBC	INSTALLED BY CONTRACTOR
ID	INSIDE DIAMETER
IN	INCH (ES)
INCL	INCLUDE (D), (ING)
INFO	INFORMATION
INSUL	INSULATED
INT	INTERIOR
INV	INVERT
JT	JOINT
KIT	KITCHEN
LAB	LABORATORY
LAM	LAMINATE (D)
LAV	LAVATORY
LB	POUND ($)
LCC	LEAD COATED COPPER
LF	LINEAR FOOT
LH	LEFT HAND
LOC'N	LOCATION
LW	LIGHTWEIGHT (CMU)
MAS	MASONRY
MATL	MATERIAL
MAX	MAXIMUM
MC	MEDICINE CABINET
MCWF	MULTI COLOR WALL FINISH
MDO	MEDIUM DENSITY OVERLAY
MECH	MECHANICAL
MED	MEDIUM
MF	MEMBRANE FLASHING
MFR	MANUFACTURER
MH	MANHOLE
MIN	MINIMUM
MISC	MISCELLANEOUS
MLDG	MOULDING, MOULDING
MO	MASONRY OPENING
MR	MOISTURE RESISTANT
MRGB	MOISTURE RESISTANT GYPSUM BOARD
MS	MOP SINK
MSF	METAL STUD FRAMING
MTL	METAL
N	NORTH
NA	NOT APPLICABLE
NIC	NOT IN CONTRACT
NO	NUMBER
NOM	NOMINAL
NRC	NOISE REDUCTION COEFFICIENT
NTS	NOT TO SCALE
O/	OVER
OC	ON CENTER
OD	OUTSIDE DIAMETER
OFS	OVERFLOW SCUPPER
OP	OPAQUE
OH	OVERHEAD
OPH	OPPOSITE HAND
OPNG	OPENING
OPP	OPPOSITE
OPS	OPERABLE PANEL SYSTEM
P, PTD	PAINT
PC	PRECAST CONC.
PERF	PERFORATED
PERIM	PERIMETER
PRKG	PARKING
PL	PLATE
PLAM	PLASTIC LAMINATE
PLYWD	PLYWOOD
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	PRESSURE TREATED
PTD	PAPER TOWEL DISPENSER
PTN	PARTITION
PVC	POLYVINYL CHLORIDE
PVMT	PAVEMENT
QR	QUARTER ROUND
QT	QUARRY TILE
RE:	REFERENCE
REF	REFRIGERATOR
REQ'D	REQUIRED
REV	REVISION (S), REVISED
RL	RAIN LEADER
RF	RUBBER FLOOR
RH	RIGHT HAND
RM	ROOM
RO	ROUGH OPENING
ROW	RIGHT OF WAY
S	SOUTH
SAT	SUSPENDED ACOUSTICAL TILE
SC	SOLID CORE
SCHED	SCHEDULE
SD	STORM DRAIN, SOAP DISPENSER
SECT	SECTION
SF	SQUARE FOOT
SGL	SAFETY GLASS
SH	SHOWER
SHT	SHEET
SHTHG	SHEATHING
SIM	SIMILAR
SLNT	SEALANT
SNR	SANITARY NAPKIN RECEPTOR
SP	SPECIAL PAINT
SPEC	SPECIFICATION
SPKR	SPEAKER
SQ	SQUARE
SS	STAINLESS STEEL
STC	SOUND TRANSMISSION CLASS
STD	STANDARD
STL	STEEL
STOR	STORAGE
STRL	STRUCTURAL
STRUCT	STRUCTURE/STRUCTURAL
SUPT	SUPPORT
SUSP	SUSPENDED
SV	SHEET VINYL
T	TOILET
TB	TOWEL BAR
TB	TACKBOARD
T&G	TONGUE AND GROOVE
TGL	TEMPERED GLASS
THK	THICK(NESS)
TO	TOP OF
TP	TOILET PARTITION
TPD	TOILET PAPER DISPENSER
TV	TELEVISION
TYP	TYPICAL
UCR	UNDER COUNTER REFRIGERATOR
UNO	UNLESS NOTED OTHERWISE
VB	VAPOR BARRIER/VINY BASE
VC	VALVE CABINET
VCT	VINYL COMPOSITION TILE
VERT	VERTICAL
VPW	VENEER PLYWOOD
VWC	VINYL WALL COVERING
W	WEST
W/	WITH
WC	WATER CLOSET
WD	WOOD
WGL	WIRE GLASS
WH	WATER HEATER
W/O	WITHOUT
WS	WATERSTOP
WP	WATERPROOF
WWF	WELDED WIRE FABRIC
WWM	WELDED WIRE MESH
YD	YARD
ZCC	ZINC-COATED COPPER

GENERAL NOTES:

1. ALL DIMENSIONS ARE TO FACE OF NEW STUDS OR FACE OF EXISTING WALL FINISH.
2. CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS PRIOR TO COMMENCING WORK. CONTRACTOR TO NOTIFY ARCHITECT AND OWNER IMMEDIATELY IF FIELD CONDITIONS ARE DISCOVERED TO DIFFER FROM CONDITIONS DESCRIBED IN THE CONSTRUCTION DOCUMENTS.
3. PATCH AND REPAIR ALL EXISTING CONSTRUCTION AFFECTED BY DEMOLITION OR REMOVAL OF EXISTING CONSTRUCTION.
4. SEAL AROUND ALL NEW PENETRATIONS IN NEW AND EXISTING CORRIDOR WALLS TO RESIST THE PASSAGE OF SMOKE BETWEEN CORRIDORS AND ADJACENT SPACES.
5. ALL PENETRATIONS THROUGH FIRE–RESISTANCE–RATED ASSEMBLIES SHALL BE SEALED WITH TESTED AND APPROVED FIRESTOP SYSTEMS.
6. CONTRACTOR SHALL INSTALL OWNER SUPPLIED ITEMS INCLUDING, BUT NOT LIMITED TO:
   - SOAP DISPENSERS
   - TOILET TISSUE DISPENSERS
   - PAPER TOWEL DISPENSERS
   - WINDOW SHADES
7. MAINTAIN 18" CLEAR AT PULL SIDE OF DOORS.
8. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING LOCATIONS OF POWER AND TEL/DATA WITH OWNER PRIOR TO COMMENCEMENT OF WORK.
9. INSTALL BLOCKING BEHIND ALL SURFACE APPLIED FIXTURES, TRIM, GRAB BARS, CASEWORK AND MISC. ACCESSORIES.
10. INSTALL MOISTURE RESISTANT GWB AT ALL WET LOCATIONS WITHIN 8'–0" OF ANY PLUMBING FIXTURE.

GENERAL PATCHING AND REPAIRING NOTES

1. Where new construction either infills or abuts existing construction, the finished faces shall align, and the surfaces shall be finished to match.

2. After cutting, fitting, or removal of building components, any resulting holes shall be patched. Such patches shall be flush with adjacent surfaces and finished to match.

3. Maintain fire ratings, smoke ratings, and acoustical ratings.

4. Provide metal cover plates at all abandoned electrical devices, finished to match wall.

1 TYPICAL BARRIER FREE PLANS & ELEVATIONS
1/4" = 1'–0"

PDT ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

COPYRIGHT 2018
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

MPHC - Building 4 - Contact Center

331 VERANDA STREET, PORTLAND, MAINE

REGISTERED ARCHITECT ANN M. FONTAINE-FISHER NO.1439 STATE OF MAINE

JOB NO.
17114

DRWN. CHK

SCALE:
As Noted

ISSUE
Permit Set
January 31, 2018

TITLE
Abbreviations, General Notes, Barrier Free Details

SHEET
A001

K:\MP - 17114 - VERANDAST - BUILDING 4 - CALL CENTER\17114 - WORKING FILES\CAD CDS\1-31-18 - MPHC -BLDG 4 - CALL CENTER BASE.DWG